

Nina

One of the
RSM team



A guide to accounting for debt modifications and restructurings

June 2026




A guide to accounting for debt modifications and restructurings

June 2026

TABLE OF CONTENTS

| | | |
|----------|--|----------|
| 1 | Introduction..... | 3 |
| 1.1 | Determining whether the same lender is involved before and after changes are made to the debt..... | 5 |
| 1.2 | Convertible debt..... | 6 |
| 1.3 | Effective interest method..... | 6 |
| 2 | Relevant literature and general concepts..... | 8 |
| 2.1 | Liability derecognition..... | 8 |
| 2.1.1 | Liability derecognition threshold..... | 8 |
| 2.1.2 | Continuing term loans with the same lender..... | 9 |
| 2.2 | TDR accounting..... | 9 |
| 2.2.1 | Nature, scope and unit of account..... | 9 |
| 2.2.1.1 | Unit of account when there are multiple term loans with the same lender..... | 11 |
| 2.2.2 | Determining whether a TDR exists..... | 11 |
| 2.2.2.1 | Is the borrower experiencing financial difficulties?..... | 11 |
| 2.2.2.2 | Is the lender granting a concession?..... | 13 |
| 2.2.2.3 | Overall indicators of whether a TDR exists for accounting purposes..... | 14 |
| 2.2.2.4 | Factors that should not be considered in TDR determination..... | 15 |
| 2.2.3 | Series of restructurings on same debt..... | 15 |
| 2.2.4 | TDR accounting model..... | 15 |
| 2.2.4.1 | Full settlement of debt through borrower's transfer of assets..... | 16 |
| 2.2.4.2 | Full settlement of debt through borrower's transfer of equity..... | 17 |
| 2.2.4.3 | Borrower and lender only change the debt's terms..... | 17 |
| 2.2.4.4 | Partial settlement of debt..... | 23 |
| 2.2.4.5 | Additional considerations when the lender is also an equity holder in the borrower..... | 24 |
| 2.2.5 | Direct costs incurred with third parties in a TDR..... | 24 |
| 2.2.6 | Lender fees incurred in the restructuring..... | 25 |
| 2.2.7 | Preexisting unamortized debt discount..... | 25 |
| 2.2.8 | Classification considerations..... | 25 |
| 2.2.9 | Disclosures..... | 26 |
| 2.3 | Extinguishment and modification accounting models for term loans..... | 26 |
| 2.3.1 | Scope..... | 26 |
| 2.3.1.1 | Unit of account when there are multiple term loans with the same lender..... | 27 |
| 2.3.1.2 | Unit of account for delayed-draw term loans (DDTLs)..... | 28 |
| 2.3.2 | Which model applies?..... | 28 |
| 2.3.2.1 | Prepayment options..... | 32 |
| 2.3.2.2 | Assessing multiple changes to the same debt within a one-year period..... | 33 |
| 2.3.2.3 | Treatment of a warrant or other sweetener or enhancement in the 10% cash flow test..... | 35 |
| 2.3.3 | Extinguishment accounting model..... | 35 |
| 2.3.3.1 | Considerations when debt is not accounted for at fair value..... | 36 |
| 2.3.3.2 | Considerations when debt is accounted for at fair value..... | 37 |
| 2.3.3.3 | Extinguishment accounting for a modification or exchange of loans..... | 37 |
| 2.3.4 | Modification accounting model..... | 38 |
| 2.3.5 | Accounting for fees and costs incurred..... | 38 |
| 2.3.5.1 | Borrower pays lender's third-party service providers..... | 40 |
| 2.3.5.2 | Fees and costs incurred in changing loans in a loan syndication..... | 40 |
| 2.3.6 | Fees between borrower and lender trigger accounting assessment..... | 41 |



- 2.3.6.1 Commitment fees on delayed-draw term loans 41
- 2.3.7 Loan participations and syndications 41
- 2.3.8 Third-party intermediaries 42
- 2.3.9 Transactions between lenders 43
- 2.4 Modification of a line-of-credit arrangement 43**
- 2.4.1 Modifications of undrawn delayed-draw term loan commitments 44
- 2.5 Changing from term loan to line-of-credit and vice versa 44**
- 2.6 Debt disclosures 45**
- 3 Examples 46**
- Appendix A: Acronyms, literature and technical accounting guide and whitepaper references 89**
- Appendix B: Definitions 91**
- Appendix C: Summary of significant changes since last edition 94**



1 Introduction

Borrowers may seek to renegotiate the terms of existing loans because they are not able to meet current loan covenants or cash flow requirements under their loans, or because they want to increase the amount borrowed or obtain lower interest rates. Lenders may be willing to renegotiate the terms of existing loans because they realize that it may be in their best interests to reconsider the terms of a loan instead of: (a) losing the borrower to a competitor that is willing to provide a reduced interest rate because of an improvement in the borrower's credit quality or a reduction in market interest rates, (b) forcing the borrower to find another lender or file for bankruptcy or (c) foreclosing on any collateralized assets. As a result of the renegotiations, the borrower and lender may agree to modify or restructure an existing loan or exchange one loan for another. The degree of change introduced by the modification, restructuring or exchange (collectively referred to as changes) depends on any number of factors, first and foremost being the financial condition and prospects of the borrower.

Naturally, there are accounting implications when the borrower and lender agree to modify or restructure an existing loan or exchange one loan for another. The accounting implications differ depending on whether the borrower's or lender's accounting is being considered. This guide deals solely with the borrower's accounting for changes made to its loans. Depending on the facts and circumstances, different accounting outcomes could result for the borrower. For example, the borrower may be required to recognize a gain or loss in the period of the changes, or the borrower may be required to recognize the effects of the changes in future periods through an adjustment to the effective interest rate. A thorough analysis of the borrower's facts and circumstances and the relevant authoritative accounting literature is required to ultimately determine how the borrower should account for changes to its loans. In some circumstances, a significant amount of professional judgment must be exercised in making this determination.


To identify the appropriate accounting model to apply to changes to a loan, the borrower must first determine whether it has met the threshold to remove a liability from its balance sheet (i.e., derecognize the liability and apply the extinguishment accounting model). Typically, this liability derecognition threshold is met when the changes involve an old loan being repaid with proceeds from a new loan with a new lender (i.e., an unrelated party that was not considered a lender with respect to the old loan), provided there is no continuing debt with the old lender. In contrast, this threshold is not met just because the borrower and the same lender exchange cash to satisfy an existing loan and issue a new loan. For additional information about determining whether the same lender is involved in the loan before and after changes are made, see [Section 1.1](#). For additional information about determining whether the liability derecognition threshold has been met, see [Section 2.1](#).

If the liability derecognition threshold has not been met, then the borrower must determine whether it should apply the accounting model for a troubled debt restructuring (TDR), which is discussed in detail in [Section 2.2](#). In some cases, a TDR results from the full settlement of debt through the transfer of cash, noncash assets or equity (i.e., the debt is derecognized in the TDR). While the net effect on the income statement is the same regardless of whether the extinguishment or TDR accounting model is applied in these cases, there are additional accounting and disclosure requirements for a TDR. As such, consideration should be given to whether the derecognition of debt meets the conditions present in a TDR.

If the liability derecognition threshold has not been met and the TDR accounting model does not apply, then for term loans the borrower must determine whether it should apply the accounting model for a debt modification or extinguishment, discussed in detail in [Section 2.3](#). The accounting for changes to a line-of-credit arrangement (which also encompasses a revolving debt or revolver arrangement when used throughout this guide) that is not a TDR is discussed in detail in [Section 2.4](#). Changes to a delayed-draw term loan (DDTL) that is not a TDR will either be accounted for under the term loan or the line-of-credit accounting model as discussed in detail in [Section 2.3.1.2](#).



The following flowchart illustrates these considerations and the order in which they should occur.



Note 1: Many of the terms used in this flowchart (e.g., financial difficulties, concessions, substantially different) have specific meanings and related implementation guidance. This guide explains and illustrates those meanings and guidance.

Note 2: As noted earlier in this section, changes to a DDTL that is not a TDR will either be accounted for under the term loan or the line-of-credit accounting model.



The conclusions reached by a borrower in determining the appropriate accounting for changes made to a loan could significantly affect its financial statements. Depending on the facts and circumstances, one or more of the following may be required of the borrower:

- Adjust the carrying amount of the loan
- Derecognize the loan and recognize a new loan
- Change the amount of interest expense recognized in the income statement on a going-forward basis or recognize a gain or loss in the income statement in the period the changes were made to the loan
- Expense some of the costs incurred to execute the changes and (or) defer and amortize other costs

The borrower must also consider classification questions related to the old loan and the new or changed loan. Classification of debt is discussed in detail in [our debt classification whitepaper](#).

As mentioned earlier, this guide deals solely with the borrower's accounting for changes to its loans. Guidance applicable to the lender, which differs, is discussed in Section 5.5 of [our financial assets guide](#).

The relevant accounting literature on accounting for the changes made to loans by the borrower (including term loans and line-of-credit arrangements) is primarily included in the following sections of the Financial Accounting Standards Board's (FASB) Accounting Standards Codification (ASC):

- ASC 405-20, Liabilities – Extinguishments of Liabilities
- ASC 470-50, Debt – Modifications and Extinguishments
- ASC 470-60, Debt – Troubled Debt Restructurings by Debtors

The remainder of this chapter discusses pervasive issues relevant to the accounting for changes a borrower makes to its debt. The relevant guidance in ASC 405-20, 470-50 and 470-60 is explained in [Chapter 2, Relevant literature and general concepts](#). Several detailed examples of how to apply this guidance are included in [Chapter 3, Examples](#).

1.1 Determining whether the same lender is involved before and after changes are made to the debt

The two key parties to a loan are the borrower and its lender. Reading and understanding the terms of the agreements that underlie a loan and any related changes to the loan should clearly identify these and other relevant parties. Identifying the relevant parties factors into determining the accounting model that should be applied in a particular situation. For example, if an old term loan is repaid with proceeds from a new term loan with a new lender (i.e., an unrelated party that was not considered a lender with respect to the old loan), then there are two separate accounting events for the borrower (provided there are no other term loans with the old lender):

1. derecognition of the old term loan (which would be accounted for as an extinguishment) and
2. entering into the new term loan with a new lender (which would be accounted for as any other issuance of new debt).

On the other hand, if the old term loan is repaid with proceeds from a new term loan that is with the same lender, then consideration must be given to whether the borrower should account for the exchange of the term loans using the TDR, modification or extinguishment accounting model. (Further discussion of identifying the unit of account in a TDR or modification or extinguishment is included in [Section 2.2.1.1](#) and [Section 2.3.1.1](#).) If the loan in this example was a line-of-credit, and the old line-of-credit was repaid with the proceeds from a new line-of-credit with the same lender, then consideration must be given to whether the borrower should account for the exchange of the lines-of-credit using the TDR or borrowing capacity accounting model.

Typically, determining whether the same lender is involved in a loan before and after any changes are made to the loan is a straightforward exercise involving looking at the name of the lender and seeing that



the name of the lender is the same before and after the changes. However, in other cases, it may not be as straightforward. For example, if an affiliate of the old lender is the new lender, or if the old lender and new lender are two subsidiaries or two divisions within the same consolidated entity, making the determination as to whether the same lender is involved in a loan before and after any changes are made to it requires additional analysis. To determine whether the same lender is involved in a loan before and after any changes are made to the loan in these less-than-straightforward situations, such as when there are multiple funds in a private equity group acting as lenders, requires careful consideration of the relevant facts and circumstances, including but not limited to addressing the following questions:

- Are the new and old lenders separate legal entities?
- Are the new and old lenders not included in the same consolidated entity?
- Are management of the new and old lenders responsible as fiduciaries to manage the lenders solely for the benefit of the owners and equity holders of each individual lender?

If the answer to each of these questions is yes, there are indications that the old and new lenders operated separately and should not be considered the same lender for accounting purposes.

Alternatively, when the new and old lenders are part of the same consolidated group and use the same representative to negotiate the debt modification with the borrower, there are indications that the old and new lenders operated together and should be considered the same lender for accounting purposes.

Additional information about identifying the lender(s) in loan participations and loan syndications, as well as identifying the roles of the parties involved, including third-party intermediaries, is provided in [Section 2.3.7](#) and [Section 2.3.8](#), respectively.

1.2 Convertible debt

This guide covers the guidance in ASC 470-50 related to the modification or exchange of debt with an embedded conversion option. Chapter 3 of [our debt and equity guide](#) address the following related to convertible debt:

- Conversions in accordance with the terms of the debt
- Induced conversions



Spotlight on change:

In November 2024, the FASB issued Accounting Standards Update (ASU) 2024-04, *Debt—Debt with Conversion and Other Options (Subtopic 470-20): Induced Conversions of Convertible Debt Instruments*. ASU 2024-04 clarifies the requirements for determining whether certain settlements of convertible debt instruments should be accounted for as an induced conversion. ASU 2024-04 is effective for all entities for annual reporting periods beginning after December 15, 2025, and interim reporting periods within those annual reporting periods. Early adoption is permitted, provided the entity has adopted ASU 2020-06, *Debt – Debt with Conversion and Other Options (Subtopic 470-20) and Derivatives and Hedging – Contracts in Entity’s Own Equity (Subtopic 815-40): Accounting for Convertible Instruments and Contracts in an Entity’s Own Equity*. Section 3.5.3.1 of [our debt and equity guide](#) address the requirements of ASU 2024-04.

1.3 Effective interest method

Relevant guidance: ASC 835-30-35-1 through 35-4

U.S. Generally Accepted Accounting Principles (U.S. GAAP) requires interest expense on debt to be recognized using the effective interest method. Under this method, any debt discount (which includes lender fees and third-party costs related to the original issuance of the debt) is amortized into interest expense using a constant interest rate over the life of the debt, which is known as the effective interest




method. U.S. GAAP permits the use of other methods of amortization if the results are not materially different than those resulting from the effective interest method.

In practice, some borrowers amortize the debt discount on a straight-line basis, which is only appropriate if doing so generates results that are not materially different from the results using the effective interest method. For purposes of the discussion in this guide, it is assumed that the borrower is recognizing interest expense using the effective interest method and that the carrying amount of the debt reflects use of that method to amortize the debt discount.



2 Relevant literature and general concepts

2.1 Liability derecognition



2.1.1 Liability derecognition threshold

Relevant guidance: ASC 405-20-40-1 through 40-2 and ASC 470-50-15-4

Extinguishment is the derecognition of a liability. Derecognizing a liability simply means to take the liability off, or remove the liability from, the borrower's balance sheet. The liability derecognition threshold is met only if:

1. The borrower pays the lender and is relieved of its obligation, or
2. The borrower is legally released as the primary obligor.

Payment to a lender may occur upon the delivery of cash, other financial assets, or goods or services. Payment may also occur if the borrower reacquires its outstanding debt securities and cancels them or holds them as treasury bonds. Legal release as the primary obligor may be granted by the lender or may occur judicially. If the liability derecognition threshold has been met, then the borrower should apply the extinguishment accounting model (see [Section 2.3.3](#)). Refer to the commentary later in this section for discussion about considering whether the extinguishment resulted from a TDR.

Questions arise regarding whether the following circumstances constitute an extinguishment: (a) the borrower is legally released by the lender as the primary obligor, (b) a third party agrees to assume the obligation and (c) the borrower agrees to become secondarily liable for the obligation. While the occurrence of all these circumstances extinguishes the borrower's original obligation, it also creates a new obligation. This new obligation is a guarantee and must be accounted for as such (i.e., initially recognized and measured at fair value in accordance with ASC 460-10-30-2).

Commentary: As discussed further in [Section 2.2.4](#) some TDRs may result in debt being fully settled either through the transfer of cash, noncash assets, equity or a combination thereof. For these TDRs, the liability derecognition threshold has been met. While the net effect on the income statement is the same regardless of whether the extinguishment accounting model or TDR accounting model is applied in these situations, there are additional accounting (related to settlement of the debt by transferring noncash assets or equity [see [Section 2.2.4.1](#) and [Section 2.2.4.2](#), respectively]) and disclosure requirements for a TDR. As such, when the changes to debt meet the liability derecognition threshold, consideration should also be given to whether those changes meet the definition of a TDR.

If the borrower and lender agree to change the terms of debt to allow the borrower to settle the debt by transferring equity-linked instruments to the lender, the borrower must determine whether those instruments should be classified as equity or a liability for accounting purposes (see our [debt and equity guide](#)). When the equity-linked instruments should be classified as equity, the discussion in the preceding paragraph applies. However, when the equity-linked instruments should be classified as a liability, the borrower has exchanged debt for a different liability with the same lender and additional considerations apply (see [Section 2.1.2](#)).


See [Example 3-1](#) for application of this guidance.

2.1.2 Continuing term loans with the same lender

There may be continuing term loans with the same lender either because the old loan was modified or exchanged with the same lender, or because there are other term loans with the same lender. (See [Section 1.1](#) for discussion regarding whether two lenders should be considered the same lender for accounting purposes.) When there are continuing term loans with the same lender, the borrower has *not* met the substance of the liability derecognition threshold and should next consider whether the changes made to the borrower's loans should be accounted for as a TDR. In other words, the mere fact that the borrower and lender concurrently exchange cash to satisfy an existing term loan (cash from borrower to lender) and issue a new term loan (cash from the same lender to borrower) should not lead the borrower to automatically conclude that the liability derecognition threshold has been met and the extinguishment accounting model should be applied. The borrower may need to account for this exchange of cash and term loans using the TDR accounting model for situations in which there has been a change to the loan's terms (with or without partial settlement of that debt) or the modification accounting model instead of the extinguishment accounting model. In addition, when the borrower has more than one term loan with the same lender and settles one or more (but less than all) of those term loans, the borrower may not have met the substance of the liability derecognition threshold (see [Section 2.2.1.1](#)).

Further, when a borrower has a term loan with multiple lenders (e.g., a syndicated loan), the borrower could meet the threshold for liability derecognition with a lender leaving the syndicate but not with the remaining lenders (see [Section 2.3.7](#)).

2.2 TDR accounting



2.2.1 Nature, scope and unit of account

Relevant guidance: ASC 470-60-10-1 through 10-2, ASC 470-60-15-4 through 15-7, ASC 470-60-15-9 through 15-11 and ASC 470-60-55-1 through 55-3

As noted in [Appendix B](#), the Master Glossary of the Codification defines a TDR as follows: “A restructuring of a debt constitutes a troubled debt restructuring if the creditor for economic or legal reasons related to the debtor’s financial difficulties grants a concession to the debtor that it would not otherwise consider.” The concession granted by the lender will affect both the borrower’s and lender’s cash flows related to the debt. The cash flows may be affected by changing: (a) the amount or timing of cash flows paid by the borrower, (b) how much of the cash flows will be designated as interest and (c) how much of the cash flows will be designated as principal, which will affect the lender’s total return and its effective interest rate as well as the borrower’s total cost and effective interest rate.

A TDR may involve debt, bonds, notes or accounts payable relating to purchasing goods or services on credit. It is not limited solely to loans or debt.

For liabilities other than bonds payable, the evaluation of whether a TDR has occurred should take place on a lender-by-lender basis, even in cases where the restructuring of a group of similar liabilities is negotiated at the same time across a number of lenders (see [Section 2.2.1.1](#) regarding situations in

which there are multiple term loans with the same lender). For bonds payable that are part of a TDR, the bond constitutes one payable (and unit of account) even though there are many bondholders.

A lender's incentive in agreeing to a TDR rests on the theory that it is better to get something instead of nothing. In other words, if the only way a lender will receive any payments from a borrower is if they agree to a concession, then they may be incented to agree to the TDR in order to collect at least some of the amount owed to them. Of course, the lender is only motivated to grant a concession that protects as much of its investment as possible. Any of the following could take place in a TDR:

- The lender agrees to settle the debt for less cash than the outstanding balance of the debt.
- The lender agrees to settle the debt by accepting assets (other than cash) whose fair value is less than the carrying amount of the debt. The assets could be accounts receivable from routine sales made by the borrower, real estate or other assets. These assets may come to the lender as a result of foreclosure, repossession or other transfers.
- The lender agrees to settle the debt by accepting a grant of equity securities issued by the borrower, provided the grant is not occurring in accordance with preexisting terms that would have permitted conversion of the debt to an equity interest.
- The borrower and lender agree to modify the terms of the debt and not transfer any assets or equity. The cash requirements under the debt may be reduced as a result of one or more of the following types of changes: (a) a reduction in the stated interest rate on the debt, (b) an extension of the maturity dates when the stated interest rate is lower than the market rate for comparable new debt, (c) a reduction in the face amount of the debt or, (d) a reduction in accrued interest owed on the debt.
- The borrower and lender agree to extend the maturity date of the debt and defer required interest payments until that date.
- The borrower and lender agree to: (a) the partial settlement of the debt through the transfer of noncash assets or equity and (b) the modification of terms for the debt that remains.

The borrower and lender may initiate the discussions that lead to a TDR, or those discussions may be forced by law or by a court. As such, a TDR may exist for accounting purposes if it was carried out under various provisions of the Federal Bankruptcy Act (e.g., reorganization) or other related federal statutes. When the borrower in a TDR is undergoing bankruptcy proceedings, a quasi-reorganization or corporate readjustment at the same time as the TDR, it is important to understand whether such activities will result in a general restatement of the borrower's liabilities. If so, a TDR does not exist for accounting purposes. [Our bankruptcy whitepaper](#) includes an overview of bankruptcy proceedings under Chapter 11, and guidance and examples related to financial reporting while in Chapter 11 bankruptcy and fresh start accounting upon emergence from bankruptcy.

The following situations are not in the scope of the TDR guidance:

- Lease modifications under ASC 842. Refer to [our lease accounting guide](#) for information about the accounting for lease modifications.
- Changes in employment-related agreements (e.g., pension plans, deferred compensation contracts)
- Failure by the borrower to pay its trade accounts according to their terms without reaching an agreement with its creditors to change the terms
- Deferral of legal action by the lender to collect past due amounts of interest and principal from the borrower without reaching an agreement with the borrower
- Application of bankruptcy accounting by the borrower and a general restatement of its liabilities (see [our bankruptcy whitepaper](#))



2.2.1.1 Unit of account when there are multiple term loans with the same lender

When there are multiple term loans with the same lender (see [Section 1.1](#)) and changes are made to one or more of those loans, we believe the changes should be evaluated for TDR purposes as if they were a single term loan with the lender. Not taking this approach could result in the borrower accounting for changes to one term loan as a TDR (and potentially recognizing a gain) when such changes might not be considered a TDR (or not result in gain recognition under the TDR accounting model) if those changes were evaluated in the context of all the term loans with that specific lender.

2.2.2 Determining whether a TDR exists

Relevant guidance: ASC 470-60-15-13 and ASC 470-60-55-4 through 55-5

Determining whether the accounting for a TDR applies in a particular situation is a matter of professional judgment. An analysis of all the facts and circumstances must be performed and no one fact or circumstance should itself be considered determinative in the face of a preponderance of contrary evidence. The accounting literature provides guidelines that should be used in this analysis. These guidelines focus on the definition of a TDR (see [Section 2.2.1](#)). Based on that definition, the following two questions must be answered to determine whether the accounting model for a TDR applies in a particular situation:

1. Is the borrower experiencing financial difficulties? (see [Section 2.2.2.1](#))
2. Is the lender granting a concession? (see [Section 2.2.2.2](#))


If the answer to both questions is yes, then the changes to the debt should be accounted for as a TDR. If the answer to either of these questions is no, then the changes to the debt should not be treated as a TDR for accounting purposes. In the latter situation, the borrower must determine whether the modification or extinguishment accounting model is appropriate (see [Section 2.3](#)).

For efficiency, the borrower should initially address the question that is easiest to answer, since a “no” response to either question results in the changes to the debt not being treated as a TDR by the borrower for accounting purposes. We believe that for most borrowers, the question of whether the borrower is experiencing financial difficulties is easiest to answer and should be answered first. Thus, a borrower’s conclusion that they are not experiencing financial difficulties would obviate the need to determine whether the lender is granting a concession.

2.2.2.1 Is the borrower experiencing financial difficulties?

Relevant guidance: ASC 470-60-15-8, ASC 470-60-55-4 and ASC 470-60-55-7 through 55-8

The following flowchart captures how a borrower should assess whether it is experiencing financial difficulties as that term is used in ASC 470-60:



The top two questions in the flowchart are focused on *why* the debt was changed. So, if the debt was changed just to reflect decreases in current market interest rates at which the borrower could obtain funds or improvements in the borrower's creditworthiness since the original issuance of the debt, and the borrower has been servicing the debt and can obtain debt from other lenders at market rates offered on comparable debt to nontroubled borrowers, there is determinative evidence that the changes to the debt were not made because the borrower was experiencing financial difficulties. When these are not the reasons the debt was changed, further analysis is required to determine whether the borrower is experiencing financial difficulties. This further analysis involves the borrower determining whether there has been a deterioration in its creditworthiness since it originally issued the debt. For purposes of assessing whether the borrower's creditworthiness has deteriorated:

- If the borrower's credit rating changes but remains an investment-grade credit rating (e.g., Standard & Poor's credit rating on the borrower drops from an A to a BBB), then its creditworthiness has not deteriorated.
- If the borrower's credit rating declines from investment grade to noninvestment grade (e.g., Standard & Poor's credit rating on the borrower drops from a BBB to a BB), then its creditworthiness has deteriorated.

In many cases, a borrower's creditworthiness has not been evaluated by a nationally recognized rating agency. This is particularly true of many privately held companies. Assessing whether a borrower's creditworthiness has deteriorated in these cases requires the consideration of other factors in the context of the borrower's specific facts and circumstances. Examples of other questions that should be considered in determining whether the borrower's creditworthiness has deteriorated when the borrower's credit has not been evaluated by a nationally recognized rating agency include the following:

- If the borrower's debt is collateralized, has there been a significant decrease in the value of that collateral?
- If the borrower has a guarantee issued by a related party or third party (or other credit enhancement) on its debt, has there been a significant decrease in the value of that guarantee or other credit enhancement? For example, if the borrower has a guarantee on its debt from a third party, has there been a decline in the financial standing of the third party that has led to a significant decrease in the value of the guarantee?
- Is the borrower part of an industry whose sector risk has deteriorated?
- Is the borrower unable to obtain new debt at reasonable terms?
- Is the borrower unable to meet the debt covenants in its existing loan agreements?
- Is the borrower experiencing liquidity issues? For example, has its working capital ratio worsened?
- Has there been a general decline in the borrower's financial performance? For example, has the borrower recently experienced recurring net losses?

Answering yes to any of these questions is an indicator that the borrower's creditworthiness has deteriorated. The final assessment as to whether the borrower's creditworthiness has deteriorated should take into consideration the responses to all of these questions, as well as other relevant facts and circumstances specific to the borrower.

If the borrower's creditworthiness has not deteriorated, then the borrower is not experiencing financial difficulties. Conversely, if the borrower's creditworthiness has deteriorated, then additional factors must be considered. Answering yes to any of the following questions is an indicator that the borrower is experiencing financial difficulties:

- Is the borrower currently in default on any of its debt?
- Has the borrower declared bankruptcy or is the borrower in the process of declaring bankruptcy?
- Is there doubt about the borrower's ability to continue as a going concern?



- Have any of the borrower's securities been delisted from an exchange?
- Are any of the borrower's securities in the process of being delisted from an exchange?
- Does the threat exist for any of the borrower's securities to be delisted from an exchange?
- Are the borrower's projected cash flows (based on current business capabilities) insufficient to cover payments required on the debt through maturity?
- Is the borrower unable to obtain debt from other lenders in which the effective interest rate charged by the lender is equal to the current market interest rate charged on comparable debt issued to a nontroubled borrower?

The final assessment as to whether the borrower is experiencing financial difficulties should take into consideration the responses to all of these questions, as well as other relevant facts and circumstances specific to the borrower. Refer also to [Section 2.2.2.3](#), which discusses the significance of certain factors to the overall analysis as to whether a TDR exists.

From a practical perspective, when a borrower's debt is not formally rated by a nationally recognized rating agency and there is not determinative evidence that the borrower is not experiencing financial difficulties, the borrower may perform the qualitative analyses related to whether there has been a deterioration in the borrower's creditworthiness and whether the borrower is experiencing financial difficulties at the same time given the interrelated nature of the analyses. Refer also to [Section 2.2.2.3](#), which discusses the significance of certain factors to the overall analysis as to whether a TDR exists.

2.2.2.2 Is the lender granting a concession?

Relevant guidance: ASC 470-60-55-10 through 55-13


A concession has been granted by the lender if the debt's effective (not stated) interest rate after changes are made to it is less than the debt's effective (not stated) interest rate prior to those changes being made.



However, there may be rare situations in which a decrease in the effective interest rate is attributable to a factor not reflected in the mathematical calculation of the effective interest rate. Adding more collateral to the debt may give rise to this situation. Provided there is persuasive evidence in support of these rare situations, a concession may not have occurred even though there has been a decrease in the borrower's effective interest rate. The accounting in such a situation should reflect the substance of the changes made to the debt.

The effective interest rate after changes are made to the debt should give effect to all of the terms of the changed debt, which should include any new or revised options, warrants, guarantees and letters of credit. The following steps should be taken when calculating the effective interest rate after the changes are made to the debt:

- Project all cash flows required under the changed debt
- Solve for the discount rate that makes the present value of the projected cash flows equal to the carrying amount of the borrower's debt before it was changed



Reflected in the carrying amount of the borrower's debt should be any unamortized premium, discount or issuance costs, and any accrued interest payable. However, hedging effects related to the debt should not be included in its carrying amount. For example, the borrower may have previously elected fair-value hedge accounting for an interest rate derivative (such as an interest rate swap) related to the debt. Adjustments to the carrying amount of the debt to record changes in fair value associated with the hedging relationship should be excluded from the carrying amount of the debt when calculating the changed debt's effective interest rate.

Reflected in the projected cash flows required under the changed debt should be any future principal and interest payments, as well as any fees paid or payable by the borrower to the lender. In addition, the projected cash flows required under the changed debt should include the effects of any new or revised enhancements (i.e., sweeteners) included in the debt. Examples of sweeteners include options, warrants, guarantees and letters of credit. One way in which adding a sweetener would directly affect cash flows is if the borrower added a new financially-sound guarantor to the debt, and as a result, the lender agreed to reduce the interest rate charged on the debt. Adding, deleting or changing a sweetener may not always have a direct effect on cash flows. Nonetheless, the FASB believes that adding, deleting or changing a sweetener should be taken into consideration when determining whether the lender has granted a concession. As such, the day-one projected cash flows required under the changed debt for purposes of determining whether a concession has been granted should include a new sweetener's fair value or the change in a revised sweetener's fair value, along with any future principal and interest payments and any fees paid or payable by the borrower to the lender. The length of time until a sweetener becomes exercisable should be taken into consideration in estimating its fair value on the date the restructuring occurs.

2.2.2.3 Overall indicators of whether a TDR exists for accounting purposes

Relevant guidance: ASC 470-60-15-8, ASC 470-60-15-12, ASC 470-60-55-4 and ASC 470-60-55-9

Overall indicators that a TDR does not exist for accounting purposes include the following:

- Other lenders are willing to loan the borrower funds at market interest rates at or near the interest rates available for debt that is not troubled.
- The fair value of the assets (including cash) or equity interest either:
 - Accepted by the lender in full satisfaction of its receivable is equal to or more than the lender's amortized cost basis in the receivable
 - Transferred by the borrower in full satisfaction of its debt is equal to or more than the carrying amount of the borrower's debt.
- To maintain its relationship with the borrower, the lender agrees to reduce the effective interest rate on the debt solely because the borrower could go elsewhere to obtain funds at a current market interest rate that is less than the effective interest rate on the debt (such decrease in the current market interest rate could be due to the occurrence of a general decrease in market interest rates or a decrease in the risk being taken on by the lender with respect to the borrower).
- The new marketable debt issued by the borrower in exchange for its old debt has an effective interest rate that is at or near current market interest rates on comparable debt issued by nontroubled borrowers.

To the extent any of these indicators exist, we believe it would take a preponderance of evidence to the contrary to conclude that a TDR does, in fact, exist for accounting purposes.

An overall indicator that a TDR exists for accounting purposes is if other lenders are only willing to loan the borrower funds at effective interest rates that are so high that the borrower would not be able to make all the required payments under the debt. To the extent this indicator exists, we believe it would take a preponderance of evidence to the contrary to conclude that a TDR does not, in fact, exist for accounting purposes.

2.2.2.4 Factors that should not be considered in TDR determination

Relevant guidance: ASC 470-60-55-6

Factors that should not enter into the determination as to whether a TDR exists for accounting purposes include:

- How much do the current lenders have invested in the debt before the restructuring?
- What is the fair value of the debt immediately before and after the changes are made?
- What transactions have occurred among the lenders affected by the changes?

In general, how long the current lenders have held their investment in the debt should also not enter into the determination as to whether a TDR exists for accounting purposes. However, a TDR could exist for accounting purposes if the lenders recently came to their current position through what was, in substance, a planned refinancing.

2.2.3 Series of restructurings on same debt

Relevant guidance: ASC 470-60-55-14

Changes to debt that occur in the same recent time frame should be evaluated on a cumulative basis to determine whether a TDR occurred. Although GAAP does not define what is considered recent for purposes of determining whether a TDR has occurred, we generally believe a one-year period should be considered recent, which is the same period prescribed in GAAP for modifications and exchanges that are not TDRs (see [Section 2.3.2.2](#)).

For purposes of determining whether the lender granted a concession in these situations, the borrower should solve for the discount rate that makes the present value of the projected cash flows (including those required as a result of the most recently changed debt) equal to the carrying amount of the borrower's debt before the first changes were made to the debt in the recent time frame. The borrower should compare this effective interest rate to the effective interest rate prior to the first changes made to the debt in the recent timeframe to determine whether the lender granted a concession. Analyzing the changes to the debt on a cumulative basis prevents the borrower from reaching a different accounting conclusion by executing the changes in stages.

2.2.4 TDR accounting model

Relevant guidance: ASC 360-10-35, ASC 470-60-35-1 through 35-2, ASC 470-60-35-4 through 35-5 and ASC 470-60-35-8 through 35-9

How a borrower accounts for a TDR depends on whether the borrower: (a) transfers assets in the TDR, (b) transfers equity in the TDR or (c) modifies the terms of the debt (e.g., the borrower and lender agree to modify the cash requirements under the debt on a going-forward basis). The remaining discussion in this section focuses on the accounting when:

- Full settlement of the debt occurs through the borrower's transfer of assets (which would include a repossession or foreclosure by the lender [see commentary later in this section for discussion of the timing related to the accounting for a TDR and the timing related to recognizing an impairment (if necessary) on the asset being foreclosed upon]) (see [Section 2.2.4.1](#))
- Full settlement of the debt occurs through the borrower's transfer of equity (see [Section 2.2.4.2](#))



- Modification of the debt's terms occurs with no assets or equity transferred in settlement (see [Section 2.2.4.3](#))
- Partial settlement of the debt occurs through the borrower's transfer of assets or equity or modification of terms (see [Section 2.2.4.4](#))

For purposes of this discussion, the carrying amount of the borrower's debt includes any unamortized premium, discount, or issuance costs and any accrued interest payable.

Commentary: Foreclosure by the lender may result in full or partial settlement of debt through the transfer of assets (see [Section 2.2.4.1](#) and [Section 2.2.4.4](#)). While the accounting for debt fully or partially settled through foreclosure does not take place until the foreclosure occurs, the borrower may be required to recognize an impairment loss on the asset group that includes the asset subject to foreclosure prior to the foreclosure occurring. Consider a situation in which an impairment loss should be recognized in 20X1 on an asset group that includes an asset about to be foreclosed upon, but the foreclosure and recognition of the related gain on restructuring is not expected to occur until 20X2. A question arises in this situation about whether the portion of the impairment loss allocated to the asset subject to foreclosure may be deferred until the gain on restructuring is recognized in 20X2. The answer to that question is no. There is no link between the timing of when an impairment loss allocated to an asset that may be subject to foreclosure should be recognized and the timing of when a gain on restructuring related to settling debt through foreclosing on the asset should be recognized.

2.2.4.1 Full settlement of debt through borrower's transfer of assets

Relevant guidance: ASC 470-50-40-2, ASC 470-60-35-2 through 35-3 and ASC 470-60-35-9

In a TDR in which the borrower agrees to transfer assets, the assets could be accounts receivable from routine sales made by the borrower, real estate or other assets (including cash). If the debt is fully settled by the transfer of assets:

- The borrower recognizes a gain on restructuring for the difference between the carrying amount of the debt and the more clearly evident fair value of the transferred assets or the settled debt. The gain on restructuring should be included as a separate line item in the income statement and should be reduced by the amount of any fees paid or payable to the lender.
- The borrower recognizes a gain or loss on the transfer of assets for any difference between the carrying amount of the transferred assets and the fair value of the transferred assets. Whether the gain or loss affects operating income depends on the nature of the assets transferred. For these purposes, the carrying amount of the transferred assets should reflect any related valuation allowances (e.g., allowance for expected credit losses) and any related unamortized premium, discount or acquisition costs.

To illustrate the accounting described above, consider a TDR in which accounts receivable are being transferred to settle outstanding debt. The carrying amount of the debt being settled is \$1.2 million on the date of the restructuring. Information related to the accounts receivable being transferred on the date of the restructuring is as follows:

- Gross balance is \$1 million,
- Related allowance for doubtful accounts (or credit losses) determined as of the date of transfer is \$100,000, and
- Fair value is \$850,000.



If the borrower concludes that this scenario represents a TDR, the borrower would record the following journal entry on the date the assets are transferred to settle the debt:

| | Debit | Credit |
|--|-------------|-------------|
| Debt | \$1,200,000 | |
| Allowance for doubtful accounts (or credit losses) | 100,000 | |
| Loss on transfer of assets (Note 1) | 50,000 | |
| Accounts receivable | | \$1,000,000 |
| Gain on troubled debt restructuring (Note 2) | | 350,000 |

Note 1: (\$1 million gross balance in accounts receivable – \$100,000 allowance for doubtful accounts) – \$850,000 fair value of accounts receivable

Note 2: \$1.2 million carrying amount of the debt – \$850,000 fair value of accounts receivable transferred

In this example, the gain on restructuring should be included as a separate line item in the income statement. The loss on transfer of assets should be included in operating income given that the assets transferred (i.e., accounts receivable) are operating assets.

Determining the fair value of debt

The fair value of a liability is based on its transfer price. It is not appropriate to assume that the price to transfer the liability is the same as the price to settle the liability or the same as the carrying amount of the liability. How a borrower estimates the amount at which it would be able to transfer one of its liabilities may present unique challenges given the lack of market information on transfer prices for entity-specific liabilities. Oftentimes, there is little market information available because contractual or other legal restrictions prevent the transfer of such liabilities. Guidance on measuring the fair value of liabilities is included in ASC 820-10-35.

2.2.4.2 Full settlement of debt through borrower's transfer of equity

Relevant guidance: ASC 470-60-35-2, ASC 470-60-35-4 and ASC 470-60-35-12

In a TDR in which the borrower agrees to transfer equity to fully settle the debt, the borrower recognizes a gain for the difference between the carrying amount of the debt and the more clearly evident fair value of the transferred equity or the settled debt. See [Section 2.2.4.1](#) for information about determining the fair value of debt. Any fees paid or payable to the lender and any direct costs incurred with third parties related to the issuance of equity to settle the debt reduce the amount recorded in equity. All other fees and direct costs incurred unrelated to the issuance of equity either: (a) are included in expense for the period, if no gain on restructuring is recognized, or (b) reduce the amount of the gain, if a gain on restructuring is recognized.

Commentary: For purposes of this discussion, equity includes equity-linked instruments that should be classified as equity, but not equity-linked instruments that should be classified as liabilities. The classification of equity-linked instruments is discussed in detail in [our debt and equity guide](#). Settling debt with equity-linked instruments that should be classified as liabilities results in there being continuing debt with the same lender, the implications of which are discussed in [Section 2.1.2](#) and [Section 2.2.1.1](#).

2.2.4.3 Borrower and lender only change the debt's terms

Relevant guidance: ASC 470-60-35-5 through 35-7 and ASC 470-60-35-10 through 35-11

In a TDR in which the borrower and lender agree to change the terms of the debt (and not transfer assets or equity), the accounting depends on whether the total cash outflows required under the restructured debt are more or less than the carrying amount of the debt prior to the restructuring. In some cases, total cash outflows required under the restructured debt may fluctuate (e.g., the interest rate varies over time depending on changes in the prime rate). In these cases, total cash outflows required under the



restructured debt should be based on the interest rate in effect at the time of the restructuring. Additional discussion about debt with a variable interest rate is provided later in this section.

To the extent the borrower must pay the lender any fees in conjunction with the restructuring, those fees should be included in the total projected cash outflows because they are essentially equivalent to additional principal and interest payments. In other words, the lender could decrease (or increase) the lender fee and retain the same economics by increasing (or decreasing) the principal or interest payments.

Total cash outflows required for restructured debt > Carrying amount of debt prior to restructuring

If total cash outflows required under the restructured debt are greater than the carrying amount of the debt prior to the restructuring, then no gain or loss is recognized and there is no adjustment to the carrying amount of the debt. The fact that no gain or loss is recognized and no adjustment is made to the carrying amount of the debt does not affect the conclusion that a TDR has occurred. The change in cash outflows resulting from the restructuring is accounted for on a prospective basis (i.e., the changes are recognized in future periods) by calculating a new effective interest rate on the restructured debt and using it to recognize lower interest expense over the restructured debt's remaining term.

As mentioned earlier, a lender fee that must be paid by the borrower in conjunction with the restructuring is included in the total cash outflows required under the restructured debt. Those total cash flows are used to calculate the effective interest rate on the restructured debt. As a result, a lender fee increases the effective interest rate, which leads to the fee being recognized over the restructured debt's remaining term.


The new effective interest rate used to account for the debt on a going-forward basis is the effective interest rate calculated on the restructured debt for purposes of determining whether the lender granted a concession to the borrower (see [Section 2.2.2.2](#)).

[Example 3-2](#) illustrates the application of this guidance.

Total cash outflows required for restructured debt < Carrying amount of debt prior to restructuring

If total cash outflows required under the restructured debt are less than the carrying amount of the debt prior to the restructuring, then a gain is generally recognized and there is an adjustment to the carrying amount of the debt. However, as explained later in this section, gain recognition may not be appropriate when contingent payments are included in the terms of the restructured debt. In addition, as discussed in [Section 2.2.4.5](#), incremental considerations arise with respect to gain recognition when the lender is also an equity holder in the borrower.

When there are no contingent payments, the amount of the recognized gain and the adjustment to the carrying amount of the debt is determined as follows:



More than one account (e.g., debt and the related debt discount or premium) may be affected by the adjustment to the carrying amount of the debt. These accounts may either be retained or combined after the restructuring. If they are retained, the adjustment should be allocated among those accounts that remain after the restructuring using their previous balances for allocation purposes.

Going forward, all cash payments under the terms of the restructured debt must be accounted for as reductions of the carrying amount of the debt, and no interest expense should be recognized on the debt

for any period between the restructuring and maturity of the debt. The only exception is to recognize interest expense according to ASC 470-60-35-10.

Example 3-3 illustrates the application of this guidance.

Contingent payments

Contingent payments, or what are essentially contingent payments, may be included in the terms of the restructured debt. Examples of such contingent payments include: (a) amounts the borrower is required to pay if its financial condition improves (based on a specified, measurable metric) by a specific date and (b) indeterminate interest payments the borrower has to make because the restructured debt is due on demand.

When contingent payments are included in the terms of the restructured debt and the total projected *noncontingent* cash outflows required under the restructured debt are less than the carrying amount of the debt prior to the restructuring, the borrower should not recognize a gain on the restructuring if the maximum total future cash payments (total projected noncontingent cash outflows plus all contingent amounts that could become payable) is greater than the carrying amount of the debt prior to the restructuring. If a gain is not recognized as a result of this guidance, a new effective interest rate must be calculated for purposes of recognizing interest expense in future periods. In some cases, this new effective interest rate may be at or near zero. When determining the new effective interest rate, only those contingent payments necessary to prevent gain recognition are included in the calculation. For example, assume in a TDR that: (a) the carrying amount of the debt prior to the restructuring is \$1 million, (b) the total projected noncontingent cash outflows required under the restructured debt are \$900,000 and (c) the maximum contingent payments that could be made under the restructured debt are \$200,000 (two payments of \$100,000 each). In this example, only \$100,000 of the maximum contingent payments is included in calculating the new effective interest rate because that is the amount that would prevent gain recognition.

The *probable* and *reasonably estimable* thresholds applied to the recognition of other contingent liabilities should be applied to determine if and when a liability should be recognized for the contingent payments included in the terms of the restructured debt. If a liability should be recognized, or when the contingent payments are actually made, consideration must be given to whether those amounts should serve to reduce the carrying amount of the restructured debt. This would be the case if those amounts were included in the total projected cash payments under the restructured debt for purposes of preventing the recognition of a gain at the time of the restructuring.

Variable interest rate

When total cash outflows required under the restructured debt may fluctuate because the interest rate varies over time (e.g., based on changes in the prime rate), the total maximum cash outflows required under the restructured debt should be based on the interest rate in effect at the time of the restructuring. If these cash outflows are less than the carrying amount of the debt prior to the restructuring, a gain is recognized for the difference, provided there are no contingent payments (other than those related to the debt's variable interest rate) that could be required in the future that would reduce the gain.

After the TDR, a debtor should not recognize a gain on the restructured debt that involves indeterminate future cash payments as long as the maximum cash payments may equal or exceed the carrying amount of the debt. Fluctuations in the debt's effective interest rate after the restructuring due to changes in the underlying benchmark or index (e.g., the prime rate) or other causes are accounted for as changes in estimates in the periods in which the changes occur. However, the accounting for those fluctuations should not result in recognizing a gain on restructuring that may be offset by future cash payments. Rather, the carrying amount of the restructured debt should remain unchanged, and future cash payments should reduce the carrying amount until the time that any gain recognized cannot be offset by future cash payments. Based on this guidance, if the debt's variable interest rate after the TDR increases to a rate above the rate on the date that the TDR occurred (the TDR variable interest rate), the incremental interest expense is recognized in the period the increase occurs. Conversely, if the debt's



variable interest rate decreases below the TDR variable interest rate, all interest accrued offsets the carrying amount of the debt, and any additional gain is not recognized until the debt is settled.

Commentary: As discussed in the preceding paragraph, when there is a decrease in the debt's variable interest rate after a TDR, a gain is not recognized until settlement of the debt, in case there is a subsequent increase in the variable interest rate that offsets the effects of the previous decrease.

If there is such a subsequent increase, we believe the borrower should continue to defer the recognition of any gain until settlement of the debt and elect one of the following two accounting policies:

1. Recognize interest expense when the variable interest rate increases above the TDR variable interest rate where such interest expense would be based on the excess of the increased variable interest rate over the TDR variable interest rate
2. Recognize the effects of the increase in the variable interest rate as a reduction in the carrying amount of the debt until the effects of the previous decrease in the variable interest rate has been offset, at which point the incremental interest is recognized as an expense

The accounting policy elected by the borrower should be disclosed and consistently applied in similar facts and circumstances.

To illustrate the accounting discussed above, consider a situation in which the borrower and lender changed a loan with a carrying amount of \$133,000, and it was determined that these changes met the definition of a TDR. Pertinent information related to the loan after the restructuring included the following:

- Interest is paid annually at a variable interest rate (which is reset at the beginning of each year), with the first interest payment being due one year after the restructuring
- Principal amount is \$100,000
- Remaining term is four years
- Variable interest rate on the date of the restructuring is 7%
- Estimated interest related cash flows are \$28,000 (\$100,000 principal x 7% variable interest rate on the date of the TDR x 4-year remaining term)

Borrower recognized a gain on restructuring of \$5,000, calculated based on the excess of the carrying amount of the debt immediately before the restructuring (\$133,000) over the total projected cash outflows required under the terms of the restructured debt (\$128,000), which represents the principal amount repayable of \$100,000 plus \$28,000 of total estimated interest payments over the term of the restructured debt.

Subsequent to the restructuring:

The variable rate of interest remained at 7% throughout Year 1; however, at the beginning of Year 2, the debt's variable interest rate changed to 6% and remained at that rate throughout the year. The following journal entries were recorded in Year 1 and 2 related to the debt:

| | Debit | Credit |
|--|---------|---------|
| Interest accrued during Year 1 (Note 1) | | |
| Debt (Note 1) | \$7,000 | |
| Accrued interest | | \$7,000 |
| Interest paid at the end of Year 1 (Note 1) | | |
| Accrued interest | \$7,000 | |
| Cash | | \$7,000 |
| Interest accrued during Year 2 (Note 2) | | |
| Debt (Notes 1 and 2) | \$6,000 | |
| Accrued interest | | \$6,000 |
| Interest paid at the end of Year 2 (Note 2) | | |
| Accrued interest | \$6,000 | |
| Cash | | \$6,000 |

Note 1: Entry to recognize interest accrued during Year 1 and then paid at the end of Year 1 is based on a variable rate of interest of 7%. The offsetting entry to accrued interest is debt, rather than interest expense, because upon the debt's restructuring, the carrying amount of the loan was adjusted to equal the total estimated cash outflows for both the remaining principal and interest payable over the term of the restructured loan.

Note 2: Entry to recognize interest accrued during Year 2 and then paid at the end of Year 2 is based on a variable rate of interest of 6%. The offsetting entry to accrued interest is debt, rather than interest expense, because upon the debt's restructuring, the carrying amount of the loan was adjusted to equal the total estimated cash outflows for both the remaining principal and interest payable over the term of the restructured loan. In accordance with ASC 470-60-35-7, no gain is recognized for the decrease in the variable interest rate (from 7% to 6%) because the variable interest rate could subsequently increase in Years 3 or 4 and offset the effects of the decrease in Year 2.

At the beginning of Years 3 and 4 and throughout these years, the debt's variable interest rate is 9% and 7%, respectively. The borrower's accounting for the interest due during Years 3 and 4 depends on whether it elects accounting policy (1) or (2) discussed earlier.

Under accounting policy (1):

- In Year 3, the borrower reduces the carrying amount of the debt by the original estimated annual interest payment of \$7,000 and records interest expense of \$2,000 for the excess of the variable interest payment based on a 9% interest rate over the original estimated annual interest payment.
- In Year 4, the borrower pays \$7,000 of interest and \$100,000 of principal and reduces the carrying amount of the debt to zero and recognizes a \$1,000 gain on restructuring.

Under accounting policy (2):

- In Year 3, the borrower reduces the carrying amount of the debt by the original estimated annual interest payment of \$7,000 plus the shortfall of \$1,000 between the interest payment made in the prior year (\$6,000) and the original estimated interest payment for that year (\$7,000). Borrower also records interest expense of \$1,000 for the difference between actual interest payment for the year (\$9,000) and the amount for which debt was reduced as noted above (\$8,000).
- In Year 4, the borrower pays \$7,000 of interest and \$100,000 of principal and reduces the carrying amount of the debt to zero with no gain or loss recorded as the interest paid in year 4 was based on a 7% variable interest rate, which is consistent with the original variable interest rate.



The following summarizes the journal entries that would be recorded in Years 3 and 4 depending on the accounting policy elected by the borrower:

| | Accounting policy (1) (Notes 1, 3 and 4) | | Accounting policy (2) (Notes 2, 3 and 4) | |
|---|---|-----------|---|-----------|
| | Debit | Credit | Debit | Credit |
| Interest accrued during Year 3 | | | | |
| Debt | \$7,000 | | \$8,000 | |
| Interest expense | 2,000 | | 1,000 | |
| Accrued interest | | \$9,000 | | \$9,000 |
| | | | | |
| Interest paid at the end of Year 3 | | | | |
| Accrued Interest | \$9,000 | | \$9,000 | |
| Cash | | \$9,000 | | \$9,000 |
| | | | | |
| Interest accrued during Year 4 | | | | |
| Debt | \$7,000 | | \$7,000 | |
| Accrued interest | | \$7,000 | | \$7,000 |
| | | | | |
| Interest paid at the end of Year 4 | | | | |
| Accrued Interest | \$7,000 | | \$7,000 | |
| Cash | | \$7,000 | | \$7,000 |
| | | | | |
| Principal repaid at maturity | | | | |
| Debt | \$101,000 | | \$100,000 | |
| Cash | | \$100,000 | | \$100,000 |
| Gain on restructuring | | 1,000 | | - |

Note 1: Entries to record the interest accrued and paid in Year 3 based on the variable interest rate of 9%. Under this accounting policy, the amount by which the carrying value of a loan with a variable interest rate is reduced is based on the lesser of the actual interest payable for the period or the amount estimated at the time of the restructuring. Any actual interest payable for the period in excess of the amount estimated at the time of the loan restructuring is recognized as interest expense until the debt carrying amount is fully settled or reduced to zero.

Note 2: Entry to record the interest paid in Year 3 based on the variable interest rate of 9%. Under this accounting policy, the amount by which the carrying value of a loan with a variable interest rate is reduced is the sum of the interest estimated at the time of the restructuring of \$7,000 plus the shortfall of \$1,000 between the accrued interest recorded in the prior year (\$6,000) and the original interest estimated at the time of restructuring for that year (\$7,000). Borrower also records interest expense of \$1,000 for the difference between actual interest owed for the year (\$9,000) and the amount for which debt was reduced (\$8,000).

Note 3: Entries to record the interest accrued and paid in Year 4 based on the variable interest rate of 7%.



Note 4: Entry to record the principal repayment in Year 4 to settle the remaining principal outstanding on the debt. The related gain upon extinguishment of the restructured debt under each respective accounting policy is calculated as follows:

| | Accounting Policy (1) | Accounting Policy (2) |
|---|-----------------------|-----------------------|
| Debt carrying value on date of restructuring | \$128,000 | \$128,000 |
| Less: Changes to debt carrying value relating to interest adjustments | | |
| Year 1 | (7,000) | (7,000) |
| Year 2 | (6,000) | (6,000) |
| Year 3 | (7,000) | (8,000) |
| Year 4 | (7,000) | (7,000) |
| Less: Principal Repayment | (100,000) | (100,000) |
| Ending debt balance recognized as a gain on extinguishment | \$1,000 | \$ - |

2.2.4.4 Partial settlement of debt

Relevant guidance: ASC 470-60-35-2 and ASC 470-60-35-8

The borrower and lender may agree to the partial settlement of debt in conjunction with a restructuring. For example, a TDR could result from any of the following:

- The borrower agrees to pay some cash to the lender and the borrower and lender agree to modify some of the remaining terms of the debt.
- The borrower agrees to transfer noncash assets to the lender and the borrower and lender agree to modify some of the remaining terms of the debt.
- The borrower agrees to transfer equity (including equity-linked instruments classified as equity [see details in [our debt and equity guide](#)]) to the lender and the borrower and lender agree to modify some of the remaining terms of the debt.
- The borrower agrees to transfer cash, noncash assets or equity (including equity-linked instruments classified as equity [see details in [our debt and equity guide](#)]) to the lender that partially settles the debt, but the terms of the debt that remain are unchanged.

When the TDR involves a partial settlement, the carrying amount of the debt is reduced by the fair value of the assets or equity transferred in the partial settlement. Unlike the full settlement of debt through the borrower's transfer of assets or equity in which the fair value of the settled debt (if it is more clearly evident) could be used in place of the fair value of the assets or equity to determine the gain on restructuring (see [Section 2.2.4.1](#) and [Section 2.2.4.2](#)), the fair value of the partially-settled debt cannot be used to reduce the carrying amount of the debt.

When noncash assets are involved, a gain or loss on the transfer of the assets is recognized for the difference between the carrying amount and fair value of the noncash assets transferred. This is similar to the approach taken when the TDR is a full settlement through the transfer of noncash assets (see [Section 2.2.4.1](#)).

After the carrying amount of the debt has been reduced and any gain or loss on the transfer of noncash assets recognized, the accounting for the restructuring follows the approach taken when the TDR involves only the modification of terms (see [Section 2.2.4.3](#)). When using this approach to account for a TDR that involves a partial settlement of the debt, the borrower's analysis should: (a) use the carrying amount of the debt after reduction for the fair value of any assets or equity transferred, (b) use the terms of the debt that remains after the partial settlement and (c) include any lender fees not related to the



issuance of equity in the total projected cash outflows required under the restructured debt. Additional considerations arise with respect to gain recognition when the lender is also an equity holder in the borrower (see the next section).

[Example 3-4](#) and [Example 3-5](#) illustrate the application of this guidance.

2.2.4.5 Additional considerations when the lender is also an equity holder in the borrower

A common related party relationship involving a borrower and a lender is when the lender is also an equity holder in the borrower. If the TDR accounting model is applied to changes in a loan with a lender that is also an equity holder, consideration must be given to whether any gain that results from applying that accounting model should be reflected in the income statement or in equity (i.e., additional paid-in capital). A key consideration in this regard is whether the substance of the transaction is an equity contribution in which the lender is restructuring the loan to protect its equity investment in the borrower. If so, that would provide a strong indication that any gain recognized in connection with the restructuring should be reflected in equity.

When determining whether the lender is protecting its equity investment in the borrower, consideration should be given to the facts and circumstances of each specific transaction, including:

- The role of the related party lender or equity investor in the transaction
- The reason the lender agreed to the restructuring of the debt that resulted in a gain to the borrower
- The substance of the transaction
- The significance of the lender's equity investment in the borrower
- Whether the debt was extinguished based on current market terms
- Whether other lenders restructured their debt in the same manner and whether those lenders are also equity holders

While there is no authoritative guidance that specifically addresses this issue, we believe that if all lenders involved in the restructuring also have an equity investment in the borrower, any gain recognized in connection with the restructuring should generally be reflected in equity. However, the substance of the transaction and the specific facts and circumstances, must be considered and judgment is required in making the determination. The considerations outlined above are generally consistent with [remarks by Sagar S. Teotia at the 2010 AICPA National Conference on Current SEC and PCAOB Developments](#) in which it was concluded that, based on the substance of the transaction and the specific facts and circumstances, a gain from the extinguishment of debt that was held by a shareholder should be considered a capital contribution from a related party and recognized in equity. While the fact pattern referenced in those remarks related to a non-TDR extinguishment, we believe the same logic should apply to a TDR extinguishment. Conversely, if there are lenders with significant loans involved in the restructuring that do not also have an equity investment in the borrower and agree to the same terms in the restructuring as lenders with an equity investment, we believe that any gain recognized in connection with the restructuring should generally be reflected in the income statement.

2.2.5 Direct costs incurred with third parties in a TDR

Relevant guidance: ASC 470-60-35-12

The borrower will likely incur direct costs with third parties in connection with executing a TDR. Any of these costs (including legal fees) that relate to transferring equity from the borrower to the lender in the TDR should reduce the amount that would otherwise have been recognized in equity. For all other direct costs with third parties incurred in executing a TDR, they are recognized in the income statement as incurred. The classification of these costs in the income statement depends on whether a gain on restructuring is recognized. If so, such costs should reduce the amount that would otherwise be recognized as a gain. If not, such costs should typically be reflected in a separate line item in the income statement.



Commentary: The borrower may incur direct costs with third parties (e.g., legal expenses) when working towards a TDR in one reporting period, but not complete the TDR until the next reporting period. When this is the case, the question arises about whether the borrower should defer those direct costs incurred in the first reporting period until the reporting period in which the TDR is completed. The answer to that question is no. The borrower should recognize direct costs incurred with third parties in conjunction with a TDR that are not related to the issuance of equity in the income statement in the period in which those costs are incurred.

2.2.6 Lender fees incurred in the restructuring

Fees paid or payable to the lender in conjunction with the TDR that are not related to the issuance of equity either decrease the amount of the gain that would have otherwise been recognized (when there are no contingent payments and total projected cash outflows under the restructured debt is less than the carrying amount of the debt prior to the restructuring) or are deferred and increase the effective interest rate used to account for the debt on a going-forward basis (when total projected cash outflows under the restructured debt are greater than the carrying amount of the debt prior to the restructuring).

2.2.7 Preexisting unamortized debt discount

To the extent there is an unamortized debt discount (which would include unamortized debt issuance costs) prior to the restructuring when the debt *is not fully settled* in the restructuring, those costs should already be included in the net carrying amount of the debt prior to the restructuring. As discussed earlier in [Section 2.2.4.3](#), if total projected cash outflows required under the restructured debt are greater than the carrying amount of the debt prior to the restructuring (and, consequently, no gain or loss is recognized), the carrying amount of the debt is used in determining the new effective interest rate for the restructured debt. This new effective interest rate is used to calculate interest expense over the remaining term of the restructured debt. As such, the unamortized debt discount prior to the restructuring continues to be recognized as interest expense over the remaining term of the restructured debt. Conversely, in a TDR in which the total projected cash outflows required under the restructured debt (including any contingent amounts) are less than the carrying amount of the debt prior to the restructuring, a gain is recognized. The calculation of the gain in this situation is based on the carrying amount of the debt prior to the restructuring less the total cash outflows required under the terms of the restructured debt. Because the unamortized debt discount is included in the carrying amount of the debt prior to the restructuring, it would effectively reduce the amount of gain recognized.

To the extent there is an unamortized debt discount prior to the restructuring when the debt *is fully settled* in the restructuring, such unamortized debt discount would reduce any gain recognized on the restructuring.

[Example 3-3](#), [Example 3-4](#) and [Example 3-5](#) provide further detail on the accounting for TDRs.

2.2.8 Classification considerations

Relevant guidance: ASC 470-60-45-1 through 45-2

When debt is restructured, consideration should be given to the current versus noncurrent classification of the debt that remains. Consideration should also be given to the current versus noncurrent classification of the debt that remains from a TDR that occurs after the borrower's balance-sheet date but before the balance sheet is issued or available to be issued.

Commentary: While the classification of debt may be affected by a TDR that occurs after the borrower's balance-sheet date but before the balance sheet is issued or available to be issued, the timing of the accounting for the TDR is not affected. In other words, any gain recognized in the accounting for the TDR cannot be pushed back to the balance-sheet date. In addition, any equity grants that were part of the TDR cannot be pushed back to the balance-sheet date.

For more information about the current versus noncurrent classification of debt, refer to our [debt classification white paper](#).



2.2.9 Disclosures

Relevant guidance: ASC 470-60-50-1 through 50-2

The borrower must disclose the following about a TDR that affected any of the financial statements presented:


- A description of how the terms of the debt changed and the major features of settlement
- The amount of any gain recognized in connection with the restructuring, as well as the gain per share
- The amount of any gain or loss recognized on the transfer of assets in connection with the restructuring

Separate TDR transactions that impact the same type of liability may be aggregated.

For public business entities following the adoption of ASU 2024-03, consider the interaction with the disclosure requirements in ASC 220-40-50-21 through 50-25, as those paragraphs integrate existing required disclosures with the new disclosures introduced by ASU 2024-03. ASC 470-60-50-1 requires entities to disclose the gain recognized from a TDR. The guidance in ASC 220-40-50-22 requires that an entity disclose that gain in the tabular format disclosure required by ASU 2024-03 if the gain is recognized entirely in one expense caption that is also a relevant expense caption as determined in accordance with the guidance in ASC 220-40-50-12 through 50-13. For additional information about the disaggregated income statement expense disclosure requirements of ASU 2024-03, refer to our publication, [New Expense Disaggregation Disclosure Requirements](#). ASU 2024-03 is effective for public business entities for annual reporting periods beginning after December 15, 2026, and interim reporting periods within annual reporting periods beginning after December 15, 2027. Early adoption is permitted.

To the extent contingent payments are involved in the TDR, the borrower should disclose in periods after the restructuring the portion of the restructured debt's carrying amount that reflects contingently payable amounts. In addition, with respect to the contingent payments, the borrower should also consider whether it satisfies the general disclosure requirements applicable to contingent liabilities. Depending on the facts and circumstances, information such as the total amount contingently payable and the terms of the contingency may need to be disclosed.

2.3 Extinguishment and modification accounting models for term loans



2.3.1 Scope

Relevant guidance: ASC 470-50-05-1, ASC 470-50-15-2 through 15-3, ASC 470-50-40-5 and ASC 470-50-55-8 through 55-9

If the borrower concludes that it has not met the liability derecognition threshold or the TDR criteria, then it must determine whether the modification or exchange should be accounted for using the extinguishment or modification accounting model. This determination may be necessary when the borrower and lender agree to exchange loans or modify the terms of an existing loan. The determination

must also be made when the borrower and lender agree to modify a loan to require its redemption at a future date for a specified amount.

The extinguishment and modification guidance discussed in this guide does not apply in any of the following circumstances:

- Conversions of debt into equity securities of the borrower pursuant to conversion privileges provided in the terms of the debt at issuance. Additionally, the guidance does not apply to conversions of convertible debt instruments pursuant to terms that reflect changes made by the borrower to the conversion privileges provided in the debt at issuance (including changes that involve the payment of consideration) for the purpose of inducing conversion.
 - Following the adoption of ASU 2024-04: Conversions of debt instruments according to conversion rights included in the terms and conditions of those instruments. Additionally, the guidance does not apply to conversions of convertible debt instruments pursuant to terms that reflect changes made by the borrower to the conversion rights provided in the debt at issuance (including changes that involve the payment of consideration) for the purpose of inducing conversion. Guidance addressing conversions of debt instruments (including induced conversions) is included in ASC 470-20-40-4, ASC 470-20-40-13 and ASC 470-20-40-15. ASU 2024-04 is effective for all entities for annual reporting periods beginning after December 15, 2025, and interim periods therein.
- Transactions between a borrower or a borrower's agent and a third party that is not the lender.
- Debt tendered to exercise detachable warrants that were originally issued with that debt if the debt is permitted to be tendered towards the exercise price of the warrants under the terms of the securities at issuance. The tendering of the debt in such a case would be accounted for in the same manner as a conversion.
- The borrower announces its intention to call a loan at its first call date.
- There is an in-substance defeasance, which occurs when the borrower establishes an irrevocable trust for the benefit of the lender and deposits in that trust the principal, interest and prepayment penalties applicable to the loan between the borrower and lender.
- There is an agreement with a lender that a debt instrument issued by the borrower and held by a different party will be redeemed.
- A loan is converted to the borrower's equity securities in accordance with conversion privileges included in the loan at issuance.
- A loan is converted to the borrower's equity securities in accordance with conversion privileges included in the loan that have been changed since issuance (including induced conversions).

The accounting for convertible debt, including conversions and modifications (other than modifications of convertible debt with an embedded conversion option [see [Section 1.2](#)]) are discussed in detail in Chapter 3 of [our debt and equity guide](#).

2.3.1.1 Unit of account when there are multiple term loans with the same lender

When there are multiple term loans with the same lender (see [Section 1.1](#)) and changes are made to one of those loans, we believe that judgment should be used in determining the unit of account for purposes of evaluating the changes under ASC 470-50. While there is no authoritative guidance that specifically addresses this issue, we believe that one of the primary considerations when determining the unit of account is whether the changed term loan reflects market terms at the time the changes were made. If so, that would be an indication that the unit of account for purposes of evaluating the changes under ASC 470-50 would be the specific term loan that was changed. Conversely, when the changed term loan does not reflect market terms, that would be an indication that the unit of account for purposes of evaluating the changes under ASC 470-50 may be a combination of some or all of the term loans with that lender. Depending on those facts and circumstances, among others, the unit of account for purposes of



evaluating the changes to the term loan under ASC 470-50 may be just the specific term loan that was changed or a combination of some or all of the term loans with that lender.

Similarly, consider a situation in which a borrower enters into a new term loan with a lender. The borrower has a preexisting term loan that was entered into prior to entering into the new term loan with the same lender (see [Section 1.1](#)) that was not changed or otherwise affected by the new term loan. In this situation, we believe that whether the new term loan should be accounted for as a separate unit of account (i.e., a new term loan that would not be evaluated under ASC 470-50) or as a combined unit of account (i.e., a modification of a preexisting term loan for incremental borrowings that would be evaluated under ASC 470-50) is subject to judgment and based on the specific facts and circumstances of each unique situation. Consistent with the discussion in the previous paragraph, we believe that one of the primary considerations when determining the unit of account is whether the new term loan reflects market terms at the time it was entered. If so, that would be an indication that the new term loan would be a separate unit of account and accounted for as a new loan. If, on the other hand, the new term loan does not reflect market terms, that would be an indication that the unit of account may be a combination of the new term loan and some or all of the preexisting term loans with that lender and evaluated as a change to the preexisting loan under ASC 470-50. Additionally, we believe other factors should also be considered when determining the unit of account, including:

- Whether the loans were negotiated or entered into contemporaneously or in contemplation of one another
- The reasons the new loan is being entered into
- The entity's history with the lender

2.3.1.2 Unit of account for delayed-draw term loans (DDTLs)

DDTLs generally represent commitments from lenders for term loan facilities in which the borrower may draw on these facilities at a future date within a period identified in the loan agreement. Therefore, these loans may not be funded, or may not be fully funded, on the date that the loan agreements are executed, but rather will be funded at some future date. This adds complexity to the models for evaluating debt modifications and restructurings, as these loans have characteristics of term loans and line-of-credit facilities. As a result, these loans may need to be evaluated under two different models depending on the facts and circumstances.

Assuming that the transaction does not meet the TDR criteria, we believe that judgment is necessary in determining the appropriate accounting model to be used when evaluating changes to DDTLs. In general, we believe that changes to DDTLs that are unfunded and not expected to be funded in the near term should be evaluated using the line-of credit model, while changes to funded DDTLs and those expected to be funded in the near term should be evaluated using the term loan model.

[Example 3-13](#) illustrates the application of this guidance.

2.3.2 Which model applies?

Relevant guidance: ASC 470-50-40-6 through 40-12A

If the borrower concludes that an exchange of loans or a modification to the terms of an existing loan do not meet the liability derecognition threshold or the TDR criteria, then it must determine whether the modification or exchange should be accounted for using the modification or extinguishment accounting model (the latter of which could result in the borrower recognizing a gain or loss in its income statement [see [Section 2.3.3](#)]). In making this determination, the mere fact that the borrower and lender concurrently exchange cash to satisfy an existing loan (cash from borrower to lender) and issue a new loan (cash from the same lender [see [Section 1.1](#)] to borrower) should not automatically lead the borrower to conclude that the extinguishment accounting model should be applied. In these and other situations in which a loan is modified, the borrower must determine whether the new loan (the modified loan or the loan received in the exchange) is substantially different from the old loan (the loan before modification or the loan given up in the exchange).






Looking forward: On April 30, 2025, the FASB issued proposed ASU, *Debt – Modifications and Extinguishments (Subtopic 470-50) and Liabilities – Extinguishments of Liabilities (Subtopic 405-20): Accounting for Debt Exchanges*. Following the comment period and initial redeliberations, the FASB decided that the repayment of an existing loan and the issuance of a new loan would be accounted for using the extinguishment accounting model and the 10% cash flow test would not need to be completed if all of the following criteria are met:

- The new debt has multiple lenders
- The old debt is repaid in accordance with its contractual terms or repurchased at market terms
- The new debt is issued at market terms

If these criteria are not met, or in other situations in which a loan is modified, the borrower must determine whether the new loan (the modified loan or the loan received in the exchange) is substantially different from the old loan (the loan before modification or the loan given up in the exchange) by performing the 10% cash flow test.

However, in March 2026, the FASB “decided to pause further deliberations on the project until it evaluates broader feedback received from the Private Company Council and the January 2025 Invitation to Comment, *Agenda Consultation*, on debt modifications and extinguishments.” As a result, a final ASU is not expected in the near term. See the FASB’s [Accounting for Debt Exchanges](#) project site for the most current developments regarding this project.

A flowchart for determining whether a substantial difference exists because of a change in the loan’s cash flows follows:




When calculating the present value of cash flows referred to in the flowchart:

- The cash flows of the new loan should include any amounts exchanged by the borrower and lender in connection with the exchange or modification, including any fees charged by the lender, or paid on behalf of the lender (see [Section 2.3.5.1](#)), to execute the modification or exchange, any incremental borrowings received by the borrower, and any repayments of principal by the borrower.
- The cash flows for loans with floating interest rates should be based on the variable rate in effect when the exchange or modification occurs.
- When either or both the preexisting or changed loan is callable or puttable, two sets of cash flows may need to be considered: (1) cash flows assuming the call or put is exercised and (2) cash flows assuming the call or put is not exercised. The cash flows that should be used in the 10% cash flow test are those that result in the smaller change between the present value of the new loan's cash flows and the present value of the old loan's remaining cash flows. A loan is callable if the lender has the right, but not the obligation, to require the borrower to repay the loan's principal before its stated maturity date. A loan is puttable if the borrower has the right, but not the obligation, to repay the loan before maturity on specified dates for a predetermined price. Refer to [Section 2.3.2.1](#) for discussion about the applicability of this guidance to explicit and implicit prepayment options.
- The discount rate is the preexisting loan's effective interest rate.
- If one or more less-than-substantially-different exchanges or modifications to the loan occurred within a year of the current exchange or modification, the changes would be assessed cumulatively (instead of separately) for purposes of applying the 10% cash flow test (see [Section 2.3.2.2](#) for additional discussion). This requirement is so the borrower does not get a different accounting answer by executing the exchange or modification in stages.
- The effects of an exchange or modification on an embedded conversion option's fair value is assessed separately and is not reflected in the 10% cash flow test (refer to the remaining content in this section for additional discussion).
- If the borrower modifies or exchanges a freestanding equity-classified written call option (such as a warrant) held by its lender as part of, or directly related to, a modification or exchange of the related debt held by that same lender, an increase or a decrease in the fair value of the freestanding equity-classified written call option held by such lender should be reflected in the 10% cash flow test.

The treatment of a "sweetener" in the 10% cash flow test is discussed in [Section 2.3.2.3](#).

Following is a flowchart for determining whether a substantial difference exists because an embedded conversion option was added, eliminated or changed in the modification or exchange:



Note 1: For purposes of determining whether a conversion option is substantive, the guidance in ASC 470-20-40-7 through 40-9 should be used. For additional information, refer to Chapter 3 of [our debt and equity guide](#).

Note 2: To determine the change in the fair value of an embedded conversion option, compare the fair value of the option right before and right after the exchange or modification.

As noted in the flowchart, the significance of an exchange or modification on an embedded conversion option's fair value is assessed separately and is not reflected in the 10% cash flow test discussed earlier in this section.




2.3.2.1 Prepayment options

Relevant guidance: ASC 470-50-40-12(c)

For a loan that is callable or puttable, two sets of cash flows may need to be considered for purposes of applying the 10% cash flow test: (1) cash flows assuming the call or put is exercised and (2) cash flows assuming the call or put is not exercised. The cash flows that should be used in the 10% cash flow test for purposes of reaching a decision about the accounting model that should be used are those that result in the smaller change between the present value of the new loan's cash flows and the present value of the original loan's remaining cash flows.

Commentary: A common form of put option present in a loan is a prepayment option. A prepayment option may be explicitly stated in the loan agreement, or it may be implied when the loan agreement does not prohibit prepayment. Such an option allows the borrower to prepay (i.e., put) the debt before it otherwise matures, often subject to a penalty. If the new loan or old loan is prepayable, the cash flows used in the 10% cash flow test may need to be calculated assuming both exercise and non-exercise of the prepayment option because GAAP indicates that the assumption that results in the smaller change in cash flows is used for purposes of reaching a decision about the accounting model that should be used to account for the modification or exchange. This is the case regardless of the probability of prepayment and even if the borrower does not have the financial ability to prepay. Any prepayment penalties are considered part of the cash flows when assuming the prepayment option is exercised. The practical effects of applying this guidance are that: (a) the modification accounting model should be applied when either assumption (i.e., exercise or non-exercise of the prepayment option) produces a change in cash flows of less than 10% (unless an evaluation of changes involving an embedded conversion option indicates otherwise) and (b) the extinguishment accounting model should be applied when both assumptions produce a change in cash flows of more than 10%. These effects are illustrated in the following flowchart:



The 10% cash flow test performed assuming exercise of the prepayment option will typically result in modification accounting because the factors that cause a change in cash flows when assuming exercise of the prepayment option (e.g., fees charged by the lender to modify the loan, a change to the prepayment penalty) would generally not rise to the magnitude necessary to cause a change in cash flows of more than 10%. However, when the prepayment penalty is expressed as a percentage of the new principal amount (rather than as a fixed dollar amount) and the principal amount increases substantially as a result of the amendment, the change in cash flows determined using the 10% cash flow test assuming exercise of the prepayment option could result in a change in cash flows of more than 10%.

From an efficiency perspective, when the borrower has a loan with a prepayment option, we believe it should start by performing the 10% cash flow test under the assumption that it expects would result in the smaller change in cash flows (which is typically the assumption that the prepayment option will be exercised). If the difference is less than 10% under the assumption that the prepayment option will be exercised, the modification accounting model should be applied, and it would not be necessary to perform the 10% cash flow test assuming non-exercise of the prepayment option. If the difference is more than

10% under the first assumption, the borrower would have to perform the 10% cash flow test under the other assumption. This would include considering all factors impacting changes in cash flows, such as interest payments, as well as reflecting all cash flows on a discounted basis while excluding the prepayment penalty.

[Example 3-6](#), [Example 3-7](#), [Example 3-8](#) and [Example 3-9](#) illustrate the application of this guidance.

2.3.2.2 Assessing multiple changes to the same debt within a one-year period

Relevant guidance: ASC 470-50-40-12(f)


As discussed in [Section 2.3.2](#), if one or more less-than-substantially-different exchanges or modifications to debt occurred within a year of the current exchange or modification, the changes should be assessed cumulatively (instead of separately) for purposes of applying the 10% cash flow test. This is required so the borrower does not get a different accounting answer by executing the exchange or modification in stages. However, before the borrower applies the 10% cash flow test on a cumulative basis, it should first determine whether the cumulative changes result in a TDR (see [Section 2.2.3](#)).

Commentary: Based on the limited guidance in ASC 470-50-40-12(f) and the guidance in ASC 470-50 in general, we believe that when there are multiple changes to the same debt within a one-year period, and the first of those changes was determined to be a modification, the borrower should evaluate the changes within the one-year period on a cumulative basis. To do so, when assuming the prepayment option is not exercised, we believe the borrower should perform the 10% cash flow test by comparing the following two amounts (i.e., 1. and 2. below) as of the date the first changes were made to the debt in the one-year period:

1. The present value of the remaining cash flows of the debt right before the first changes were made in the one-year period
 - a. Remaining cash flows include principal repayments and interest payable on the outstanding principal balance from the date right before the first changes were made through the maturity date
2. The present value of the cash flows for the changed debt on the date the first changes were made to the debt, which should reflect all the changes made to the debt within the one-year period (i.e., the first and the subsequent changes made to the debt within the one-year period) and include:
 - a. Incremental borrowings or principal repayments made (or to be made) from the date of the first changes in the one-year period through the final maturity date
 - b. Interest payments through the debt's final maturity date
 - c. Fees paid or payable to the lender from the date of the first changes in the one-year period through the final maturity date

The discount rate used for present-value purposes is the effective interest rate of the debt right before the first changes were made to the debt in the one-year period.

As discussed further in [Section 2.3.2.1](#), when the debt that has been changed is prepayable, the cash flows used in the 10% cash flow test may need to be calculated assuming both exercise and non-exercise of the prepayment option because GAAP indicates that the assumption that results in the smaller change in cash flows is used for purposes of reaching a decision about the accounting model that should be used to account for the changes made to the debt. For the reasons discussed in [Section 2.3.2.1](#), from an efficiency perspective, when the borrower has debt with a prepayment option, it should start by performing the 10% cash flow test under the assumption that it expects would result in the smaller change in cash flows, which is typically the assumption that the prepayment option will be exercised. To perform the 10% cash flow test under the assumption that the prepayment option will be exercised when there are multiple changes to the same debt within a one-year period, we believe that U.S. GAAP requires calculating: (a) the preexisting debt's remaining cash flows assuming the debt is prepaid right before the first changes were made to the debt within the one-year period and (b) the present value of the changed debt's cash flows on the date the first changes were made to the debt in the one-year period



assuming the debt is prepaid right after the last changes were made to the debt within the one-year period.

The following table provides the inputs that should be used to calculate the preexisting debt's remaining cash flows and the changed debt's cash flows assuming the prepayment option will be exercised:

| | Inputs to the 10% cash flow test assuming prepayment option is exercised | |
|---------------------------------|--|---|
| | Preexisting debt's remaining cash flows | Changed debt's cash flows |
| Present value of input required | No | Yes (Note 1) |
| Principal | Principal amount outstanding right before the first change in the one-year period | Principal repaid or borrowed between the date of the first change and the date of the last change in the one-year period plus the remaining principal repayment due after the last-change date |
| Lender fees | Accrued and unpaid lender fees due right before the first change in the one-year period | Lender fees paid in conjunction with making the first and any subsequent changes to the debt in the one-year period, plus any due and unpaid lender fees as of the last-change date |
| Interest | Accrued and unpaid interest due right before the first change in the one-year period | Interest paid after the first change in the one-year period up to and including any interest paid in conjunction with the last change in the one-year period, plus any accrued and unpaid interest as of the last-change date |
| Prepayment penalty or fee | Penalty or fee that would be paid upon prepayment based on the debt's terms right before the first change in the one-year period | Penalty or fee that would be paid upon prepayment based on the debt's terms right after the last change in the one-year period |

Note 1: The discount rate used for present valuing purposes is the effective interest rate of the debt right before the first changes in the one-year period

If the 10% cumulative cash flow test performed assuming prepayment results in a percentage change in cash flows of less than 10%, the borrower accounts for the last change made to the debt in the one-year period as a modification (unless an evaluation of changes involving an embedded conversion option indicate otherwise [see [Section 2.3.2](#)]). Conversely, if the cumulative 10% cash flow test performed assuming prepayment results in a change in cash flows of 10% or more, the borrower should reperform the 10% cash flow test assuming the debt is not prepaid. In this case, the 10% cash flow test will exclude the prepayment penalty and must include calculations of the present value of all cash flows over the life of the debt. If the cumulative 10% cash flow test assuming the debt is not prepaid results in a change in cash flows of less than 10%, the borrower accounts for the last change made to the debt in the one-year period as a modification (unless an evaluation of changes involving an embedded conversion option indicate otherwise). Conversely, if that cumulative 10% cash flow test results in a change in cash flows of 10% or more, the borrower accounts for the last change made to the debt in the one-year period as an extinguishment.

[Example 3-12](#) and [Example 3-13](#) provide comprehensive illustrations of this guidance.



2.3.2.3 Treatment of a warrant or other sweetener or enhancement in the 10% cash flow test

Relevant guidance: ASC 470-50-40-12A and ASC 470-50-40-17A

Commentary: In some situations, a sweetener might be added to or removed from a loan agreement as a result of a modification or exchange of the loan. In other situations, the terms of a sweetener included in the original terms of the loan agreement might be changed. The question that arises in these situations is how adding, changing or removing a sweetener affects the conclusion about whether there is a substantial difference between the old loan and the new loan (and, therefore, whether the extinguishment or modification accounting model should be applied to account for the modification or exchange of the loan). While GAAP does not explicitly answer this question for sweeteners as a whole, GAAP does address the treatment of changes in the fair value of freestanding equity-classified written call options that are modified together with the related debt, stating that the fair value of those changes should be reflected in the 10% cash flow test. Further, when determining whether a concession has been granted in a TDR (see [Section 2.2.2.2](#)), GAAP requires the effects of any new, revised or removed sweeteners to be included in the projected cash flows required under the debt after the changes are made even though adding, revising or removing a sweetener may not always have a direct effect on cash flows. As such, when performing the analysis as to whether a concession has been granted, the day-one projected cash flows required under the debt after the changes are made includes the new sweetener's fair value or the change in a revised sweetener's fair value. Based on this guidance, we believe it would also be appropriate to take this approach when assessing whether there is a substantial difference between the old loan and new loan when a modification or exchange occurs. In other words, we believe that it would be appropriate to include a new sweetener's fair value in the cash flows of the new loan for purposes of the 10% cash flow test used to determine whether there is a substantial difference between the old loan and new loan. In addition, if the terms of a sweetener have changed, we believe it would be appropriate to include the change in the fair value of the sweetener in the new loan's cash flows for purposes of the 10% cash flow test.

The accounting for the fair value or the change in fair value of a sweetener (e.g., warrant) that is added, revised or removed depends on whether the extinguishment or modification accounting model should be applied to the modification or exchange itself. For example, if a loan agreement is modified to include a warrant and the fair value of that warrant is \$1 million, then \$1 million would be included in the new loan's cash flows for purposes of the 10% cash flow test. In addition, if the modification accounting model is applicable, the fair value of the warrant would be recognized as a debt discount. In contrast, if the extinguishment accounting model is applicable, the fair value of the warrant would be taken into consideration in determining the gain or loss on extinguishment (i.e., it would increase what would otherwise be a loss or decrease what would otherwise be a gain). The accounting for any equity-linked sweetener or enhancement, including whether it should be classified as a liability or equity, is addressed in [our debt and equity guide](#).

2.3.3 Extinguishment accounting model

Relevant guidance: ASC 470-50-40-1 through 40-2 and ASC 470-50-40-13

The essence of extinguishment accounting is to remove the settled loan from the borrower's balance sheet. However, extinguishment accounting might also apply when a loan is modified or exchanged (see [Section 2.3.3.3](#)). For the modification or exchange of a loan that qualifies for extinguishment accounting, a loan remains on the borrower's balance sheet after the modification or exchange. In these cases, the old loan (i.e., the loan being modified or given up in the exchange) is effectively derecognized and a new loan (i.e., the modified loan or loan received in the exchange) is recognized. The remainder of this section discusses extinguishment accounting (both when debt is and is not accounted for at fair value) and the special consideration involved when extinguishment accounting is applied to the modification or exchange of a loan.

Prior to accounting for a loan extinguishment, the borrower should identify all of the rights and privileges being exchanged between the borrower and lender as part of the extinguishment. If more than just the extinguishment of a loan is occurring between the parties, then separate accounting recognition for any



activities above and beyond the extinguishment would be required. In doing so, a portion of the consideration exchanged by the parties would need to be allocated to these additional activities.

Example 3-10 provides an illustration of this guidance.

2.3.3.1 Considerations when debt is not accounted for at fair value

Relevant guidance: ASC 470-50-40-1 through 40-2, ASC 470-50-40-3 and ASC 470-50-40-13

Depending on the facts and circumstances surrounding the extinguishment of a loan, the borrower may be required to separately recognize a gain or loss in the period of the extinguishment (i.e., recognition of a gain or loss upon a loan extinguishment is not deferred to future periods). The gain or loss is calculated as the difference between the loan's reacquisition price (as defined below) and its net carrying amount.

The loan's reacquisition price is the amount paid to extinguish (settle) the loan, which includes any call premium or costs of reacquisition. If the loan is extinguished through the direct exchange of a new loan (i.e., the borrower replaces its existing loan for a new loan with the same lender), the old loan's reacquisition price is the present value of the new loan's cash flows. When there are incremental borrowings in the new loan, the reacquisition price of the old loan should be equivalent to the new loan's fair value less the fair value of those incremental borrowings. If a loan is extinguished early through the borrower's issuance of common or preferred stock to the lender, the more clearly evident of the issued stock's fair value or the loan's fair value should be used as the reacquisition price.

The loan's net carrying amount is: (a) the amount due at maturity (including any accrued but unpaid interest), (b) plus (minus) any related unamortized debt premium (discount) and (c) minus any related unamortized debt issuance costs.

Although ASC 470-50-40-2 only states that the gain or loss on extinguishment of debt should be "identified as a separate item" of income, we believe that presenting the gain or loss as a separate line item in the income statement is generally appropriate. However, we also believe that presenting the extinguishment gain or loss within interest expense may also be acceptable if the amount is disclosed parenthetically on the income statement or in the notes accompanying the financial statements.

If a loan is extinguished at maturity under the terms and conditions agreed to at issuance (i.e., no early extinguishment, no modification of terms, etc.) and all accrued interest has been paid, the reacquisition price of the loan would typically be the amount of the principal repayment. In addition, a gain or loss on extinguishment would normally not exist in this situation because the principal repayment and the net carrying amount of the loan would be the same.

To the extent the borrower and lender are related parties, consideration should be given to whether the extinguishment of a loan is effectively a capital transaction between the parties.

Commentary: A common related-party relationship involving a borrower and a lender is when the lender is also an equity holder in the borrower. If extinguishment accounting is applied to changes in a loan with a lender that is also an equity holder, consideration must be given to whether any gain or loss that results from applying extinguishment accounting should be reflected in the income statement or in equity (e.g., additional paid-in capital).

When the extinguishment accounting model results in a loss, we believe the loss should only be recorded in equity if all of the equity holders were also holders of the debt that was extinguished, as this situation is akin to a dividend.

When the extinguishment accounting model results in a gain, a key consideration related to whether the gain should be reflected in equity is whether the substance of the transaction is an equity contribution in which the lender is modifying or exchanging the loan to protect its equity investment in the borrower. If so, that would provide a strong indication that the gain on extinguishment should be reflected in equity. When determining whether the lender is protecting its equity investment in the borrower, consideration should be given to the facts and circumstances of each specific transaction, including:

- The role of the related party lender/equity investor in the transaction



- The reason the lender agreed to the extinguishment of the debt that resulted in a gain to the borrower
- The substance of the transaction
- The significance of the lender's equity investment in the borrower
- Whether the debt was extinguished based on current market terms
- Whether other lenders' debt was extinguished in the same manner and whether those lenders are also equity holders

While there is no authoritative guidance that specifically addresses this issue, we believe that if all lenders involved in the extinguishment also have an equity investment in the borrower, any gain recognized in connection with the extinguishment should generally be reflected in equity. However, the substance of the transaction and the specific facts and circumstances must be considered, and judgment will be required in making the final determination. The above considerations are generally consistent with [remarks by Sagar S. Teotia at the 2010 AICPA National Conference on Current SEC and PCAOB Developments](#) in which it was concluded that, based on the substance of the transaction and the specific facts and circumstances, a gain from the extinguishment of debt that was held by a shareholder should be considered a capital contribution from a related party and recognized in equity. Conversely, if there are lenders with significant loans involved in the extinguishment that do not also have an equity investment in the borrower and agree to the same terms as lenders with an equity investment, we believe that any gain recognized in connection with the extinguishment should generally be reflected in the income statement.

2.3.3.2 Considerations when debt is accounted for at fair value

Relevant guidance: ASC 470-50-40-2A

The borrower may have elected the fair value option to account for its debt in accordance with ASC 815-15 or ASC 825-10. When that is the case, and the borrower extinguishes the debt early, the carrying amount of the debt and its fair value on the extinguishment date should be the same. As such, unlike when debt is not accounted for at fair value, there is no difference between the carrying amount of the debt and its reacquisition price for which to recognize a gain or loss. However, to the extent there is a cumulative gain or loss reflected in other comprehensive income related to changes in the credit risk of the debt (see ASC 825-10-45-6), the borrower should reclassify that gain or loss from other comprehensive income to net income.

2.3.3.3 Extinguishment accounting for a modification or exchange of loans

Relevant guidance: ASC 470-50-40-13

When extinguishment accounting is applied to a modification or exchange of loans, the loan that remains after the modification, or the loan received in the exchange, should be recognized at its fair value. The fair value is also used to determine the debt extinguishment gain or loss to be recognized and the effective interest rate of the new loan.

Commentary: Applying extinguishment accounting to the modification or exchange of loans requires the borrower to determine the fair value of the new loan (i.e., the loan that remains after the modification or the loan that is received in the exchange).

GAAP defines the fair value of a liability as the price that would be paid to transfer the liability in an orderly transaction between market participants at the measurement date. Under the fair value measurement principles of ASC 820, the liability is assumed to continue (i.e., it is not settled or extinguished), and the market participant to whom the liability is transferred would be required to fulfill the obligation. Nonperformance risk (i.e., the risk that an obligation will not be fulfilled, which includes a reporting entity's own credit risk) is also assumed to remain unchanged before and after the transfer, implying that the liability is hypothetically transferred to a market participant of equal credit standing.

The fair value of a liability is not based on the price to settle a liability with the existing counterparty, but rather to transfer it to a market participant of equal credit standing (i.e., equal credit standing as the



current debtor). Consequently, this affects the assumptions about the principal (or most advantageous) market and the market participants in the exit market for the liability.

When available, the fair value of a liability should be measured using the quoted price in an active market for the identical liability held by another party as an asset. Although there is a public market for debt securities, for most middle-market borrowers, a quoted price for the liability being measured will not be available. Absent a quoted price for an identical or similar liability, ASC 820 indicates the fair value of a liability should be measured from the perspective of a market participant that holds the identical instrument as an asset at the measurement date. As with all fair value measurements, inputs used to determine the fair value of a liability from the perspective of a market participant that holds the identical instrument as an asset must be prioritized in accordance with the fair value hierarchy. Absent quoted prices for the identical instrument held as an asset, other valuation approaches, including the income or market approaches, would be used to determine the liability's fair value.

Guidance on measuring the fair value of liabilities is included in ASC 820-10-35. When faced with the challenge of determining the fair value of a new loan, the borrower should consider engaging the assistance of a qualified valuation specialist.

2.3.4 Modification accounting model

Relevant guidance: ASC 470-50-40-14 through 40-15

There is no gain or loss recognized in the income statement under the modification accounting model. Instead, modification accounting requires the calculation of a new effective interest rate for the modified loan.

In determining the new effective interest rate, the old loan's carrying amount is adjusted for any increase in the fair value of an embedded conversion option. The adjustment increases any related debt discount or decreases any related debt premium. As a result, the carrying amount of the loan decreases and additional paid-in capital increases. Conversely, a decrease in the fair value of an embedded conversion option does not result in an adjustment to the loan's carrying amount or additional paid-in capital. For purposes of determining whether the fair value of an embedded conversion option has increased or decreased, the fair values of the option right before and right after the modification or exchange are compared to each other.

Additionally, any new lender fees paid at closing should also be considered in the determination of the new effective interest rate (see [Section 2.3.5](#)).

2.3.5 Accounting for fees and costs incurred

Relevant guidance: ASC 470-50-40-17 through 40-18A

How a borrower accounts for fees and costs involved in an exchange or modification of loans depends on: (a) whether the fees and costs are between the borrower and lender or between the borrower and a third party (e.g., the borrower's legal counsel) and (b) whether extinguishment or modification accounting is applied to the exchange or modification:

| If borrower applies... | Fees between borrower and lender are... | Costs incurred with third parties are... | Unamortized debt discount, premium and issuance costs on old loan are... |
|---------------------------|--|---|--|
| Extinguishment accounting | Expensed | Deferred as debt issuance costs and amortized over the term of the new loan | Expensed |
| Modification accounting | Deferred as a debt discount or reduction of debt premium (as appropriate) and amortized over the term of the modified loan | Expensed | Continue to be amortized over the term of the modified loan (Note 1) |

Note 1: Refer to the commentary later in this section

Fees between the borrower and lender when the borrower is required to apply the extinguishment accounting model are included in the calculation of the gain or loss on extinguishment. Such fees are deemed to be related to extinguishing the old loan. Fees between the borrower and lender when the borrower is required to apply the modification accounting model are not expensed. Such fees are deemed to be related to the modified loan and should be recognized in interest expense over the remaining term of the modified loan. If there is a debt premium for the loan at the time of the modification, then the fees between the borrower and lender reduce the debt premium. Otherwise (i.e., there is a debt discount or there is neither a debt premium nor a debt discount for the loan at the time of the modification), the fees between the borrower and lender are recorded as a debt discount. Debt waiver fees are an example of a fee paid by the borrower to the lender for which the accounting depends on whether the borrower is required to apply extinguishment or modification accounting (see [Section 2.3.6](#) for additional discussion). Additionally, increases or decreases in the fair value of the borrower's freestanding equity-classified written call options held by the lender that were modified or exchanged either as a part of or directly related to the debt modification are accounted for as fees between the borrower and the lender.

Designation of fees by the lender as being related to the old loan or new loan does not influence the accounting for those fees. The model applied to the fees follows the accounting model used for the modification or exchange itself. As such, the accounting guidance on this subject determines whether the fees are in substance related to the old loan or new loan.

Costs incurred with third parties when the borrower is required to apply extinguishment accounting are recognized as debt issuance costs and amortized to expense over the term of the new loan. Deferred debt issuance costs are presented with any debt discount as a contra-liability on the balance sheet. Costs incurred with third parties when the borrower is required to apply modification accounting are expensed as incurred. Additionally, increases (but not decreases) in the fair value of freestanding equity-classified written call options held by a third party that were modified or exchanged either as a part of or directly related to the debt modification are accounted for as fees between the borrower and third parties.

Commentary: When the modification accounting model is applied to a loan modification in which there was a partial paydown of principal in connection with a prepayment option, we believe the borrower may choose one of the following accounting policies to account for the unamortized debt discount, premium and issuance costs related to the old loan:

1. Leave those unamortized amounts on its balance sheet and continue to amortize them over the term of the new loan (based on a literal application of the guidance in the table at the beginning of this section on the treatment of these amounts under modification accounting) or
2. Write off a portion of those unamortized amounts in proportion to the partial paydown and continue to amortize the remaining portion over the term of the new loan.



When a borrower makes a partial paydown of principal that is not part of a loan modification and for which there was an existing prepayment option, we believe that the borrower must apply the guidance in (2) above.

This accounting policy election does not affect the borrower otherwise being required to: (a) defer and amortize all fees charged to the borrower by the lender to change the debt and reflecting those fees in a debt discount or as a reduction of debt premium (as appropriate) (i.e., none of these fees may be expensed) and (b) expense all costs incurred with third parties (i.e., none of these expenses may be capitalized).

2.3.5.1 Borrower pays lender's third-party service providers


In some cases, the borrower may agree to directly pay the lender's third-party service providers (e.g., its external legal counsel) for the services provided to the lender in connection with the exchange or modification of a loan, or the lender may agree to directly pay the borrower's third-party service providers for services provided to the borrower in connection with the exchange or modification of a loan. The appropriate characterization of these payments by the borrower is important, given the different accounting treatment afforded fees between the borrower and the lender and costs incurred with third parties. If the third-party service provider's fees are charges for services provided to the lender, we believe those fees should be characterized as fees between the borrower and lender for accounting purposes because that is consistent with their substance. We believe this is the appropriate characterization regardless of whether those fees are: (a) billed directly to the borrower by the third-party service provider or (b) billed to the lender by the third-party service provider and ultimately paid by the borrower based on payment instructions provided by the lender to the borrower. If the third-party service provider's fees are charges for services provided to the borrower, we believe those fees should be characterized as third-party costs for accounting purposes because that is consistent with their substance. We believe this is the appropriate characterization regardless of whether those fees are paid directly by the borrower or paid by the lender on the borrower's behalf.

Consider the following situation. The lender hires a law firm to provide the lender with legal counsel in connection with the modification of a loan between the lender and one of its borrowers. The lender instructs the law firm to bill the borrower directly for the legal services provided to the lender in connection with the modification. While the borrower agrees to pay the law firm directly, it is the lender that was provided the legal services. Based on these arrangements, the law firm bills the borrower \$100,000. In addition, the lender charges the borrower a fee of \$400,000 to execute the modification. In this situation, the question arises as to how the borrower should characterize, from an accounting perspective, the billings for the services provided by the law firm to the lender. Should those billings be characterized as: (a) fees between the borrower and the lender or (b) direct costs incurred with third parties? Because the law firm's fees are charges for services provided to the lender, we believe the law firm's fees should be characterized as fees between the borrower and lender for accounting purposes. In other words, the total fees charged by the lender to the borrower in connection with the loan modification are \$500,000, of which \$400,000 is billed directly by the lender and \$100,000 is billed by the law firm on the lender's behalf. In this example, the borrower is essentially acting as the lender's agent for purposes of paying the law firm for the legal services it provided to the lender. The same accounting treatment would result if \$100,000 was billed to the lender by the third-party service provider and ultimately paid by the borrower (based on payment instructions provided by the lender to the borrower) rather than billed directly to the borrower by the third-party service provider.

2.3.5.2 Fees and costs incurred in changing loans in a loan syndication

As discussed further in [Section 2.3.7](#), in a loan syndication, many lenders are individually loaning specific amounts to the borrower, and the borrower is obligated to repay each individual lender. The guidance on how to account for the modification or exchange of loans would only apply to modifications or exchanges involving the borrower and the lenders taking part in the modification or exchange. In addition, the guidance is applied separately to each loan in the syndication that is modified or exchanged.

In some cases, one of the lenders in the syndicate will act in an investment banking or underwriting capacity for purposes of coordinating the modification or exchange across all the lenders participating in it



(including itself). In those situations, we believe that the fees charged by the lender that is also acting in that capacity should be evaluated to determine the portion of the fee related to the modification or exchange of its loan and the portion representing a direct third-party cost related to the underwriting or investment banking services it is providing to coordinate the modification or exchange across all lenders taking part in it. We believe that treating the entire fee charged by the lender acting in the capacity of an underwriter or investment banker as a lender fee could result in reaching the wrong conclusions with respect to: (a) whether modification or extinguishment accounting should be applied to the changes made to that lender's individual loan and (b) whether the appropriate amount of the fee is capitalized or expensed.

2.3.6 Fees between borrower and lender trigger accounting assessment

Relevant guidance: ASC 470-50-05-4

Cash flows are inevitably affected when a borrower and lender agree to modify or exchange loans. In a more obvious sense, a loan's cash flows change if the borrower and lender agree to change the loan's principal amount, interest rate or maturity date. Perhaps less obvious are changes to a loan's cash flows when the borrower and lender exchange fees to alter other terms of the loan. For example, paying a lender a fee in connection with obtaining a debt waiver letter affects the loan's cash flows. The significance of this change in cash flows must be evaluated to determine whether applying the modification or extinguishment accounting model is appropriate. This determination then plays a part in how the fees themselves should be treated from an accounting perspective. Examples of other situations in which fees may be exchanged between a borrower and a lender include those related to changing: (a) recourse or nonrecourse features, (b) priority, (c) collateralization features, (d) guarantor and (e) option features.

2.3.6.1 Commitment fees on delayed-draw term loans


As discussed further in [Section 2.3.1.2](#), DDTLs have characteristics of both term loans and line-of-credit arrangements. A borrower will generally pay commitment fees to the lender related to a DDTL, which are based on the size of the commitment by the lender and are generally payable based on either the undrawn commitment or the total commitment. Such fees are due whether or not the debt is drawn. Therefore, these fees are consistent with fees paid on a line-of-credit arrangement. We believe, therefore, that these fees should be treated consistently with fees related to line-of-credit arrangements (see [Section 2.4](#)) and recorded as either: (a) an asset or (b) a reduction of the carrying amount of debt, but only to the extent there is a debt balance on the balance sheet when paid. Once the DDTL is drawn, we believe that the fees (related to the drawn portion) should be treated consistent with term loan fees and reflected as a reduction of the debt balance and amortized over the life of the debt using the effective interest method. To the extent that the DDTL remains undrawn, the fees should be amortized on a straight-line basis over the life of the commitment.

2.3.7 Loan participations and syndications

Relevant guidance: ASC 470-50-55-1 through 55-3

In a loan participation, one lender (i.e., the lead bank) makes a loan to the borrower and then transfers undivided interests in that loan to other banks (i.e., participating banks). For purposes of accounting for an extinguishment, modification or exchange of a loan in this situation, the lender is the lead bank and not the participating banks. As such, the guidance on how to account for the modification or exchange of loans only applies to modifications or exchanges involving the borrower and the lead bank.

In a loan syndication or public debt issuance, many lenders are individually loaning specific amounts to the borrower (the total of which is the full amount of financing sought by the borrower) and the borrower is obligated to repay each individual lender. Because there are multiple lenders, the borrower must identify which lenders are taking part in the modification or exchange. The guidance on how to account for the modification or exchange of loans only applies to modifications or exchanges involving the borrower and the lenders taking part in the modification or exchange. In addition, the guidance on how to account for the modification or exchange of loans should be applied separately to each loan in the syndication or public issuance that is modified or exchanged. For those lenders not taking part in the modification or



exchange, there is no accounting event. For example, consider a situation where there are 20 loans with 20 different lenders in a syndication. Fifteen of those loans are being changed and five of those loans are not being changed. Further to this, no fees are being paid to those five lenders. For the five loans not being changed, there are no accounting events for the borrower. For the 15 loans that are being changed, the borrower must separately consider whether the changes made to each of those loans should be accounted for using the TDR, modification or extinguishment accounting model. Depending on the facts and circumstances, the borrower may need to separately perform the concession analysis (to determine whether there is a TDR) and the 10% cash flow test for each of the 15 loans that are changed. The results of separately performing those analyses and tests could result in some of the 15 changed loans being accounted for under one model and others being accounted for under a different model.

To determine whether two or more lenders in the loan syndication or public issuance should be treated as the same lender for accounting purposes, refer to the guidance in [Section 1.1](#).

[Section 2.3.5.2](#) discusses an issue that may arise with respect to the accounting for certain fees charged by a lender when changes are made to multiple loans in the syndication.

[Example 3-11](#) illustrates the application of this guidance.



Looking forward: On April 30, 2025, the FASB issued proposed ASU, *Debt – Modifications and Extinguishments (Subtopic 470-50) and Liabilities – Extinguishments of Liabilities (Subtopic 405-20): Accounting for Debt Exchanges*. Following the comment period and initial redeliberations, the FASB decided that the repayment of an existing loan and the issuance of a new loan would be accounted for using the extinguishment accounting model and the 10% cash flow test would not need to be completed if all of the following criteria are met:

- The new debt has multiple lenders
- The old debt is repaid in accordance with its contractual terms or repurchased at market terms
- The new debt is issued at market terms

If these criteria are not met, or in other situations in which a loan is modified, the borrower must determine whether the new loan (the modified loan or the loan received in the exchange) is substantially different from the old loan (the loan before modification or the loan given up in the exchange) by performing the 10% cash flow test.

However, in March 2026, the FASB “decided to pause further deliberations on the project until it evaluates broader feedback received from the Private Company Council and the January 2025 Invitation to Comment, *Agenda Consultation*, on debt modifications and extinguishments.” As a result, a final ASU is not expected in the near term. See the FASB’s [Accounting for Debt Exchanges](#) project site for the most current developments regarding this project.

2.3.8 Third-party intermediaries

Relevant guidance: ASC 470-50-40-19 through 40-20, ASC 470-50-55-4 through 55-5 and ASC 470-50-55-7

A third-party intermediary may be involved in the efforts to modify or exchange loans. For example, an investment banker may buy back the borrower’s debt from its lenders and coordinate new debt agreements between the borrower and its lenders. Whenever a third-party intermediary is involved in a modification or exchange of loans, consideration should be given to whether the intermediary is acting as a principal or an agent.

If the intermediary is acting as an agent of the borrower, then the intermediary’s involvement in the transaction would not affect the borrower’s accounting for the modification or exchange (other than needing to account for any fees paid or payable to the intermediary). In other words, the borrower will not change their accounting treatment solely due to involving an intermediary that is acting as its agent in the modification or exchange of loans. For accounting purposes, the borrower should effectively look through

an intermediary that is acting as an agent, and any actions of the intermediary should be considered actions of the borrower. Conversely, if the third-party intermediary is a principal in the modification or exchange of a loan, then the borrower should treat the intermediary as the lender and not look through it for accounting purposes.

A full analysis of the third-party intermediary's role should be performed to determine whether it is acting as a principal or an agent. Indicators to consider in this regard are presented in the following table:

| Indicators | Principal | Agent of borrower |
|--|------------------------------|---------------------|
| Intermediary places own funds at risk? | Yes | No |
| Basis of agreement with intermediary is... | Firmly committed | Best efforts |
| Borrower directs intermediary's activities and intermediary cannot act independently | No | Yes |
| Intermediary is subject to loss on transactions entered into with lenders | Yes | No |
| Intermediary's income is based on... | Value of borrower's security | Pre-established fee |

Commentary: Legal counsel may need to be consulted when analyzing whether a third-party intermediary is acting as a principal or an agent of the borrower in the exchange or modification of loans.

2.3.9 Transactions between lenders

Relevant guidance: ASC 470-50-40-7 and ASC 470-50-55-6

To the extent there are multiple lenders involved in a loan (e.g., bonds sold to several different parties, several banks in a loan arrangement), transfers or exchanges between the lenders do not result in a modification or exchange for the borrower. The borrower is not affected in this situation unless funds pass through the borrower or an agent of the borrower. To the extent an intermediary is involved in a transfer or exchange between lenders, consideration should be given to whether the intermediary is functioning as a principal or an agent in the transfer or exchange (see [Section 2.3.8](#)). When the intermediary is functioning as a principal in a transfer or exchange between lenders, it should be considered a lender.

2.4 Modification of a line-of-credit arrangement

Relevant guidance: ASC 470-50-40-21 through 40-23, and ASC 470-50-55-10 through 55-13

A borrower often incurs direct costs (e.g., lender's fee, third-party legal costs) upon entering a line-of-credit arrangement which should be deferred and amortized over the term of the arrangement. When there is a modification or exchange involving a line-of-credit arrangement, the borrower must first determine whether the modification or exchange should be accounted for as a TDR. If not, the question arises regarding the accounting for any related preexisting unamortized deferred costs. To answer this question, the borrower must compare the borrowing capacity of the old arrangement to the borrowing capacity of the new arrangement. In addition, the borrower must also account for any direct costs incurred to execute the modification or exchange.

The borrowing capacity of the old arrangement is determined by taking the arrangement's commitment amount and multiplying it by the arrangement's remaining term at the date of the modification or exchange. The borrowing capacity of the new or modified arrangement is determined by taking the new or modified arrangement's commitment amount and multiplying it by the term of the new or modified arrangement.

For example, if the borrower has a line-of-credit arrangement whose remaining term is three years and the amount available under the line-of-credit arrangement (i.e., the commitment amount) is \$10 million, the borrowing capacity of that old line-of-credit arrangement is \$30 million (\$10 million commitment amount × 3-year remaining term).



As illustrated in the table below, accounting for the preexisting unamortized deferred costs related to the line-of-credit arrangement depends on the change in the line-of-credit arrangement's borrowing capacity, while any direct costs incurred to execute the modification or exchange are deferred and amortized over the term of the new arrangement:

| Change in borrowing capacity? | Preexisting unamortized deferred costs | Costs incurred in connection with modification |
|---|---|---|
| Increase (borrowing capacity of new arrangement is greater than the borrowing capacity of old arrangement) or no change (borrowing capacity of the new arrangement is equal to the borrowing capacity of old arrangement) | Defer and amortize over term of new arrangement | Defer and amortize over term of new arrangement |
| Decrease (borrowing capacity of new arrangement is less than borrowing capacity of old arrangement) | Write off in proportion to the decrease in borrowing capacity; for portion not written off, defer and amortize over term of new arrangement | Defer and amortize over term of new arrangement |

Any preexisting unamortized deferred costs written off as a result of applying this guidance should be reported as a separate line item in the income statement.

The amount of unamortized deferred costs at the balance-sheet date may be presented in the balance sheet as either: (a) an asset or (b) a reduction of the carrying amount of debt, but only to the extent there is a debt balance.

The above assessment should be made on a lender-by-lender basis. If a lender exits the line-of-credit arrangement completely, then all unamortized costs associated with that lender should be expensed.

An increase or decrease in the fair value of a freestanding equity-classified written call option held by a lender or a third party that was modified together with a line-of-credit arrangement held by the same lender is accounted in the same manner as fees paid in connection with the line-of-credit arrangement modification.

[Example 3-14](#) and [Example 3-15](#) illustrate the application of this guidance.

2.4.1 Modifications of undrawn delayed-draw term loan commitments

We believe the accounting guidance for modifications of line-of-credit commitments also applies to modifications of undrawn DDTL commitments.

2.5 Changing from term loan to line-of-credit and vice versa

Relevant guidance: ASC 470-50-40-21

[Section 2.3](#) discusses how to account for changes to a term loan that do not result in a TDR (term loan guidance). [Section 2.4](#) discusses how to account for changes to a line-of-credit arrangement that do not result in a TDR (line-of-credit guidance). In some cases, a borrower may replace a line-of-credit arrangement with a term loan with the same lender (i.e., a line-of-credit arrangement is converted to a term loan), or a borrower may replace a term loan with a line-of-credit arrangement with the same lender (i.e., a term loan is converted to a line-of-credit arrangement).

When the borrower replaces a line-of-credit with a term loan with the same lender (see [Section 1.1](#)), and the replacement should not be accounted for as a TDR, the line-of-credit guidance should be applied to account for that change.



Commentary: ASC 470-50 does not address how a borrower should account for the replacement of a term loan with a line-of-credit arrangement with the same lender (see [Section 1.1](#)). However, as discussed earlier in this section, the replacement of a line-of-credit arrangement with a term loan with the same lender should be accounted for using the line-of-credit arrangement guidance, which is consistent with the nature of the credit facility before it was changed. By analogy, we believe that the replacement of a term loan with a line-of-credit should be accounted for using the term loan guidance, which is consistent with the nature of the credit facility before it was changed.

2.6 Debt disclosures

Relevant guidance: ASC 470-10-50-5, ASC 505-10-50-3; for public entities SEC Regulation S-X, Rules 4-08 and 5-02

The Codification requires a relatively limited number of disclosures about an entity's borrowings. Disclosure requirements include information, in summary form, about the rights and privileges of the outstanding debt. A few of these disclosure requirements have been noted elsewhere in this guide. The SEC requires more disclosures about a public company's debt. Required disclosures for public companies include the amount of each debt instrument, the nature and interest rate, maturity date, the priority of the debt (i.e., if the debt is senior debt or subordinated debt), unused commitments related to line of credit arrangements and whether the debt is convertible. Disclosures are also required if there are any contingencies related to payments of principal or interest. Further, a public company must disclose significant changes in the authorized or outstanding debt amounts that occurred since the latest balance sheet date.

Commentary: In the absence of a specific disclosure requirement, a borrower should still consider whether the users of its financial statements would be interested in, or influenced by, information pertaining to the entity's debts. For example, even though there is not a specific requirement that calls for the disclosure of changes to a loan and whether those changes were accounted for using the modification or extinguishment accounting model, the borrower should still consider whether the users of its financial statements would find information about the changes and related accounting helpful and relevant. In general, if the user of the financial statements would be influenced by such information, then it should be disclosed. The extent of the disclosures would vary depending on the facts and circumstances.

3 Examples



Example 3-1: Liability derecognition threshold (Section 2.1.1)

Facts

Borrower and Lender entered into a debt agreement on March 31, 20X1, with the following terms:

- Principal amount is \$5 million
- Stated interest rate is 10%
- Principal is repayable in one lump sum on March 31, 20X6
- Interest is payable annually in arrears on March 31
- Term is five years
- There is no embedded conversion option
- There is a prepayment penalty of 5% if the debt is repaid prior to March 31, 20X4

Lender charged Borrower a lender fee of \$100,000 and Borrower incurred \$50,000 in third-party debt issuance costs, which was accrued, but not yet paid as of March 31, 20X1. Borrower's debt is not rated by a credit rating agency. Borrower has not elected to account for its debt using the fair value option. There are no other outstanding loans with Lender and Lender does not have an equity investment in Borrower. Borrower recognizes interest expense using the effective interest method (see Section 1.3).

Borrower records the following journal entry on March 31, 20X1:

| | Debit | Credit |
|---|-------------|-------------|
| Cash (\$5 million principal – \$100,000 lender fee) | \$4,900,000 | |
| Debt discount (\$100,000 lender fee + \$50,000 debt issuance costs) | 150,000 | |
| Debt | | \$5,000,000 |
| Payable to third party (for debt issuance costs) | | 50,000 |

In addition, Borrower determines that its effective interest rate for the purpose of recognizing interest expense over the term of the debt is approximately 10.8%. Borrower determined this by using the following inputs in a present value software tool:

- Compounding period: Annual
- Net carrying amount of the debt on March 31, 20X1: \$4,850,000 (\$5 million principal amount – \$150,000 debt discount)
- Interest payments: \$500,000 each year starting on March 31, 20X2, and ending on March 31, 20X6 (\$5 million principal amount × 10% stated interest rate)
- Principal repayment: \$5 million on March 31, 20X6

Changes are made to the debt on March 31, 20X3. The following includes a roll forward of the debt discount and the carrying amount of the debt (debt principal net of debt discount) from after its issuance on March 31, 20X1, to before it is changed on March 31, 20X3, as well as the interest expense recognized in the twelve months ending March 31, 20X2 and 20X3:

| | Debt discount | Carrying amount of debt | Interest expense |
|---|---------------|-------------------------|------------------|
| Balance on March 31, 20X1 | \$150,000 | \$4,850,000 | |
| Amortization of debt discount (\$500,000 interest payment – \$524,178 interest expense) | (24,178) | 24,178 | |
| Interest expense (\$4,850,000 × 10.8%) | | | \$524,178 |
| Balance on March 31, 20X2 | \$125,822 | \$4,874,178 | |
| Amortization of debt discount (\$500,000 interest payment – \$526,791 interest expense) | (26,791) | 26,791 | |
| Interest expense (\$4,874,178 × 10.8%) | | | \$526,791 |
| Balance on March 31, 20X3, before changes are made to the debt | \$99,031 | \$4,900,969 | |

On March 31, 20X3, Borrower decides to extinguish the debt with Lender early, but as part of the negotiation process, Borrower and Lender agree to modify the debt so that there is only a 2% prepayment penalty. Upon paying Lender the principal amount of \$5 million, a prepayment penalty of \$100,000 and the interest otherwise due on March 31, 20X3, of \$500,000, Borrower is relieved of its obligation under the debt agreement. Borrower is not experiencing financial difficulties on March 31, 20X3.

Analysis

Borrower determines that the liability derecognition threshold has been met, due to the fact that the borrower was relieved of its obligation after paying the lender and because the borrower and lender did not enter into new loans nor were there any other preexisting term loans between the borrower and the lender. As a result, the borrower records the following journal entry on March 31, 20X3:

| | Debit | Credit |
|---|-------------|-------------|
| Debt | \$5,000,000 | |
| Accrued interest payable | 500,000 | |
| Loss on early extinguishment of debt (Note 1) | 199,031 | |
| Cash | | \$5,600,000 |
| Debt discount | | 99,031 |

Note 1: \$99,031 derecognition of debt discount + \$100,000 prepayment penalty

Even though the liability derecognition threshold has been met, Borrower considers whether the changes to the debt meet the definition of a TDR for disclosure purposes. Because Borrower is not experiencing financial difficulties, it determines that the changes to the debt do not meet the definition of a TDR.



Example 3-2: TDR with modification of terms in which no gain is recognized (Section 2.2.4.3)

Facts

Borrower and Lender entered into a debt agreement on March 31, 20X1, with the following terms:

- Principal amount is \$5 million
- Stated interest rate is 10%

- Principal is repayable in one lump sum on March 31, 20X6
- Interest is payable annually in arrears on March 31
- Term is five years
- There is no embedded conversion option

Lender charged Borrower a lender fee of \$100,000 and Borrower incurred \$50,000 in third-party debt issuance costs. Borrower's debt is not rated by a credit rating agency. Borrower has not elected to account for its debt using the fair value option. There are no other outstanding loans with Lender and Lender does not have an equity investment in Borrower. Borrower recognizes interest expense using the effective interest method (see [Section 1.3](#)).

Borrower records the following journal entry on March 31, 20X1:

| | Debit | Credit |
|---|-------------|-------------|
| Cash (\$5 million principal – \$100,000 lender fee) | \$4,900,000 | |
| Debt discount (\$100,000 lender fee + \$50,000 debt issuance costs) | 150,000 | |
| Debt | | \$5,000,000 |
| Payable to third party (for debt issuance costs) | | 50,000 |

Borrower determines that its effective interest rate for the purpose of recognizing interest expense over the term of the debt is approximately 10.8%.

Changes are made to the debt on March 31, 20X3. The debt discount and carrying amount of the debt on March 31, 20X3, before the debt is changed are \$99,031 and \$4,900,969, respectively.

Due to increased competitive pressures and unexpected increases in its operating costs, Borrower is falling behind its financial projections to a significant degree, and its cash flows in recent periods are lagging significantly behind its cash flows in comparable prior periods. As such, Borrower is unable to make the interest payment required (\$500,000) on March 31, 20X3. In addition, Borrower's revised projections do not show sufficient cash flows in the remainder of 20X3 and beginning of 20X4 to support making the interest payment required on March 31, 20X4. Borrower attempts to identify other sources of financing and discovers that its financial situation severely hinders its ability to do so. In other words, other lenders are either not willing to lend to Borrower or are only willing to lend to Borrower at extremely disadvantageous terms.

On March 31, 20X3, Borrower and Lender agree to change the terms of the debt agreement in the following ways:

- Principal amount is reduced to \$4 million.
- Principal is still repayable in one lump sum; however, the due date is extended to March 31, 20X8.
- Accrued and unpaid interest of \$500,000 is forgiven.

The stated interest rate remains 10%. Borrower incurred \$50,000 in third-party costs related to making changes to the debt.

Analysis

Borrower first determines that the liability derecognition threshold has not been met because it has not been relieved of its obligation under the debt, nor has it been legally released as the primary obligor under the debt.



Borrower next determines that its creditworthiness has deteriorated and that it is experiencing financial difficulties for the following reasons:

- It has fallen behind its financial projections to a significant degree.
- Its cash flows in recent periods are lagging significantly behind its cash flows in comparable prior periods.
- It is not able to service its debt because it cannot make the interest payment that was otherwise required on March 31, 20X3.
- Its revised projections do not show sufficient cash flows in the remainder of 20X3 and beginning of 20X4 to support making the interest payment required on March 31, 20X4.
- Other lenders are either not willing to lend to it or are only willing to lend to it at extremely disadvantageous terms.

Borrower next calculates the effective interest rate on the changed debt (for the purpose of determining whether Lender has granted it a concession) to be approximately 2.5% by using the following inputs in a present value software tool:

- Compounding period: Annual
- Net carrying amount of the debt on March 31, 20X3: \$5,400,969 (\$4,900,969 carrying amount of the debt prior to the changes + \$500,000 of accrued and unpaid interest)
- Interest payments: \$400,000 each year starting on March 31, 20X4, and ending on March 31, 20X8 (\$4 million principal amount after the changes × 10% stated interest rate)
- Principal repayment: \$4 million after the changes on March 31, 20X8

Borrower determines that Lender has granted a concession because the effective interest rate on the debt after the restructuring of 2.5% is less than the effective interest rate on the debt before the restructuring of 10.8%.

Because Borrower is experiencing financial difficulties and Lender has granted a concession, Borrower concludes it should account for the changes to the debt as a TDR. To properly account for the changes to the debt as a TDR, Borrower must first determine whether the total cash outflows required under the restructured debt are more or less than the current carrying amount of the debt. Borrower determines that the total cash outflows required under the restructured debt are \$6 million, which consists of repaying principal in the amount of \$4 million and making five annual interest payments of \$400,000 (\$4 million principal amount × 10% stated interest rate). Because total cash outflows expected under the restructured debt (\$6 million) are greater than the carrying amount of the debt prior to the restructuring (\$5,400,969), Borrower concludes that no gain results from the TDR.

As such, Borrower records the following journal entry on March 31, 20X3, to expense the third-party costs incurred in conjunction with the restructuring and reclassify the accrued interest to include it in the carrying amount of the debt:



| | Debit | Credit |
|--------------------------|-----------|-----------|
| Accrued interest payable | \$500,000 | |
| Other expense (Note 1) | 50,000 | |
| Debt | | \$500,000 |
| Payable to third party | | 50,000 |

Note 1: Direct costs incurred with third parties in connection with a TDR are expensed as incurred (see [Section 2.2.5](#))

On a going-forward basis, Borrower recognizes interest expense using the effective interest rate on the debt after the restructuring of 2.5% and recognizes the difference between interest paid and interest expense as a reduction of the debt's carrying amount.

Commentary

It is important to note that the carrying amount of the debt was not reduced on the date the debt was changed to reflect the \$1 million of principal and \$500,000 of accrued and unpaid interest forgiven by Lender. Instead, in accordance with [Section 2.2.4.3](#), those forgiven amounts are removed from the debt's carrying amount as a result of recognizing interest expense at a rate of 2.5% while paying interest at a rate of 10%. Provided below is an amortization table for the debt (assuming no further changes are made to the debt), which illustrates the reduction in principal over time to remove the forgiven amounts from the carrying amount of the debt:

| | March 31 | | | | |
|--|-------------|-------------|-------------|-------------|-------------|
| | 20X4 | 20X5 | 20X6 | 20X7 | 20X8 |
| Interest expense (beginning carrying amount × 2.5%) | \$133,300 | \$126,718 | \$119,973 | \$113,061 | \$105,979 |
| Interest payment (\$4 million × 10%) | \$400,000 | \$400,000 | \$400,000 | \$400,000 | \$400,000 |
| Beginning carrying amount of debt | \$5,400,969 | \$5,134,269 | \$4,860,987 | \$4,580,960 | \$4,294,021 |
| Reduction in carrying amount of debt (interest payment – interest expense) | (266,700) | (273,282) | (280,027) | (286,939) | (294,021) |
| Principal repayment | | | | | (4,000,000) |
| Ending carrying amount of debt | \$5,134,269 | \$4,860,987 | \$4,580,960 | \$4,294,021 | \$ - |



Example 3-3: TDR with modification of terms in which a gain is recognized ([Section 2.2.4.3](#))

Facts

Borrower and Lender entered into a debt agreement on March 31, 20X1, with the following terms:

- Principal amount is \$5 million
- Stated interest rate is 10%
- Principal is repayable in one lump sum on March 31, 20X6
- Interest is payable annually in arrears on March 31



- Term is five years
- There is no embedded conversion option

Lender charged Borrower a lender fee of \$100,000 and Borrower incurred \$50,000 in third-party debt issuance costs. Borrower's debt is not rated by a credit rating agency. Borrower has not elected to account for its debt using the fair value option. There are no other outstanding loans with Lender and Lender does not have an equity investment in Borrower. Borrower recognizes interest expense using the effective interest method (see [Section 1.3](#)).

Borrower records the following journal entry on March 31, 20X1:

| | Debit | Credit |
|---|-------------|-------------|
| Cash (\$5 million principal – \$100,000 lender fee) | \$4,900,000 | |
| Debt discount (\$100,000 lender fee + \$50,000 debt issuance costs) | 150,000 | |
| Debt | | \$5,000,000 |
| Payable to third party (for debt issuance costs) | | 50,000 |

Borrower determines that its effective interest rate for the purpose of recognizing interest expense over the term of the debt is approximately 10.8%.

Changes are made to the debt on March 31, 20X3. The debt discount and carrying amount of the debt on March 31, 20X3, before the debt is changed are \$99,031 and \$4,900,969, respectively.

Due to increased competitive pressures and unexpected increases in its operating costs, Borrower is falling behind its financial projections to a significant degree, and its cash flows in recent periods are lagging significantly behind its cash flows in comparable prior periods. As such, Borrower is unable to make the interest payment required (\$500,000) on March 31, 20X3. In addition, Borrower's revised projections do not show sufficient cash flows in the remainder of 20X3 and beginning of 20X4 to support making the interest payment required on March 31, 20X4. Borrower attempts to identify other sources of financing and discovers that its financial situation severely hinders its ability to do so. In other words, other lenders are either not willing to lend to Borrower or are only willing to lend to Borrower at extremely disadvantageous terms.

On March 31, 20X3, Borrower and Lender agree to change the terms of the debt agreement in the following ways:

- Principal amount is reduced to \$3.5 million.
- Principal is still repayable in one lump sum; however, the due date is extended to March 31, 20X8.
- Accrued and unpaid interest of \$500,000 is forgiven.

The stated interest rate remains 10%. Borrower incurred \$50,000 in third-party costs related to making changes to the debt.

Analysis

Borrower first determines that the liability derecognition threshold has not been met because it has not been relieved of its obligation under the debt nor has it been legally released as the primary obligor under the debt.

Borrower next determines that its creditworthiness has deteriorated and that it is experiencing financial difficulties for the following reasons:

- It has fallen behind its financial projections to a significant degree.
- Its cash flows in recent periods are lagging significantly behind its cash flows in comparable prior periods.



- It is not able to service its debt because it cannot make the interest payment that was otherwise required on March 31, 20X3.
- Its revised projections do not show sufficient cash flows in the remainder of 20X3 and beginning of 20X4 to support making the interest payment required on March 31, 20X4.
- Other lenders are either not willing to lend to it or are only willing to lend to it at extremely disadvantageous terms.

Borrower next calculates the effective interest rate on the changed debt (for the purpose of determining whether Lender has granted it a concession) to be approximately -0.7% by using the following inputs in a present value software tool:

- Compounding period: Annual
- Net carrying amount of the debt on March 31, 20X3: \$5,400,969 (\$4,900,969 carrying amount of the debt prior to the changes + \$500,000 of accrued and unpaid interest)
- Interest payments: \$350,000 each year starting on March 31, 20X4, and ending on March 31, 20X8 (\$3,500,000 principal amount after the changes × 10% stated interest rate)
- Principal repayment: \$3,500,000 after the changes on March 31, 20X8

Borrower determines that Lender has granted a concession because the effective interest rate on the debt after the restructuring of -0.7% is less than the effective interest rate on the debt before the restructuring of 10.8%.

Because Borrower is experiencing financial difficulties and Lender has granted a concession, Borrower concludes it should account for the changes to the debt as a TDR. To properly account for the changes to the debt as a TDR, Borrower must first determine whether the total cash outflows required under the restructured debt are more or less than the current carrying amount of the debt. Borrower determines that the total cash outflows required under the restructured debt are \$5.25 million, which consists of repaying principal in the amount of \$3.5 million and making five annual interest payments of \$350,000 (\$3,500,000 principal amount × 10% stated interest rate). Because total cash outflows expected under the restructured debt (\$5.25 million) are less than the carrying amount of the debt prior to the restructuring (\$5,400,969), Borrower concludes that a gain should be recognized for the TDR. As a result, Borrower records the following journal entry on March 31, 20X3, to account for the restructuring:

| | Debit | Credit |
|--------------------------|-----------|-----------|
| Accrued interest payable | \$500,000 | |
| Debt discount (Note 1) | 150,969 | |
| Debt | | \$500,000 |
| Gain on TDR (Note 2) | | 100,969 |
| Payable to third party | | 50,000 |

Note 1: \$5,400,969 carrying amount of the debt prior to the restructuring – \$5,250,000 total cash outflows expected under the restructured debt

Note 2: (\$5,400,969 carrying amount of the debt prior to the restructuring – \$5,250,000 total cash outflows expected under the restructured debt) – \$50,000 of third-party costs incurred in conjunction with the restructuring

After the recognition of the gain on restructuring, the adjusted carrying amount of the debt is equal to the total future cash flows (interest and principal) expected on the restructured debt. As a result, the Borrower does not recognize any future interest expense and the carrying amount of the debt is reduced by the future interest and principal payments made by the Borrower.





Example 3-4: TDR with gain recognition upon transfer of assets and modification of terms (Section 2.2.4.4)

Facts

Borrower and Lender entered into a debt agreement on March 31, 20X1, with the following terms:

- Principal amount is \$5 million
- Stated interest rate is 10%
- Principal is repayable in one lump sum on March 31, 20X6
- Interest is payable annually in arrears on March 31
- Term is five years
- There is no embedded conversion option

Lender charged Borrower a lender fee of \$100,000 and Borrower incurred \$50,000 in third-party debt issuance costs. Borrower's debt is not rated by a credit rating agency. Borrower has not elected to account for its debt using the fair value option. There are no other outstanding loans with Lender and Lender does not have an equity investment in Borrower. Borrower recognizes interest expense using the effective interest method (see Section 1.3).

Borrower records the following journal entry on March 31, 20X1:

| | Debit | Credit |
|---|-------------|-------------|
| Cash (\$5 million principal – \$100,000 lender fee) | \$4,900,000 | |
| Debt discount (\$100,000 lender fee + \$50,000 debt issuance costs) | 150,000 | |
| Debt | | \$5,000,000 |
| Payable to third party (for debt issuance costs) | | 50,000 |

Borrower determines that its effective interest rate for the purpose of recognizing interest expense over the term of the debt is approximately 10.8%.

Changes are made to the debt on March 31, 20X3. The debt discount and carrying amount of the debt on March 31, 20X3, before the debt is changed are \$99,031 and \$4,900,969, respectively.

Due to increased competitive pressures and unexpected increases in its operating costs, Borrower is falling behind its financial projections to a significant degree, and its cash flows in recent periods are lagging significantly behind its cash flows in comparable prior periods. As such, Borrower is unable to make the interest payment required (\$500,000) on March 31, 20X3. In addition, Borrower's revised projections do not show sufficient cash flows in the remainder of 20X3 and beginning of 20X4 to support making the interest payment required on March 31, 20X4. Borrower attempts to identify other sources of financing and discovers that its financial situation severely hinders its ability to do so. In other words, other lenders are either not willing to lend to Borrower or are only willing to lend to Borrower at extremely disadvantageous terms.

On March 31, 20X3, Borrower transfers a building to Lender in partial settlement of the debt, and the remaining principal amount of the debt is reduced to \$3 million. The gross carrying amount of the building and the related accumulated depreciation are \$2 million and \$500,000, respectively, for a net carrying amount of \$1.5 million. The fair value of the building at the date of transfer is \$1.8 million. Borrower and Lender also agree to change the terms of the debt agreement in the following ways:

- The remaining principal amount is still repayable in one lump sum; however, the due date is extended to March 31, 20X8.

- Accrued and unpaid interest of \$500,000 is forgiven.

The stated interest rate remains 10%. Borrower incurred \$50,000 in third-party costs related to making changes to the debt.

Analysis

Borrower first determines that the changes to the debt do not meet the liability derecognition threshold because there is continuing debt with the same lender.

Borrower next determines that its creditworthiness has deteriorated and that it is experiencing financial difficulties for the following reasons:

- It has fallen behind its financial projections to a significant degree.
- Its cash flows in recent periods are lagging significantly behind its cash flows in comparable prior periods.
- It is not able to service its debt because it cannot make the interest payment that was otherwise required on March 31, 20X3.
- Its revised projections do not show sufficient cash flows in the remainder of 20X3 and beginning of 20X4 to support making the interest payment required on March 31, 20X4.
- Other lenders are either not willing to lend to it or are only willing to lend to it at extremely disadvantageous terms.

Borrower next calculates the effective interest rate on the changed debt (for purposes of determining whether Lender has granted it a concession) to be approximately 5.3% using the following inputs in a present value software tool:

- Compounding period: Annual
- Net carrying amount of the debt on March 31, 20X3: \$3,600,969 (\$4,900,969 carrying amount of the debt prior to the changes + \$500,000 of accrued and unpaid interest – \$1,800,000 fair value of the building transferred to Lender)
- Interest payments: \$300,000 each year starting on March 31, 20X4, and ending on March 31, 20X8 (\$3 million principal amount after the changes × 10% stated interest rate)
- Principal repayment: \$3 million after the changes on March 31, 20X8

Borrower determines that Lender has granted a concession because the effective interest rate on the debt after the restructuring of 5.3% is less than the effective interest rate on the debt before the restructuring of 10.8%.

First, Borrower records the following journal entry to recognize a gain of \$300,000 for the excess of the fair value of the building (\$1.8 million) over its net carrying amount (\$1.5 million):

| | Debit | Credit |
|--------------------------------|-------------|-------------|
| Debt (Note 1) | \$1,800,000 | |
| Accumulated depreciation | 500,000 | |
| Building | | \$2,000,000 |
| Gain on transfer of a building | | 300,000 |

Note 1: Because the debt is only partially settled in the TDR, the fair value of assets transferred is used to reduce the carrying amount of the debt (see [Section 2.2.4.4](#))

Because Borrower is experiencing financial difficulties and Lender has granted a concession, Borrower concludes it should account for the changes to the debt as a TDR. To properly account for the changes to the debt as a TDR, Borrower determines whether the total cash outflows required under the restructured



debt are more or less than the carrying amount of the debt after it is reduced by the fair value of the building. Borrower determines that the total cash outflows required under the restructured debt are \$4.5 million, which consists of repaying principal in the amount of \$3 million and making five annual interest payments of \$300,000 (\$3 million principal amount × 10% stated interest rate). Because total cash outflows expected under the restructured debt (\$4.5 million) are greater than the carrying amount of the debt after it is reduced by the fair value of the building (\$3,600,969), Borrower concludes that no gain on the TDR should be recognized. As a result, Borrower records the following journal entry on March 31, 20X3, to account for the TDR:

| | Debit | Credit |
|--------------------------|-----------|-----------|
| Accrued interest payable | \$500,000 | |
| Other expense | 50,000 | |
| Debt | | \$500,000 |
| Payable to third party | | 50,000 |

On a going-forward basis, Borrower recognizes interest expense using the effective interest rate on the debt after the restructuring of 5.3% and recognizes the difference between the interest paid and interest expense as a reduction of the debt's carrying amount.



Example 3-5: TDR with loss recognition upon transfer of assets and modification of terms (Section 2.2.4.4)

Facts

Borrower and Lender entered into a debt agreement on March 31, 20X1, with the following terms:

- Principal amount is \$5 million
- Stated interest rate is 10%
- Principal is repayable in one lump sum on March 31, 20X6
- Interest is payable annually in arrears on March 31
- Term is five years
- There is no embedded conversion option

Lender charged Borrower a lender fee of \$100,000 and Borrower incurred \$50,000 in third-party debt issuance costs. Borrower's debt is not rated by a credit rating agency. Borrower has not elected to account for its debt using the fair value option. There are no other outstanding loans with Lender and Lender does not have an equity investment in Borrower. Borrower recognizes interest expense using the effective interest method (see Section 1.3).

Borrower records the following journal entry on March 31, 20X1:

| | Debit | Credit |
|---|-------------|-------------|
| Cash (\$5 million principal – \$100,000 lender fee) | \$4,900,000 | |
| Debt discount (\$100,000 lender fee + \$50,000 debt issuance costs) | 150,000 | |
| Debt | | \$5,000,000 |
| Payable to third party (for debt issuance costs) | | 50,000 |



Borrower determines that its effective interest rate for the purpose of recognizing interest expense over the term of the debt is approximately 10.8%.

Changes are made to the debt on March 31, 20X3. The debt discount and carrying amount of the debt on March 31, 20X3, before the debt is changed are \$99,031 and \$4,900,969, respectively.

Due to increased competitive pressures and unexpected increases in its operating costs, Borrower is falling behind its financial projections to a significant degree, and its cash flows in recent periods are lagging significantly behind its cash flows in comparable prior periods. As such, Borrower is unable to make the interest payment required (\$500,000) on March 31, 20X3. In addition, Borrower's revised projections do not show sufficient cash flows in the remainder of 20X3 and beginning of 20X4 to support making the interest payment required on March 31, 20X4. Borrower attempts to identify other sources of financing and discovers that its financial situation severely hinders its ability to do so. In other words, other lenders are either not willing to lend to Borrower or are only willing to lend to Borrower at extremely disadvantageous terms.

On March 31, 20X3, Borrower transfers a building to Lender in partial settlement of the debt, and the remaining principal amount of the debt is reduced to \$3 million. The gross carrying amount of the building and the related accumulated depreciation are \$2 million and \$500,000, respectively, for a net carrying amount of \$1.5 million. The fair value of the building at the date of transfer is \$1.2 million. Borrower and Lender also agree to change the terms of the debt agreement in the following ways:

- The remaining principal amount is still repayable in one lump sum; however, the due date is extended to March 31, 20X8.
- Accrued and unpaid interest of \$500,000 is forgiven.

The stated interest rate remains 10%. Borrower incurred \$50,000 in third-party costs related to making changes to the debt.

Analysis

Borrower first determines that the changes to the debt do not meet the liability derecognition threshold because there is continuing debt with the same lender.

Borrower next determines that its creditworthiness has deteriorated and that it is experiencing financial difficulties for the following reasons:

- It has fallen behind its financial projections to a significant degree.
- Its cash flows in recent periods are lagging significantly behind its cash flows in comparable prior periods.
- It is not able to service its debt because it cannot make the interest payment that was otherwise required on March 31, 20X3.
- Its revised projections do not show sufficient cash flows in the remainder of 20X3 and beginning of 20X4 to support making the interest payment required on March 31, 20X4.
- Other lenders are either not willing to lend to it or are only willing to lend to it at extremely disadvantageous terms.

Borrower next calculates the effective interest rate on the changed debt (for purposes of determining whether Lender has granted it a concession) to be approximately 1.6% using the following inputs in a present value software tool:

- Compounding period: Annual
- Net carrying amount of the debt on March 31, 20X3: \$4,200,969 (\$4,900,969 carrying amount of the debt prior to the changes + \$500,000 of accrued and unpaid interest – \$1,200,000 fair value of the building transferred to Lender)



- Interest payments: \$300,000 each year starting on March 31, 20X4, and ending on March 31, 20X8 (\$3 million principal amount after the changes × 10% stated interest rate)
- Principal repayment: \$3 million after the changes on March 31, 20X8

Borrower determines that Lender has granted a concession because the effective interest rate on the debt after the restructuring of 1.6% is less than the effective interest rate on the debt before the restructuring of 10.8%.

First, Borrower records the following journal entry to recognize a loss of \$300,000 for the excess of the building's net carrying amount (\$1.5 million) over its fair value (\$1.2 million):

| | Debit | Credit |
|--------------------------------|-------------|-------------|
| Debt (Note 1) | \$1,200,000 | |
| Accumulated depreciation | 500,000 | |
| Loss on transfer of a building | 300,000 | |
| Building | | \$2,000,000 |

Note 1: Because the debt is only partially settled in the TDR, the fair value of assets transferred is used to reduce the carrying amount of the debt (see [Section 2.2.4.4](#))

Because Borrower is experiencing financial difficulties and Lender has granted a concession, Borrower concludes it should account for the changes to the debt as a TDR. To properly account for the changes to the debt as a TDR, Borrower determines whether the total cash outflows required under the restructured debt are more or less than the carrying amount of the debt after it is reduced by the fair value of the building. Borrower determines that the total cash outflows required under the restructured debt are \$4.5 million, which consists of repaying principal in the amount of \$3 million and making five annual interest payments of \$300,000 (\$3 million principal amount × 10% stated interest rate). Because total cash outflows expected under the restructured debt (\$4.5 million) are greater than the carrying amount of the debt after it is reduced by the fair value of the building (\$4,200,969), Borrower concludes that no gain on the TDR should be recognized. As a result, Borrower records the following journal entry on March 31, 20X3, to account for the TDR:

| | Debit | Credit |
|--------------------------|-----------|-----------|
| Accrued interest payable | \$500,000 | |
| Other expense | 50,000 | |
| Debt | | \$500,000 |
| Payable to third party | | 50,000 |

On a going-forward basis, Borrower recognizes interest expense using the effective interest rate on the debt after the restructuring of 1.6% and recognizes the difference between the interest paid and interest expense as a reduction of the debt's carrying amount.



Example 3-6: Changes to prepayable debt that result in modification accounting ([Section 2.3.2.1](#))

Facts

Borrower and Lender entered into a debt agreement on March 31, 20X1, with the following terms:

- Principal amount is \$5 million
- Stated interest rate is 10%

- Principal is repayable in one lump sum on March 31, 20X6
- Interest is payable annually in arrears on March 31
- Term is five years
- Prepayment is permitted; however, there is a requirement to pay a \$150,000 penalty upon prepayment
- There are covenants that Borrower must comply with on a quarterly basis.
- There is no embedded conversion option

Lender charged Borrower a lender fee of \$100,000 and Borrower incurred \$50,000 in third-party debt issuance costs. Borrower's debt is not rated by a credit rating agency. Borrower has not elected to account for its debt using the fair value option. There are no other outstanding loans with Lender and Lender does not have an equity investment in Borrower. Borrower recognizes interest expense using the effective interest method (see [Section 1.3](#)).

Borrower records the following journal entry on March 31, 20X1:

| | Debit | Credit |
|---|-------------|-------------|
| Cash (\$5 million principal – \$100,000 lender fee) | \$4,900,000 | |
| Debt discount (\$100,000 lender fee + \$50,000 debt issuance costs) | 150,000 | |
| Debt | | \$5,000,000 |
| Payable to third party (for debt issuance costs) | | 50,000 |

Borrower determines that its effective interest rate for purposes of recognizing interest expense over the term of the debt is approximately 10.8%.

Changes are made to the debt on March 31, 20X3. The debt discount and carrying amount of the debt on March 31, 20X3, before the debt is changed are \$99,031 and \$4,900,969, respectively.

Borrower pays interest of \$500,000 (\$5 million principal × 10% stated interest rate) on March 31, 20X3, and determines that it will be in compliance with the debt covenants as of that date. However, due to planned plant expansion, Borrower does not expect to be in compliance with the debt covenants as of June 30, 20X3. As such, Borrower negotiates with Lender to change the terms to reset the debt covenants so that Borrower is expected to be in compliance as of June 30, 20X3, and throughout the remaining term of the debt. In addition to resetting the debt covenants, Borrower and Lender also agree to the following changes on March 31, 20X3:

- Extend the maturity date to March 31, 20X8
- Increase the stated interest rate to 13%

Borrower must pay a \$100,000 fee to Lender as compensation for executing the changes to the debt. In addition, Borrower incurs \$50,000 of third-party costs with its lawyers related to making these changes to the debt. The changes to the debt do not trigger the prepayment penalty. Borrower is not experiencing financial difficulties (see [Section 2.2.2.1](#)).

Analysis

Borrower first determines that the liability derecognition threshold has not been met because it has not been relieved of its obligation under the debt nor has it been legally released as the primary obligor under the debt.

Borrower next determines that the changes to the debt do not meet the definition of a TDR because it is not experiencing financial difficulties (see [Section 2.2.2.1](#)).



Lastly, Borrower must determine whether the changed debt is substantially different from the original debt by applying the 10% cash flow test (see [Section 2.3.2](#)). In doing so, Borrower must determine the present value of the original debt's remaining cash flows and the present value of the changed debt's cash flows. Because the debt is prepayable, Borrower may need to perform the 10% cash flow test assuming that the debt is prepaid and again assuming that the debt is not prepaid (see [Section 2.3.2.1](#)). If the difference in cash flows is less than 10% under the assumption that the prepayment option will be exercised, the modification accounting model should be applied, and it would not be necessary to perform the 10% cash flow test assuming non-exercise of the prepayment option.

From an efficiency perspective, since the Borrower believes that the smaller change in cash flows will result when assuming that the debt is prepaid, Borrower first applies the 10% cash flow test as of the date of the change under that assumption.

Following is the 10% cash flow test performed by Borrower assuming the debt is prepaid on March 31, 20X3 (the date the debt was changed):

| | Original debt's remaining cash flows | Changed debt's cash flows |
|---|--------------------------------------|---------------------------|
| Principal repayment | \$5,000,000 | \$5,000,000 |
| Lender fee (Note 1) | - | 100,000 |
| Interest payments (Note 2) | - | - |
| Prepayment penalty (Note 3) | 150,000 | 150,000 |
| Present value of the remaining cash flows (Notes 4 and 5) | \$5,150,000 | \$5,250,000 |
| Difference | | \$100,000 |
| % difference | | 1.9% |

Note 1: The lender fee for the original debt is not included in the test because the test uses only the original debt's remaining cash flows.

Note 2: There are no interest payments reflected in the test because: (a) the modification was made on March 31, 20X3, (b) the interest payment made on March 31, 20X3, represents interest accrued through that date, and (c) Borrower is assuming that the debt is prepaid on March 31, 20X3. In other words, no incremental amount of interest would be due upon prepayment of the debt on March 31, 20X3.

Note 3: The prepayment penalty is included in this test because this example assumes that the debt is prepaid.

Note 4: No incremental present value calculations are needed when Borrower assumes the debt is prepaid on the date the changes are made to the debt.

Note 5: The third-party costs for the original debt and changed debt are not included in the test because the test should only reflect cash flows between the borrower and the lender (see [Section 2.3.2](#)).

Assuming prepayment on March 31, 20X3, the difference between the present value of the original debt's remaining cash flows and the present value of the changed debt's cash flows is \$100,000, or 1.9% of the present value of the original debt's remaining cash flows. Because the difference is less than 10% (and an embedded conversion option is not part of the debt before or after the changes), the changes to the debt should be accounted for as a modification. Borrower does not perform the 10% cash flow test again assuming that the debt is not prepaid, because only one of the assumptions needs to result in a change in cash flows of less than 10% to result in modification accounting (see [Section 2.3.2.1](#)).



Borrower records the following journal entry to account for the modification on March 31, 20X3:

| | Debit | Credit |
|-----------------------------|-----------|-----------|
| Debt discount | \$100,000 | |
| Legal fees expense (Note 1) | 50,000 | |
| Payable to Lender | | \$100,000 |
| Payable to third party | | 50,000 |

Note 1: Third-party costs are expensed as incurred when modification accounting is applied (see [Section 2.3.5](#))

Even though the prepayment penalty was included in the 10% cash flow test under the assumption that the debt was prepaid, Borrower did not actually pay the penalty because the debt was not prepaid. As such, Borrower does not include the penalty in this journal entry.

For the purpose of accounting for the debt on a going-forward basis, Borrower calculates the effective interest rate on the changed debt to be approximately 14.2% by using the following inputs in a present value software tool:

- Compounding period: Annual
- Net carrying amount of the debt on March 31, 20X3: \$4,800,969 (\$4,900,969 carrying amount of the debt prior to the modification – \$100,000 lender fee recognized in the debt discount in conjunction with the modification)
- Interest payments: \$650,000 each year starting on March 31, 20X4, and ending on March 31, 20X8 (\$5 million principal amount × 13% stated interest rate after the changes)
- Principal repayment: \$5 million on March 31, 20X8

Borrower records the following journal entry when it makes the required interest payment on March 31, 20X4:

| | Debit | Credit |
|---------------------------|-----------|----------|
| Interest expense (Note 1) | \$680,012 | |
| Debt discount (Note 2) | | \$30,012 |
| Cash (Note 3) | | 650,000 |

Note 1: \$4,800,969 carrying amount of the debt after the modification × 14.2% effective interest rate after the modification


Note 2: \$680,012 interest expense (see Note 1) – \$650,000 interest paid (see Note 3)

Note 3: \$5 million principal amount × 13% stated interest rate after the modification

Commentary

If Borrower had not realized that it may have to consider the results of the 10% cash flow test under both the assumption that the debt is prepaid as well as the assumption that it is not prepaid, it may have reached an inappropriate conclusion that extinguishment accounting should be applied. As further illustrated in [Example 3-10](#), which is based on the same facts as this example, except prepayment is specifically prohibited under the debt both before and after the changes are made, the difference between the present value of the original debt's remaining cash flows and the present value of the changed debt's cash flows is \$606,107, or 12.4% of the present value of the original debt's remaining cash flows.

If the only change in cash flows in this example was due to Borrower paying Lender a fee solely to obtain a debt waiver letter for the expected noncompliance with the debt covenants as of June 30, 20X3 (i.e., no change to the interest rate or maturity date), that change in cash flows should still be evaluated using the 10% cash flow test to determine whether Borrower should apply the modification or extinguishment accounting model. This determination then dictates how the fee itself should be treated from an accounting perspective. To the extent payment of a fee for a debt waiver letter is accounted for as a



modification, the fee is included in the debt discount (and included in the computation of the new effective interest rate to recognize the remaining discount as interest expense over the remaining term of the loan) and any costs incurred with third parties (e.g., Borrower's legal fees) to help obtain the debt waiver letter are expensed as incurred.



Example 3-7: Changes to prepayable debt including incremental borrowings (Section 2.3.2.1)

Facts

Borrower and Lender entered into a debt agreement on March 31, 20X1, with the following terms:

- Principal amount is \$5 million
- Stated interest rate is 10%
- Principal is repayable in one lump sum on March 31, 20X6
- Interest is payable annually in arrears on March 31
- Term is five years
- Prepayment is permitted; however, there is a requirement to pay a \$150,000 penalty upon prepayment
- There are covenants that Borrower must comply with on a quarterly basis
- There is no embedded conversion option

Lender charged Borrower a lender fee of \$100,000 and Borrower incurred \$50,000 in third-party debt issuance costs. Borrower's debt is not rated by a credit rating agency. Borrower has not elected to account for its debt using the fair value option. There are no other outstanding loans with Lender and Lender does not have an equity investment in Borrower. Borrower recognizes interest expense using the effective interest method (see Section 1.3).

Borrower records the following journal entry on March 31, 20X1:

| | Debit | Credit |
|---|-------------|-------------|
| Cash (\$5 million principal – \$100,000 lender fee) | \$4,900,000 | |
| Debt discount (\$100,000 lender fee + \$50,000 debt issuance costs) | 150,000 | |
| Debt | | \$5,000,000 |
| Payable to third party (for debt issuance costs) | | 50,000 |

Borrower determines that its effective interest rate for the purpose of recognizing interest expense over the term of the debt is approximately 10.8%.

Changes are made to the debt on March 31, 20X3. The debt discount and carrying amount of the debt on March 31, 20X3, before the debt is changed are \$99,031 and \$4,900,969, respectively.

Borrower pays interest of \$500,000 (\$5 million principal × 10% stated interest rate) on March 31, 20X3, and determines that it is in compliance with the debt covenants as of that date. However, due to planned plant expansion, Borrower does not expect to be in compliance with the debt covenants as of June 30, 20X3, and throughout the remaining term of the debt. As such, Borrower negotiates with Lender to change the terms to reset the debt covenants so that Borrower is expected to be in compliance as of June 30, 20X3, and throughout the remaining term of the debt. In addition to resetting the debt covenants, Borrower and Lender also agree to the following changes on March 31, 20X3:

- Lender provides incremental borrowings of \$2 million to Borrower (which increases the debt's principal amount to \$7 million)
- Extend the maturity date to March 31, 20X8
- Increase the stated interest rate to 13%

Borrower must pay a \$100,000 fee to Lender as compensation for executing the changes to the debt. In addition, Borrower incurs \$50,000 of third-party costs with its lawyers related to making these changes to the debt. The changes to the debt do not trigger the prepayment penalty. Borrower is not experiencing financial difficulties (see [Section 2.2.2.1](#)).

Analysis

Borrower first determines that the liability derecognition threshold has not been met because it has not been relieved of its obligation under the debt nor has it been legally released as the primary obligor under the debt.

Borrower next determines that the changes to the debt do not meet the definition of a TDR because it is not experiencing financial difficulties (see [Section 2.2.2.1](#)).

Lastly, Borrower determines whether the changed debt is substantially different from the original debt by applying the 10% cash flow test (see [Section 2.3.2](#)). In doing so, Borrower must determine the present value of the original debt's remaining cash flows and the present value of the changed debt's cash flows. Because the debt is prepayable, Borrower may need to perform the 10% cash flow test assuming that the debt is prepaid and again assuming that the debt is not prepaid.

Borrower believes that the smaller change in cash flows will result when assuming that the debt is prepaid. As such, Borrower first applies the 10% cash flow test under that assumption.

Following is the 10% cash flow test performed by Borrower assuming the debt is prepaid on March 31, 20X3 (the date the debt was changed):

| | Original debt's remaining cash flows | Changed debt's cash flows |
|---|--------------------------------------|---------------------------|
| Principal repayment (Note 1) | \$5,000,000 | \$7,000,000 |
| Incremental borrowings (Note 1) | - | (2,000,000) |
| Lender fee (Note 2) | - | 100,000 |
| Interest payments (Note 3) | - | - |
| Prepayment penalty (Note 4) | 150,000 | 150,000 |
| Present value of the remaining cash flows (Notes 5 and 6) | \$5,150,000 | \$5,250,000 |
| Difference | | \$100,000 |
| % difference | | 1.9% |

Note 1: The principal repayment increased to \$7 million as a result of the incremental borrowings that were included in the changes to the debt (which are also separately reflected as cash proceeds (i.e., incremental borrowings) in the test).

Note 2: The lender fee for the original debt is not included in the test because the test uses only the original debt's remaining cash flows.

Note 3: There are no interest payments reflected in the test because: (a) the modification was made on March 31, 20X3, (b) the interest payment made on March 31, 20X3, represents interest accrued through that date,



and (c) Borrower is assuming that the debt is prepaid on March 31, 20X3. In other words, no incremental amount of interest would be due upon prepayment of the debt on March 31, 20X3.

Note 4: The prepayment penalty is included in this test because this example assumes that the debt is prepaid.

Note 5: No incremental present value calculations are needed when Borrower assumes the debt is prepaid on the date the changes are made to the debt.

Note 6: The third-party costs for the original debt and changed debt are not included in the test because the test should only reflect cash flows between the borrower and the lender (see [Section 2.3.2](#)).

Assuming prepayment on the date the debt was changed, the difference between the present value of the original debt's remaining cash flows and the present value of the changed debt's cash flows is \$100,000, or 1.9% of the present value of the original debt's remaining cash flows. Because the difference is less than 10% (and an embedded conversion option is not part of the debt before or after the changes), the changes to the debt should be accounted for as a modification. Borrower does not perform the 10% cash flow test again assuming that the debt is not prepaid, because only one of the assumptions needs to result in a change in cash flows of less than 10% to result in modification accounting.

Borrower records the following journal entry to account for the modification on March 31, 20X3:

| | Debit | Credit |
|------------------------|-------------|-------------|
| Cash (Note 1) | \$1,900,000 | |
| Debt discount | 100,000 | |
| Legal fees expense | 50,000 | |
| Debt | | \$2,000,000 |
| Payable to third party | | 50,000 |

Note 1: \$2 million incremental borrowings received – \$100,000 lender fee paid

Even though the prepayment penalty was included in the 10% cash flow test under the assumption that the debt was prepaid, Borrower did not actually pay the fee because the debt was not prepaid. As such, Borrower does not include the fee in this journal entry.

For purposes of accounting for the debt on a going-forward basis, Borrower calculates the effective interest rate on the changed debt to be approximately 13.8% by using the following inputs in a present value software tool:

- Compounding period: Annual
- Net carrying amount of the debt on March 31, 20X3: \$6,800,969 (\$4,900,969 carrying amount of the debt prior to the modification – \$100,000 lender fee recognized in the debt discount in conjunction with the modification + \$2 million of incremental borrowings)
- Interest payments: \$910,000 each year starting on March 31, 20X4, and ending on March 31, 20X8 (\$7 million principal amount after the changes × 13% stated interest rate after the changes)
- Principal repayment: \$7 million on March 31, 20X8, after the changes

Borrower records the following journal entry when it makes the required interest payment on March 31, 20X4:

| | Debit | Credit |
|---------------------------|-----------|----------|
| Interest expense (Note 1) | \$940,215 | |
| Debt discount (Note 2) | | \$30,215 |
| Cash (Note 3) | | 910,000 |

Note 1: \$6,800,969 carrying amount of the debt after the modification × 13.8% effective interest rate after the modification

Note 2: \$940,215 interest expense (see Note 1) – \$910,000 interest paid (see Note 3)



Note 3: \$7 million principal after the modification × 13% stated interest rate after the modification

Commentary

If Borrower had considered the results of the 10% cash flow test under both the assumption that the debt is prepaid as well as the assumption that it is not prepaid (see [Section 2.3.2.1](#)), it may have reached an inappropriate conclusion that extinguishment accounting should be applied. The effects that a prepayment option may have on the outcome of applying the 10% cash flow test can be observed by comparing the examples in [Example 3-6](#) and [Example 3-9](#).

The incremental borrowings had no net effect on the changed debt's cash flows used in the 10% cash flow test in this example compared to those cash flows in [Example 3-6](#) because both tests assumed the debt was prepaid. If the debt was not prepayable in this example, the incremental borrowings would have had a net effect on the changed debt's cash flows compared to those cash flows in [Example 3-6](#) because of the present value effects related to the incremental borrowings in this example being received on March 31, 20X3, and repaid (with the other \$5 million of principal) on March 31, 20X8.

It would be inappropriate in this situation for Borrower to: (a) treat the incremental borrowings as a new borrowing, (b) allocate the lender fee and third-party costs between the new borrowing and preexisting borrowing and (c) perform the 10% cash flow test on the preexisting borrowing (i.e., as if there were no incremental borrowings).



Example 3-8: Changes to prepayable DDTL ([Section 2.3.2.1](#))

Facts

Borrower and Lender entered into a DDTL on March 31, 20X1, with the following terms:

- Total DDTL commitment amount is \$7 million, of which \$5 million was drawn on March 31, 20X1
- Stated interest rate is 10%
- Principal is repayable in one lump sum on March 31, 20X6
- Interest is payable annually in arrears on March 31
- Term is five years
- Prepayment is permitted; however, there is a requirement to pay a \$150,000 penalty upon prepayment
- There are covenants that Borrower must comply with on a quarterly basis
- There is no embedded conversion option
- Commitment fee on undrawn portion of the DDTL is 0.5% of undrawn principal amount and is payable annually in arrears

Lender charged Borrower a lender fee of \$100,000 relating to the drawn portion of the DDTL and Borrower incurred \$50,000 in third-party issuance costs. Borrower's DDTL is not rated by a credit rating agency. Borrower has not elected to account for its DDTL using the fair value option. There are no other outstanding loans with Lender and Lender does not have an equity investment in Borrower. Borrower recognizes interest expense using the effective interest method (see [Section 1.3](#)).

Borrower records the following journal entry on March 31, 20X1:

| | Debit | Credit |
|---|-------------|-------------|
| Cash (\$5 million principal – \$100,000 lender fee) | \$4,900,000 | |
| Debt discount (\$100,000 lender fee + \$50,000 debt issuance costs) | 150,000 | |
| DDTL | | \$5,000,000 |
| Payable to third party (for debt issuance costs) | | 50,000 |

Borrower determines that its effective interest rate for the purpose of recognizing interest expense over the term of the DDTL is approximately 10.8%. Borrower does not consider the undrawn portion of the total DDTL commitment in the effective interest rate determination because undrawn DDTL commitments are analogous to line-of-credit arrangements (see [Section 2.4.1](#)).

Borrower pays a commitment fee of \$10,000 on the undrawn DDTL on each of March 31, 20X2, and March 31, 20X3. On March 31, 20X3, Borrower draws the remaining \$2 million of credit available under the DDTL commitment. The debt discount and carrying amount of the debt on March 31, 20X3, are \$99,031 and \$6,900,969, respectively, which includes the impact of the additional drawdown under the DDTL permitted under the terms of the original agreement. Borrower pays interest of \$500,000 (\$5 million principal × 10% stated interest rate) on March 31, 20X3, and determines that it is in compliance with the DDTL's covenants as of that date.

Changes are made to the debt on March 31, 20X3.

Due to planned plant expansion, Borrower does not expect to be in compliance with the DDTL's covenants as of June 30, 20X3. As such, Borrower negotiates with Lender to change the terms to reset the DDTL's covenants so that Borrower is expected to be in compliance as of June 30, 20X3, and throughout the remaining term of the DDTL. In addition to resetting the DDTL's covenants, Borrower and Lender also agree to the following changes on March 31, 20X3:

- Lender provides an incremental commitment of \$3 million to Borrower, which is immediately drawn (which increases the DDTL's principal amount to \$10 million)
- Extend the maturity date to March 31, 20X8
- Increase the stated interest rate to 13%

Borrower must pay a \$100,000 fee to Lender relating to the drawn portion of the DDTL as compensation for executing the changes to the DDTL. In addition, Borrower incurs \$50,000 of third-party costs with its lawyers related to making these changes to the DDTL. The changes to the DDTL do not trigger the prepayment penalty. Borrower is not experiencing financial difficulties (see [Section 2.2.2.1](#)).

Analysis

Borrower first determines that the liability derecognition threshold has not been met because it has not been relieved of its obligation under the DDTL nor has it been legally released as the primary obligor under the DDTL.

Borrower next determines that the changes to the DDTL do not meet the definition of a TDR because it is not experiencing financial difficulties (see [Section 2.2.2.1](#)).

Lastly, Borrower determines whether the changed DDTL is substantially different from the original DDTL by applying the 10% cash flow test (see [Section 2.3.2](#)). In doing so, Borrower must determine the present value of the original DDTL's remaining cash flows and the present value of the changed DDTL's cash flows. Because the DDTL is prepayable, Borrower may need to perform the 10% cash flow test assuming that the DDTL is prepaid and again assuming that the DDTL is not prepaid.



Borrower believes that the smaller change in cash flows will result when assuming that the DDTL is prepaid. As such, Borrower first applies the 10% cash flow test under that assumption.

Following is the 10% cash flow test performed by Borrower assuming the DDTL is prepaid on March 31, 20X3 (the date the DDTL was changed):

| | Original DDTL's remaining cash flows | Changed DDTL's cash flows |
|---|--------------------------------------|---------------------------|
| Principal repayment (Note 1) | \$7,000,000 | \$10,000,000 |
| Incremental borrowings (Note 1) | - | (3,000,000) |
| Lender fee (Note 2) | - | 100,000 |
| Interest payments (Note 3) | - | - |
| Prepayment penalty (Note 4) | 150,000 | 150,000 |
| Present value of the remaining cash flows (Notes 5 and 6) | \$7,150,000 | \$7,250,000 |
| Difference | | \$100,000 |
| % difference | | 1.4% |

Note 1: The drawdown of the remaining \$2 million available under the DDTL immediately prior to modification, which increases the principal repayment amount to \$7 million, is included in the original DDTL's remaining cash flows, as such drawdown was pursuant to the DDTL's original terms. The principal repayment increased to \$10 million as a result of the \$3 million of incremental borrowings that were included in the changes to the DDTL (which are also separately reflected as cash proceeds (i.e., incremental borrowings) in the test).

Note 2: The lender fee for the original DDTL is not included in the test because the test uses only the original DDTL's remaining cash flows, including the additional \$2 million borrowed pursuant to the original terms.

Note 3: There are no interest payments reflected in the test because: (a) the modification was made on March 31, 20X3, (b) the interest payment made on March 31, 20X3, represents interest accrued through that date, and (c) Borrower is assuming that the debt is prepaid on March 31, 20X3. In other words, no incremental amount of interest would be due upon prepayment of the debt on March 31, 20X3.

Note 4: The prepayment penalty is included in this test because this example assumes that the debt is prepaid.

Note 5: No incremental present value calculations are needed when Borrower assumes the debt is prepaid on the date the changes are made to the debt.

Note 6: The third-party costs for the original debt and changed debt are not included in the test because the test should only reflect cash flows between the borrower and the lender (see [Section 2.3.2](#)).

Assuming prepayment on the date the debt was changed, the difference between the present value of the original debt's remaining cash flows and the present value of the changed debt's cash flows is \$100,000, or 1.4% of the present value of the original debt's remaining cash flows. Because the difference is less than 10% (and an embedded conversion option is not part of the debt before or after the changes), the changes to the debt should be accounted for as a modification. Borrower does not perform the 10% cash flow test again assuming that the debt is not prepaid, because only one of the assumptions needs to result in a change in cash flows of less than 10% to result in modification accounting.



Borrower records the following journal entry to account for the modification on March 31, 20X3:

| | Debit | Credit |
|------------------------|-------------|-------------|
| Cash (Note 1) | \$2,900,000 | |
| Debt discount | 100,000 | |
| Legal fees expense | 50,000 | |
| Debt | | \$3,000,000 |
| Payable to third party | | 50,000 |

Note 1: \$3 million incremental borrowings received – \$100,000 lender fee paid

Even though the prepayment penalty was included in the 10% cash flow test under the assumption that the debt was prepaid, Borrower did not actually pay the fee because the debt was not prepaid. As such, Borrower does not include the fee in this journal entry.

For purposes of accounting for the debt on a going-forward basis, Borrower calculates the effective interest rate on the changed debt to be approximately 13.6% by using the following inputs in a present value software tool:

- Compounding period: Annual
- Net carrying amount of the debt on March 31, 20X3: \$9,800,969 (\$6,900,969 carrying amount of the debt prior to the modification – \$100,000 lender fee recognized in the debt discount in conjunction with the modification + \$3 million of incremental borrowings)
- Interest payments: \$1,300,000 each year starting on March 31, 20X4, and ending on March 31, 20X8 (\$10 million principal amount (\$7 million plus \$3 million incremental borrowings) × 13% stated interest rate after the changes)
- Principal repayment: \$10 million on March 31, 20X8, after the changes

Borrower records the following journal entry when it makes the required interest payment on March 31, 20X4:

| | Debit | Credit |
|---------------------------|-------------|-----------|
| Interest expense (Note 1) | \$1,330,366 | |
| Debt discount (Note 2) | | \$30,366 |
| Cash (Note 3) | | 1,300,000 |

Note 1: \$9,800,969 carrying amount of the DDTL after the modification × 13.6% effective interest rate after the modification

Note 2: \$1,330,366 interest expense (see Note 1) – \$1,300,000 interest paid (see Note 3)

Note 3: \$10 million principal after the modification × 13% stated interest rate after the modification.



Example 3-9: Changes to prepayable debt with partial repayment of principal (Section 2.3.2.1)

Facts

Borrower and Lender entered into a debt agreement on March 31, 20X1, with the following terms:

- Principal amount is \$5 million
- Stated interest rate is 10%
- Principal is repayable in one lump sum on March 31, 20X6

- Interest is payable annually in arrears on March 31
- Term is five years
- Prepayment is permitted; however, there is a requirement to pay a \$150,000 penalty upon prepayment
- There are covenants that Borrower must comply with on a quarterly basis
- There is no embedded conversion option

Lender charged Borrower a lender fee of \$100,000 and Borrower incurred \$50,000 in third-party debt issuance costs. Borrower's debt is not rated by a credit rating agency. Borrower has not elected to account for its debt using the fair value option. There are no other outstanding loans with Lender and Lender does not have an equity investment in Borrower. Borrower recognizes interest expense using the effective interest method (see [Section 1.3](#)).

Borrower records the following journal entry on March 31, 20X1:

| | Debit | Credit |
|---|-------------|-------------|
| Cash (\$5 million principal – \$100,000 lender fee) | \$4,900,000 | |
| Debt discount (\$100,000 lender fee + \$50,000 debt issuance costs) | 150,000 | |
| Debt | | \$5,000,000 |
| Payable to third party (for debt issuance costs) | | 50,000 |

Borrower determines that its effective interest rate for the purpose of recognizing interest expense over the term of the debt is approximately 10.8%.

Changes are made to the debt on March 31, 20X3. The debt discount and carrying amount of the debt on March 31, 20X3, before the debt is changed are \$99,031 and \$4,900,969, respectively.

Borrower pays interest of \$500,000 (\$5 million principal × 10% stated interest rate) on March 31, 20X3, and determines that it is in compliance with the debt covenants as of that date. However, due to planned plant expansion, Borrower does not expect to be in compliance with the debt covenants as of June 30, 20X3. As such, Borrower negotiates with Lender to change the terms to reset the debt covenants so that Borrower is expected to be in compliance as of June 30, 20X3, and throughout the remaining term of the debt. In addition to resetting the debt covenants, Borrower and Lender also agree to the following changes on March 31, 20X3:

- Borrower repays \$1 million of principal (which reduces the debt's principal amount to \$4 million)
- Extend the maturity date to March 31, 20X8
- Increase the stated interest rate to 13%

While Lender agreed to waive (in this one instance only) the prepayment penalty that would otherwise be due from Borrower in connection with its prepayment of \$1 million principal, Borrower must pay a \$100,000 fee to Lender as compensation for executing the changes to the debt. In addition, Borrower incurs \$50,000 of third-party costs with its lawyers related to making these changes to the debt. Borrower is not experiencing financial difficulties (see [Section 2.2.2.1](#)).

Analysis

Borrower first determines that the changes to the debt do not meet the liability derecognition threshold because there is continuing debt with the same lender.

Borrower next determines that the changes to the debt do not meet the definition of a TDR because it is not experiencing financial difficulties.



Lastly, Borrower determines whether the changed debt is substantially different from the original debt by applying the 10% cash flow test (see [Section 2.3.2](#)). In doing so, Borrower must determine the present value of the original debt's remaining cash flows and the present value of the changed debt's cash flows. Because the debt is prepayable, Borrower may need to perform the 10% cash flow test assuming that the debt is prepaid and again assuming that the debt is not prepaid.

Borrower believes that the smaller change in cash flows will result when assuming that the debt is prepaid. As such, Borrower first applies the 10% cash flow test under that assumption.

Following is the 10% cash flow test performed by Borrower assuming the debt is prepaid on March 31, 20X3 (the date the debt was changed):

| | Original debt's remaining cash flows | Changed debt's cash flows |
|---|--------------------------------------|---------------------------|
| Principal repayment (Note 1) | \$5,000,000 | \$5,000,000 |
| Lender fee (Note 2) | - | 100,000 |
| Interest payments (Note 3) | - | - |
| Prepayment penalty (Note 4) | 150,000 | 150,000 |
| Present value of the remaining cash flows (Notes 5 and 6) | \$5,150,000 | \$5,250,000 |
| Difference | | \$100,000 |
| % difference | | 1.9% |

- Note 1:** Although the Borrower prepaid only \$1 million in connection with making changes to the debt, for purposes of applying the 10% cash flow test, it is assumed that the entire principal amount outstanding prior to the date the changes were made to the debt (\$5 million) is prepaid (see [Section 2.3.2.1](#)).
- Note 2:** The lender fee for the original debt is not included in the test because the test uses only the original debt's remaining cash flows.
- Note 3:** There are no interest payments reflected in the test because: (a) the modification was made on March 31, 20X3, (b) the interest payment made on March 31, 20X3, represents interest accrued through that date, and (c) Borrower is assuming that the debt is prepaid on March 31, 20X3. In other words, no incremental amount of interest would be due upon prepayment of the debt on March 31, 20X3.
- Note 4:** The prepayment penalty is included in this test because this example assumes that the debt is prepaid. While Lender waived the prepayment penalty related to the prepayment of \$1 million principal on March 31, 20X3, the prepayment penalty for prepaying the debt in full was not changed.
- Note 5:** No incremental present value calculations are needed when Borrower assumes the debt is prepaid on the date the changes are made to the debt.
- Note 6:** The third-party costs for the original debt and changed debt are not included in the test because the test should only reflect cash flows between the borrower and the lender (see [Section 2.3.2](#)).

Assuming prepayment on the date the debt was changed, the difference between the present value of the original debt's remaining cash flows and the present value of the changed debt's cash flows is \$100,000, or 1.9% of the present value of the original debt's remaining cash flows. Because the difference is less than 10% (and an embedded conversion option is not part of the debt before or after the changes), the changes to the debt should be accounted for as a modification. Borrower does not perform the 10% cash flow test again assuming that the debt is not prepaid, because only one of the assumptions needs to result in a change in cash flows of less than 10% to result in modification accounting.



Borrower records the following journal entry to account for the modification on March 31, 20X3:

| | Debit | Credit |
|------------------------|-------------|-------------|
| Debt | \$1,000,000 | |
| Debt discount (Note 1) | 100,000 | |
| Legal fees expense | 50,000 | |
| Cash | | \$1,100,000 |
| Payable to third party | | 50,000 |

Note 1: Borrower's accounting policy when the modification accounting model is applied to debt for which there was a partial paydown of principal in connection with a prepayment option is to leave the preexisting unamortized debt discount on its balance sheet and continue to amortize it over the term of the changed debt. See [Section 2.3.5](#) for additional discussion.

For purposes of accounting for the debt on a going-forward basis, Borrower calculates the effective interest rate on the changed debt to be approximately 14.5% by using the following inputs in a present value software tool:

- Compounding period: Annual
- Net carrying amount of the debt on March 31, 20X3: \$3,800,969 (\$4,900,969 carrying amount of the debt prior to the modification – \$100,000 lender fee recognized in the debt discount in conjunction with the modification – \$1 million principal repayment on March 31, 20X3)
- Interest payments: \$520,000 each year starting on March 31, 20X4, and ending on March 31, 20X8 (\$4 million principal amount after the changes × 13% stated interest rate after the changes)
- Principal repayment: \$4 million after the changes on March 31, 20X8

Borrower records the following journal entry when it makes the required interest payment on March 31, 20X4:

| | Debit | Credit |
|---------------------------|-----------|----------|
| Interest expense (Note 1) | \$549,834 | |
| Debt discount (Note 2) | | \$29,834 |
| Cash (Note 3) | | 520,000 |

Note 1: \$3,800,969 carrying amount of the debt after the modification × 14.5% effective interest rate after the modification

Note 2: \$549,834 interest expense (see Note 1) – \$520,000 interest paid (see Note 3)

Note 3: \$4 million principal after the modification × 13% stated interest rate after the modification

Commentary

For purposes of determining the present value of the changed debt's cash flows, Borrower included any amounts exchanged by Borrower and Lender in connection with the changes to the debt. This included both fees paid to Lender and the principal repaid by Borrower. It is critical that the principal repayment was included in the present value of the changed debt's cash outflows. If it was not, Borrower would have inappropriately accounted for the changes to the debt as an extinguishment instead of a modification.

If Borrower had not realized that it may have to consider the results of the 10% cash flow test under both the assumption that the debt is prepaid as well as the assumption that it is not prepaid, it may have reached an inappropriate conclusion that extinguishment accounting should be applied. The effects that a prepayment option may have on the outcome of applying the 10% cash flow test can be observed by comparing this example with [Example 3-6](#).



The principal repayment had no net effect on the changed debt's cash flows used in the 10% cash flow test in this example compared to those cash flows in [Example 3-6](#) because both tests assumed the debt was prepaid. If the debt was not prepayable in this example, the principal repayment would have had a net effect on the changed debt's cash flows compared to those cash flows in [Example 3-6](#) because of the present value effects related to Borrower repaying \$1 million in principal in this example on March 31, 20X3, and repaying the remaining \$4 million of principal on March 31, 20X8.

It would be inappropriate in this situation for Borrower to split the debt into two pieces—one with a principal amount of \$1 million (to which the \$1 million principal repayment would be assigned and the extinguishment accounting model applied) and the other with a principal amount of \$4 million (on which the 10% cash flow test would be performed), with the lender fees and third-party costs allocated between the two pieces and accounted for accordingly. See [Section 2.1.2](#) for a discussion of the unit of account when there are multiple term loans with one lender.



Example 3-10: Changes to debt that result in extinguishment accounting ([Section 2.3.3](#))

Facts

Borrower and Lender entered into a debt agreement on March 31, 20X1, with the following terms:

- Principal amount is \$5 million
- Stated interest rate is 10%
- Principal is repayable in one lump sum on March 31, 20X6
- Interest is payable annually in arrears on March 31
- Term is five years
- Prepayment is prohibited
- There are covenants that Borrower must comply with on a quarterly basis
- There is no embedded conversion option

Lender charged Borrower a lender fee of \$100,000 and Borrower incurred \$50,000 in third-party debt issuance costs. Borrower's debt is not rated by a credit rating agency. Borrower has not elected to account for its debt using the fair value option. There are no other outstanding loans with Lender and Lender does not have an equity investment in Borrower. Borrower recognizes interest expense using the effective interest method (see [Section 1.3](#)).

Borrower records the following journal entry on March 31, 20X1:

| | Debit | Credit |
|---|-------------|-------------|
| Cash (\$5 million principal – \$100,000 lender fee) | \$4,900,000 | |
| Debt discount (\$100,000 lender fee + \$50,000 debt issuance costs) | 150,000 | |
| Debt | | \$5,000,000 |
| Payable to third party (for debt issuance costs) | | 50,000 |

Borrower determines that its effective interest rate for the purpose of recognizing interest expense over the term of the debt is approximately 10.8%.

Changes are made to the debt on March 31, 20X3. The debt discount and carrying amount of the debt on March 31, 20X3, before the debt is changed are \$99,031 and \$4,900,969, respectively.

Borrower pays interest of \$500,000 (\$5 million principal × 10% stated interest rate) on March 31, 20X3, and determines that it is in compliance with the debt covenants as of that date. However, due to planned plant expansion, Borrower does not expect to be in compliance with the debt covenants as of June 30, 20X3. As such, Borrower negotiates with Lender to change the terms to reset the debt covenants so that Borrower is expected to be in compliance as of June 30, 20X3, and throughout the remaining term of the debt. In addition to resetting the debt covenants, Borrower and Lender also agree to the following changes on March 31, 20X3:

- Extend the maturity date to March 31, 20X8
- Increase the stated interest rate to 13%

Borrower must pay a \$100,000 fee to Lender as compensation for executing the changes to the debt. In addition, Borrower incurs \$50,000 of third-party costs with its lawyers related to making these changes to the debt. The fair value of the changed debt on March 31, 20X3, is \$5 million. Borrower is not experiencing financial difficulties (see [Section 2.2.2.1](#)).

Analysis

Borrower first determines that the liability derecognition threshold has not been met because it has not been relieved of its obligation under the debt nor has it been legally released as the primary obligor under the debt.

Borrower next determines that the changes to the debt do not meet the definition of a TDR because it is not experiencing financial difficulties.

Lastly, Borrower determines whether the changed debt is substantially different from the original debt by applying the 10% cash flow test (see [Section 2.3.2](#)). In doing so, as prepayment is prohibited, Borrower must determine the present value of the original debt's remaining cash flows and the present value of the changed debt's cash flows by using the following inputs in a present value software tool:

| | Original debt's remaining cash flows (Note 1) | Changed debt's cash flows (Note 1) |
|---------------------|--|--|
| Compounding period | Annual | Annual |
| Lender fee | Note 2 | \$100,000 on March 31, 20X3 |
| Interest payments | \$500,000 per year starting on March 31, 20X4, and ending on March 31, 20X6 (Note 3) | \$650,000 per year starting on March 31, 20X4, and ending on March 31, 20X8 (Note 4) |
| Principal repayment | \$5 million on March 31, 20X6 | \$5 million on March 31, 20X8 |
| Discount rate | 10.8% | 10.8% |

Note 1: The third-party costs for the original debt and changed debt are not included in the test because the test should only reflect cash flows between the borrower and the lender (see [Section 2.3.2](#))

Note 2: The lender fee for the original debt is not included in the test because the test uses only the original debt's remaining cash flows

Note 3: \$5 million principal amount × 10% stated interest rate

Note 4: \$5 million principal amount × 13% stated interest rate

Using the inputs for the original debt's remaining cash flows in a present value software tool, Borrower calculates the present value of those cash flows to be \$4,900,969, which is the same as the carrying amount of the debt before the changes were made because Borrower recognizes interest expense using the effective interest rate method. Using the inputs for the changed debt's remaining cash flows in a present value software tool, Borrower calculates the present value of those cash flows to be \$5,507,076. Borrower determines that the difference in those cash flows is \$606,107, or 12.4%. Because the difference is more than 10%, the changes to the debt should be accounted for as an extinguishment (see [Section 2.3.2](#)).



Borrower records the following journal entry (shown on a gross basis for illustration purposes) to account for the extinguishment on March 31, 20X3:

| | Debit | Credit |
|---------------------------------|-------------|-------------|
| Old debt (principal) (Note 1) | \$5,000,000 | |
| Loss on extinguishment (Note 2) | 199,031 | |
| Debt discount (Note 3) | 50,000 | |
| New Debt (Note 1) | | \$5,000,000 |
| Payable to third party | | 50,000 |
| Payable to Lender | | 100,000 |
| Debt discount (Note 3) | | 99,031 |

Note 1: Under the extinguishment accounting model, the gross amount of the original debt should be derecognized and the fair value (reacquisition price) of the changed debt should be recognized

Note 2: (\$5 million reacquisition price [which is the same as the fair value of the changed debt] – \$4,900,969 carrying amount of the debt before the changes) + \$100,000 lender fee charged in conjunction with making the changes to the debt

Note 3: Reflects entries to: (a) derecognize the debt discount for the original debt (\$99,031) and (b) recognize the debt discount for the changed debt (\$50,000 of third-party costs incurred to change the debt)

On a going-forward basis, Borrower calculates a new effective interest rate on the debt and recognizes interest expense and amortizes the debt discount of \$50,000 using that rate over the remaining term of the debt.

Commentary

As illustrated in [Example 3-6](#), if this debt had been prepayable with a penalty of \$150,000, Borrower would have accounted for the changes to the debt as a modification instead of an extinguishment. This difference underscores the need for a borrower to understand whether its debt is or is not prepayable.



Example 3-11: Changes to prepayable loans in a syndication ([Section 2.3.2.1](#) and [Section 2.3.7](#))

Facts

On January 1, 20X0, Borrower obtained \$400 million of financing from a syndicated term loan in which four banks participated—Banks A, B, C and D. None of the banks should be considered the same lender for accounting purposes (see [Section 1.1](#)), and Borrower has no other outstanding loans with any of the banks. As part of the syndicated term loan, each bank entered into a loan with Borrower. The principal amount of each loan varied by lender as follows:

- Bank A: \$40 million
- Bank B: \$80 million
- Bank C: \$120 million
- Bank D: \$160 million

The following are the other terms applicable to each of the loans:

- Term is ten years
- Maturity date is December 31, 20X9 (entire principal due at maturity)
- Stated interest rate is 5.0%

- Interest is paid annually in arrears on December 31
- Prepayment is allowed without penalties
- There is no embedded conversion option in any of the loans

Lender fees and debt issuance costs incurred by Borrower in connection with obtaining the financing through the syndicated term loan were \$4 million. Borrower does not account for the loans at fair value. Borrower recognizes interest expense using the effective interest method (see [Section 1.3](#)).

In late 20X4, Borrower sold a plant for cash in the amount of \$100 million. As a result, Borrower re-assessed its financing needs and decided to modify the syndicated term loan on January 1, 20X5, as follows:

- Bank B's loan was repaid in full and Bank B no longer participates in the syndicated term loan or provides any other financing to Borrower.
- Banks A, C and D remained in the syndicated term loan with no changes to the outstanding principal amounts of \$40 million, \$120 million and \$160 million, respectively.
- The stated interest rate of each remaining loan was reduced from 5.0% to 4.75%.
- The maturity date of each remaining loan was extended five years from December 31, 20X9, to December 31, 20Y4.

As a result of these changes, the total borrowings under the modified syndicated term loan were reduced from \$400 million to \$320 million. Prior to the modification, there was \$2,278,143 in the aggregate in the debt discount related to the syndicated term loan, which was allocated to each lender using the original principal amount of each loan relative to the total original principal amount of all the loans (See table below). Borrower is not experiencing financial difficulties (see [Section 2.2.2.1](#)).

Bank A acted as the lead bank in modifying the syndicated term loan and received \$1 million in fees from Borrower. Banks C and D, who acted solely in the capacity of lenders, received fees from Borrower of \$900,000 and \$1.2 million, respectively.

Analysis

Borrower first determines that the liability derecognition threshold has been met with respect to Bank B's loan because Borrower has been relieved of its obligation under the loan as a result of having repaid the loan. However, with respect to its loans with Banks A, C and D, Borrower concludes that it has not been relieved of its obligation under any of those loans nor has it been legally released as the primary obligor under any of those loans.

Borrower next determines that a TDR has not occurred because it is not experiencing financial difficulties.

Accounting for loan with Bank B

Given that the liability derecognition threshold was met with respect to Bank B's loan when it was repaid in full, and Bank B is no longer participating in the syndicated term loan or providing any other financing to Borrower, the extinguishment accounting model is applied to Bank B's loan. Any unamortized debt discount related to Bank B's loan should be derecognized when accounting for its extinguishment. Borrower allocates the total unamortized debt discount to each of the loans in the original syndicated term loan, using the original principal amount of each loan relative to the total original principal amount of all the loans:



| | Principal | % of total principal | Allocation of preexisting debt discount |
|--------|---------------|----------------------|---|
| Bank A | \$40,000,000 | 10% | \$227,814 |
| Bank B | 80,000,000 | 20% | 455,629 |
| Bank C | 120,000,000 | 30% | 683,443 |
| Bank D | 160,000,000 | 40% | 911,257 |
| Total | \$400,000,000 | 100% | \$2,278,143 |

None of the fees paid by Borrower to the banks that remained in the modified syndicated term loan should be allocated to the extinguishment of Bank B's loan because the repayment of the loan to Bank B was pursuant to the original terms of the loan.

The following journal entry illustrates the effects that the application of the extinguishment accounting model to Bank B's loan has on Borrower's financial statements:

| | Debit | Credit |
|--------------------------------|------------|--------------|
| Loss on extinguishment of loan | \$455,629 | |
| Debt | 80,000,000 | |
| Cash | | \$80,000,000 |
| Debt discount | | 455,629 |

The loss on extinguishment of the loan should be included as a separate line on the income statement.

Accounting for loans with Banks A, C and D

Borrower must determine whether each modified loan remaining in the syndicated term loan is substantially different from the preexisting loan by applying the 10% cash flow test to each loan. For the purpose of applying that test, Borrower must determine the lender fees that should be attributable to each loan because those fees should be included in the test for each loan.

Given that Bank A is acting as the lead bank with respect to coordinating the changes to the loans remaining in the syndicated term loan, Borrower must determine how much of the fee charged by Bank A should be treated as a lender fee versus a third-party cost for accounting purposes. After performing additional research and analysis related to the fees charged by each bank, Borrower determines the following:

- Bank C's and Bank D's fees (\$900,000 and \$1.2 million, respectively) represent 0.75% of the principal amounts of their loans (\$120 million and \$160 million, respectively). Because Banks C and D are only acting in the capacity of lenders and would expect a fee commensurate with the fair value of the service they are providing, Borrower concludes that an equivalent fair-value based lender fee for Bank A's loan would be \$300,000 (\$40 million principal amount × 0.75%).
- With Bank A's assistance, Borrower determined that \$280,000 of Bank A's \$1 million fee represented out-of-pocket lending costs, such as filing fees, attorney's fees for modifying the syndicated term loan and other direct expenses, which should be treated as a lender fee for accounting purposes because they were incurred in connection with lending activities (See [Section 2.3.5.2](#)). In addition, because the \$280,000 of out-of-pocket lending costs relate to the lending activities of all three banks, they should be allocated to each bank's loan (for the purpose of the 10% cash flow test performed for each loan) based on the principal amount of each loan remaining in the modified syndicated term loan relative to the total principal amount of all the loans remaining in the modified syndicated term loan. As such, the following amount of out-of-pocket lending costs should



be allocated to each loan remaining in the modified syndicated term loan for the purpose of applying the 10% cash flow test:

| | Principal | % of total principal | Allocation of out-of-pocket lending costs |
|--------|---------------|----------------------|---|
| Bank A | \$40,000,000 | 12.5% | \$35,000 |
| Bank C | 120,000,000 | 37.5% | 105,000 |
| Bank D | 160,000,000 | 50.0% | 140,000 |
| Total | \$320,000,000 | 100% | \$280,000 |

- Borrower determines that the remaining amount of Bank A's fee of \$420,000 (\$1 million total fee – \$300,000 imputed lender fee – \$280,000 for out-of-pocket lending costs) represents compensation for the underwriting services Bank A provided in connection with its role as the lead bank and should be treated as a third-party cost for accounting purposes (see [Section 2.3.5.2](#)). Bank A has two roles in the modified syndicated term loan: one role is that of a lender and the other is that of an underwriter. If Bank A had not acted in the capacity of an underwriter, and Borrower instead hired a third party to act in that capacity, the fees paid to the third party would have been treated as a third-party cost. As such, the fees paid to Bank A for the services provided in its capacity as an underwriter should be treated as a third-party cost for accounting purposes.

Based on this analysis, Borrower determines that the lender fees associated with each bank's loan for the purpose of the 10% cash flow test is as follows:

| | Bank A | Bank C | Bank D |
|---|-----------|-------------|-------------|
| Lender fee based on 0.75% of principal amount | \$300,000 | \$900,000 | \$1,200,000 |
| Allocated out-of-pocket lending costs | 35,000 | 105,000 | 140,000 |
| Total | \$335,000 | \$1,005,000 | \$1,340,000 |

Next, Borrower must determine whether the changed loan with each lender is substantially different from the original loan with each lender by applying the 10% cash flow test (see [Section 2.3.2](#)). In doing so, Borrower must determine the present value of each original loan's remaining cash flows and the present value of each changed loan's cash flows. Because each loan is prepayable, Borrower may need to perform the 10% cash flow tests assuming that the loans are prepaid and again assuming that the loans are not prepaid.

Borrower believes that the smaller change in cash flows will result when assuming that the loans are prepaid. As such, Borrower first applies the 10% cash flow test under that assumption.



Following are the 10% cash flow tests performed by Borrower assuming the loans are prepaid on January 1, 20X5 (the date the loans were changed):

| | Bank A | Bank C | Bank D |
|---|--------------|---------------|---------------|
| Original loan's remaining cash flows, consisting of principal repayment | \$40,000,000 | \$120,000,000 | \$160,000,000 |
| Changed loan's remaining cash flows, consisting of: | | | |
| Principal repayment | \$40,000,000 | \$120,000,000 | \$160,000,000 |
| Lender fees | 335,000 | 1,005,000 | 1,340,000 |
| Total | \$40,335,000 | \$121,005,000 | \$161,340,000 |
| Difference | \$335,000 | \$1,005,000 | \$1,340,000 |
| % difference | 0.84% | 0.84% | 0.84% |

Assuming prepayment on the date the debt was changed, the difference between each original loan's remaining cash flows and each changed loan's remaining cash flows is less than 1% of the present value of each respective original loan's remaining cash flows. Because the difference is less than 10% (and an embedded conversion option is not part of any of the loans before or after the changes), the changes to each of the loans should be accounted for as a modification (see [Section 2.3.5](#)). Borrower does not need to perform the 10% cash flow test assuming that the prepayment option is not exercised, because only one of the 10% cash flow tests needs to have a change of less than 10% to result in modification accounting.

Borrower records the following journal entry to account for the modifications to its loans with Banks A, C and D on January 1, 20X5:

| | Debit | Credit |
|--------------------------------|-------------|-------------|
| Debt discount (Note 1) | \$2,680,000 | |
| Underwriting expenses (Note 2) | 420,000 | |
| Payable to Bank A | | \$3,100,000 |

Note 1: \$2,680,000 is the sum of each bank's lender fees for accounting purposes (\$335,000 for Bank A + \$1,005,000 for Bank C + \$1,340,000 for Bank D). See computation above (see [Section 2.3.5](#))

Note 2: \$420,000 of Bank A's fee represents compensation for the underwriting services Bank A provided in connection with its role as the lead bank and should be treated as a third-party cost for accounting purposes (see [Section 2.3.5.2](#))

For the purpose of accounting for the loans on a going-forward basis, Borrower calculates the effective interest rate on the changed loans to be approximately 4.9% by using the following inputs in a present value software tool:

- Compounding period: Annual
- Net carrying amount of the loans on January 1, 20X5:



| | Amount |
|---|----------------------|
| Gross debt balance prior to the modification | \$400,000,000 |
| Debt discount prior to the modification | (2,278,143) |
| Gross debt balance for Lender B derecognized on January 1, 20X5 | (80,000,000) |
| Debt discount allocated to Lender B and derecognized on January 1, 20X5 | 455,629 |
| Additional debt discount for lender fees related to the modification | (2,680,000) |
| Net carrying amount of the loans after the modification | <u>\$315,497,486</u> |

- Interest payments: \$15,200,000 each year starting on December 31, 20X5, and ending on December 31, 20Y4 (\$320 million principal amount × 4.75% stated interest rate)
- Principal repayment: \$320 million on December 31, 20Y4

Borrower records the following journal entry when it makes the required interest payment on December 31, 20X5:

| | Debit | Credit |
|---------------------------|--------------|------------|
| Interest expense (Note 1) | \$15,559,115 | |
| Debt discount (Note 2) | | \$359,115 |
| Cash (Note 3) | | 15,200,000 |

Note 1: \$315,497,486 carrying amount of the loans after the modification × 4.9% effective interest rate after the modification

Note 2: \$15,559,115 interest expense (see Note 1) – \$15,200,000 interest paid (see Note 3)

Note 3: \$320 million principal amount after the modification × 4.75% stated interest rate after the modification

Commentary

If Borrower had not appropriately considered the substance of the fees paid to Bank A, the cash flows used in the 10% cash flow test would have been misstated. In addition, the amount of those fees recognized as an expense versus additional debt discount would also have been incorrect. In other words, if Borrower assumed that all amounts paid to Bank A were a lender fee merely because Bank A was one of the lenders in the modified syndicated term loan, it would have overstated the debt discount and understated expenses by \$420,000. This example further underscores the importance of understanding the substance of payments to lenders and third-party service providers and accounting for those payments based on their substance.

Given that the terms of each lender's loan that remains in the syndicated term loan are the same before and after the syndicated term loan is modified, the effective interest rate and interest expense can be calculated in the aggregate for the entire syndicated term loan. In situations where this is not the case, the effective interest rate and interest expense may need to be calculated individually for each loan.





Example 3-12: Multiple changes to prepayable debt within a one-year period (Section 2.3.2.1 and Section 2.3.2.2)

Facts

Borrower and Lender entered into a debt agreement on June 30, 20X0, with the following terms:

- Principal amount is \$7 million
- Stated interest rate is 8%
- Principal is repayable in one lump sum on June 30, 20X5
- Interest is payable annually in arrears on June 30
- Term is five years
- There is no embedded conversion option

Lender charged Borrower a lender fee of \$150,000 and Borrower incurred \$75,000 in third-party debt issuance costs. The debt agreement indicates that prepayment is permitted. However, there is a requirement to pay a \$100,000 penalty upon prepayment.

Borrower has not elected to account for its debt using the fair value option. There are no other outstanding loans with Lender.

Borrower calculates an effective interest rate of 8.8% and applies the effective interest method (see Section 1.3) to recognize interest expense over the term of the debt. Borrower pays interest of \$560,000 on June 30, 20X1 and 20X2 (the latter prior to making changes to the debt on that date).

Changes to the debt on June 30, 20X2

Borrower and Lender make the following changes to the debt on June 30, 20X2:

- Extending the maturity date to June 30, 20X7
- Adding incremental borrowings of \$2 million (which increases the total principal amount to \$9 million)
- Increasing the prepayment penalty to \$200,000

Borrower must pay a \$250,000 fee to Lender as compensation for executing the changes to the debt. Borrower incurs \$100,000 of third-party costs with its lawyers related to making these changes to the debt. The changes to the debt do not trigger the prepayment penalty. Borrower is not experiencing financial difficulties (see Section 2.2.2.1).

Analysis of the changes to the debt on June 30, 20X2

Borrower first determines that the liability derecognition threshold has not been met because it has not been relieved of its obligation under the debt nor has it been legally released as the primary obligor under the debt.

Borrower next determines that the changes to the debt do not meet the definition of a TDR because it is not experiencing financial difficulties.

Assuming that the debt will be prepaid on June 30, 20X2, immediately before the changes to the debt (for the purpose of the preexisting debt's remaining cash flows) and immediately after the changes to the debt (for the purpose of the changed debt's cash flows), Borrower performs the 10% cash flow test and determines the percentage change in cash flows as of June 30, 20X2, as follows:

| Nature of cash flows | Original debt's remaining cash flows as of June 30, 20X2 | Changed debt's cash flows as of June 30, 20X2 |
|---|--|---|
| Principal repayment (Note 1) | \$7,000,000 | \$9,000,000 |
| Incremental borrowings (Note 1) | - | (2,000,000) |
| Lender fee (Note 2) | - | 250,000 |
| Interest payments (Note 3) | - | - |
| Prepayment penalty (Note 4) | 100,000 | 200,000 |
| Present value of the remaining cash flows (Notes 5 and 6) | \$7,100,000 | \$7,450,000 |
| Difference | | \$350,000 |
| % difference | | 4.9% |

Note 1: The principal repayment increased to \$9 million as a result of the \$2 million incremental borrowings that were included in the changes to the debt (which are also separately reflected as cash proceeds on the Incremental borrowings line in the test).

Note 2: The lender fee for the original debt is not included in the test because the test uses only the original debt's remaining cash flows.

Note 3: There are no interest payments reflected in this test because: (a) the modification was made on June 30, 20X2, (b) the interest payment made on June 30, 20X2, represents interest accrued through that date, and (c) Borrower is assuming that the debt is prepaid on June 30, 20X2. In other words, no incremental amount of interest would be due upon prepayment of the debt on June 30, 20X2.

Note 4: The prepayment penalty is included in this test because this example assumes that the debt is prepaid.

Note 5: No incremental present value calculations are needed when Borrower assumes the debt is prepaid on the date the changes are made to the debt.

Note 6: The third-party costs for the original debt and changed debt are not included in the test because the test should only reflect cash flows between the borrower and the lender (see [Section 2.3.2](#)).

Because the percentage change in cash flows is less than 10%, Borrower concludes that the changes to the debt on June 30, 20X2, should be accounted for as a modification (see [Section 2.3.2](#)). Borrower defers the lender fees, calculates a new effective interest rate of 9.1% (see [Section 1.3](#)) and will recognize interest expense using the effective interest method over the remaining term of the debt using that rate. Third-party costs of \$100,000 are expensed.

Changes to the debt on March 31, 20X3

Borrower and Lender make the following change to the debt on March 31, 20X3:

- Extending the maturity date of the debt to June 30, 20X9

Borrower must pay a \$250,000 fee to Lender as compensation for executing the change to the debt. Borrower also paid interest of \$540,000 ($\$9 \text{ million} \times 8\% \times [9 \text{ months} \div 12 \text{ months}]$) to Lender on March 31, 20X3. Borrower incurs \$100,000 of third-party costs with its lawyers related to making these changes to the debt. The changes to the debt do not trigger the prepayment penalty. Borrower is not experiencing financial difficulties.

Analysis of the changes to the debt on March 31, 20X3

Borrower first determines that the liability derecognition threshold has not been met because it has not been relieved of its obligation under the debt nor has it been legally released as the primary obligor under the debt.

Borrower next determines that the changes to the debt do not meet the definition of a TDR because it is not experiencing financial difficulties.



Because the changes made to the debt on March 31, 20X3, occurred within one year of the changes made to the debt on June 30, 20X2, and the changes made to the debt on June 30, 20X2, were accounted for as a modification, Borrower must analyze the changes made to the debt within the one-year period on a cumulative basis for the purpose of performing the 10% cash flow test and determining how to account for the additional changes made to the debt on March 31, 20X3 (see [Section 2.3.2.2](#)).

To analyze the changes to the debt on a cumulative basis, Borrower first performs the test assuming exercise of the prepayment option (see [Section 2.3.2.2](#)). The calculation of the original debt's remaining cash flows as of June 30, 20X2, remains consistent with the previous calculation at \$7.1 million. However, the calculation of the changed debt's cash flows as of June 30, 20X2, must now assume exercise of the prepayment option right after the last changes were made to the debt on March 31, 20X3 (rather than right after the first changes were made to the debt on June 30, 20X2). As a result, the present value of the payments made between June 30, 20X2, and March 31, 20X3, must also be determined as part of this calculation.

To determine the present value of the changed debt's cash flows, the following inputs in a present value software tool were used:

| | Changed debt's cash flows as of June 30, 20X2 (considering changes from both modifications) |
|--|---|
| Compounding period | Annual |
| Principal repayment (Note 1) | \$9 million on March 31, 20X3 |
| Incremental borrowings (Note 1) | \$2 million on June 30, 20X2 |
| Lender fees (Note 2) | \$250,000 on June 30, 20X2, and \$250,000 on March 31, 20X3 |
| Interest payments (Note 3) | \$540,000 on March 31, 20X3 |
| Prepayment penalty (Note 4) | \$200,000 on March 31, 20X3 |
| Discount rate (Note 5) | 8.8% |
| Present value of the remaining cash flows (Note 6) | \$7,620,952 |

Note 1: The principal repayment increased to \$9 million as a result of the \$2 million incremental borrowings that were included in the changes to the debt (which are also separately reflected as cash proceeds on the Incremental borrowings line in the test).

Note 2: The lender fee for the original debt is not included in the test because the test uses only the original debt's remaining cash flows. The lender fees for the changed debt reflects the lender fees of \$250,000 on June 30, 20X2, and March 31, 20X3.

Note 3: \$9 million principal amount x 8% stated interest rate from June 30, 20X2, through March 31, 20X3.

Note 4: The prepayment penalty reflected in the terms of the debt after the March 31, 20X3, changes is included in this test because this example assumes that the debt is prepaid on March 31, 20X3.

Note 5: [Section 2.3.2.2](#) states that in evaluating changes on a cumulative basis, the discount rate used is the effective interest rate of the debt right before the first changes were made to the debt in the one-year period on June 30, 20X2.

Note 6: The third-party costs for the original debt and changed debt are not included in the test because the test should only reflect cash flows between the borrower and the lender (see [Section 2.3.2](#)).

The net change in present value of the remaining cash flows on a cumulative basis is \$520,952 (\$7,620,952 - \$7,100,000) or 7.3%. As this is less than a 10% change in cash flows, Borrower accounts for the changes to the debt on March 31, 20X3, as a modification. Borrower defers the lender fees, calculates a new effective interest rate (see [Section 1.3](#)) after the changes to the debt on March 31, 20X3, and will recognize interest expense using the effective interest method over the remaining term of the debt using that rate. Third-party costs are expensed as incurred.





Example 3-13: Multiple changes to prepayable debt with a prepayment fee based on a percentage of principal within a one-year period ([Section 2.3.2.1](#) and [Section 2.3.2.2](#))

Facts

- Borrower and Lender entered into a debt agreement on June 30, 20X0, with the following terms:
- Principal amount is \$7 million
- Stated interest rate is 8%
- Principal is repayable in one lump sum on June 30, 20X5
- Interest is payable annually in arrears on June 30
- Term is five years
- There is no embedded conversion option

Lender charged Borrower a lender fee of \$150,000 and Borrower incurred \$75,000 in third-party debt issuance costs. The debt agreement indicates that prepayment is permitted. However, there is a requirement to pay a penalty of 3% of the outstanding principal upon prepayment.

Borrower has not elected to account for its debt using the fair value option. There are no other outstanding loans with Lender.

Borrower calculates an effective interest rate of 8.8% and will recognize interest expense using the effective interest method (see [Section 1.3](#)) over the term of the debt using that rate. Borrower pays interest of \$560,000 on June 30, 20X1 and 20X2 (the latter prior to making changes to the debt on that date).

Changes to the debt on June 30, 20X2

Borrower and Lender make the following changes to the debt on June 30, 20X2:

- Extending the maturity date to June 30, 20X7
- Adding incremental borrowings of \$2 million (which increases the total principal amount to \$9 million)

Borrower must pay a \$250,000 fee to Lender as compensation for executing the changes to the debt. Borrower incurs \$100,000 of third-party costs with its lawyers related to making these changes to the debt. The changes to the debt do not trigger the prepayment penalty. Borrower is not experiencing financial difficulties (see [Section 2.2.2.1](#)).

Analysis of the changes to the debt on June 30, 20X2

Borrower first determines that the liability derecognition threshold has not been met because it has not been relieved of its obligation under the debt nor has it been legally released as the primary obligor under the debt.

Borrower next determines that the changes to the debt do not meet the definition of a TDR because it is not experiencing financial difficulties.

Assuming that the debt will be prepaid on June 30, 20X2, immediately before the changes to the debt for the purpose of the preexisting debt's remaining cash flows and immediately after the changes to the debt for the purpose of the changed debt's cash flows, Borrower performs the 10% cash flow test and determines the percentage change in cash flows as of June 30, 20X2, as follows:

| Nature of cash flows | Original debt's remaining cash flows as of June 30, 20X2 | Changed debt's cash flows as of June 30, 20X2 |
|---|--|---|
| Principal repayment (Note 1) | \$7,000,000 | \$9,000,000 |
| Incremental borrowings (Note 1) | - | (2,000,000) |
| Lender fee (Note 2) | - | 250,000 |
| Interest payments (Note 3) | - | - |
| Prepayment penalty (Note 4) | 210,000 | 270,000 |
| Present value of the remaining cash flows (Notes 5 and 6) | \$7,210,000 | \$7,520,000 |
| Difference | | \$310,000 |
| % difference | | 4.3% |

Note 1: The principal repayment increased to \$9 million as a result of the \$2 million incremental borrowings that were included in the changes to the debt (which are also separately reflected as cash proceeds on the Incremental borrowings line in the test).

Note 2: The lender fee for the original debt is not included in the test because the test uses only the original debt's remaining cash flows.

Note 3: There are no interest payments reflected in this test because: (a) the modification was made on June 30, 20X2, (b) the interest payment made on June 30, 20X2, represents interest accrued through that date, and (c) Borrower is assuming that the debt is prepaid on June 30, 20X2. In other words, no incremental amount of interest would be due upon prepayment of the debt on June 30, 20X2.

Note 4: The prepayment penalty is included in this test because this example assumes that the debt is prepaid. The penalty was calculated based on 3% of the outstanding principal.

Note 5: No incremental present value calculations are needed when Borrower assumes the debt is prepaid on the date the changes are made to the debt.

Note 6: The third-party costs for the original debt and changed debt are not included in the test because the test should only reflect cash flows between the borrower and the lender (see [Section 2.3.2](#)).

Because the percentage change in cash flows is less than 10%, Borrower concludes that the changes to the debt on June 30, 20X2, should be accounted for as a modification (see [Section 2.3.2](#)). Borrower defers the lender fees, calculates a new effective interest rate of 9.1% (see [Section 1.3](#)) and will recognize interest expense using the effective interest method over the remaining term of the debt using that rate. Third-party costs are expensed as incurred.

Changes to the debt on March 31, 20X3

Borrower and Lender make the following changes to the debt on March 31, 20X3:

- Extending the maturity date of the debt to June 30, 20X9
- Adding incremental borrowings of \$15 million (which increases the total principal amount to \$24 million)

Borrower must pay a \$250,000 fee to Lender as compensation for executing the changes to the debt. Borrower also paid interest of \$540,000 ($\$9 \text{ million} \times 8\% \times [9 \text{ months} \div 12 \text{ months}]$) to Lender on March 31, 20X3. Borrower incurs \$100,000 of third-party costs with its lawyers related to making these changes to the debt. The changes to the debt do not trigger the prepayment penalty. Borrower is not experiencing financial difficulties.

Analysis of the changes to the debt on March 31, 20X3

Borrower first determines that the liability derecognition threshold has not been met because it has not been relieved of its obligation under the debt nor has it been legally released as the primary obligor under the debt.



Borrower next determines that the changes to the debt do not meet the definition of a TDR because it is not experiencing financial difficulties.

Because the changes made to the debt on March 31, 20X3, occurred within one year of the changes made to the debt on June 30, 20X2, and the changes made to the debt on June 30, 20X2, were accounted for as a modification, Borrower must analyze the changes made to the debt within the one-year period on a cumulative basis for the purpose of performing the 10% cash flow test and determining how to account for the additional changes made to the debt on March 31, 20X3 (see [Section 2.3.2.2](#)).

To analyze the changes to the debt on a cumulative basis, Borrower first performs the test assuming exercise of the prepayment option (see [Section 2.3.2.2](#)). The calculation of the original debt's remaining cash flows as of June 30, 20X2, remains consistent with the previous calculation at \$7,210,000. However, the calculation of the changed debt's cash flows as of June 30, 20X2, must now assume exercise of the prepayment option right after the last changes were made to the debt on March 31, 20X3 (rather than right after the first changes were made to the debt on June 30, 20X2). As a result, the present value of the payments made between June 30, 20X2, and March 31, 20X3, must also be determined as part of this calculation. To determine the present value of the changed debt's cash flows, the following inputs in a present value software tool were used:

| | Changed debt's cash flows as of June 30, 20X2 (considering changes from both modifications) |
|--|---|
| Compounding period | Annual |
| Principal repayment (Note 1) | \$24 million on March 31, 20X3 |
| Incremental borrowings (Note 1) | \$2 million on June 30, 20X2, and \$15 million on March 31, 20X3 |
| Lender fees (Note 2) | \$250,000 on June 30, 20X2, and \$250,000 on March 31, 20X3 |
| Interest payments (Note 3) | \$540,000 on March 31, 20X3 |
| Prepayment penalty (Note 4) | \$720,000 on March 31, 20X3 |
| Discount rate (Note 5) | 8.8% |
| Present value of the remaining cash flows (Note 6) | \$8,108,730 |

Note 1: The principal repayment increased to \$24 million as a result of the \$17 million incremental borrowings that were included in the changes to the debt (which are also separately reflected as cash proceeds on the Incremental borrowings line in the test).

Note 2: The lender fee for the original debt is not included in the test because the test uses only the original debt's remaining cash flows. The lender fees for the changed debt reflects the lender fees of \$250,000 on June 30, 20X2, and March 31, 20X3.

Note 3: \$9 million principal amount as of June 30, 20X2 x 8% stated interest rate through March 31, 20X3.

Note 4: The prepayment penalty reflected in the terms of the debt after the March 31, 20X3, change is included in this 10% cash flow test (3% of the outstanding principal of \$24 million) because this example assumes the debt is prepaid on March 31, 20X3.

Note 5: [Section 2.3.2.2](#) states that in evaluating changes on a cumulative basis, the discount rate used is the effective interest rate of the debt right before the first changes were made to the debt in the one-year period on June 30, 20X2.

Note 6: The third-party costs for the original debt and changed debt are not included in the test because the test should only reflect cash flows between the borrower and the lender (see [Section 2.3.2](#)).



The net change in present value of the remaining cash flows on a cumulative basis is \$898,730 (\$8,108,730 - \$7,210,000) or 12.5% when exercise of the prepayment option is assumed. As the percentage change under this assumption is more than 10%, Borrower must also perform the test assuming the prepayment option is not exercised. The inputs used in a present value tool and the results are as follows:

| | Original debt's remaining cash flows as of June 30, 20X2 (Note 1) | Changed debt's cash flows as of June 30, 20X2 (considering changes from both modifications) (Note 1) |
|---|---|---|
| Compounding period | Annual | Annual |
| Principal repayment | \$7 million on June 30, 20X5 | \$24 million on June 30, 20X9 |
| Incremental borrowings | N/A | \$2 million on June 30, 20X2, and \$15 million on March 31, 20X3 |
| Lender fees (Note 2) | N/A | \$250,000 on June 30, 20X2, \$250,000 on March 31, 20X3 |
| Interest payments | \$560,000 on June 30, 20X3, 20X4 and 20X5 (Note 3) | \$1,020,000 payable on June 30, 20X3, and then \$1,920,000 per year starting on June 30, 20X4, and ending on June 30, 20X9 (Note 4) |
| Discount rate (Note 5) | 8.8% | 8.8% |
| Present value of the remaining cash flows | \$6,853,786 | \$6,584,424 |
| Difference | | \$269,362 |
| % difference | | 3.9% |

Note 1: The third-party costs for the original debt and changed debt are not included in the test because the test should only reflect cash flows between the borrower and the lender.

Note 2: The lender fee for the original debt is not included in the test because the test uses only the original debt's remaining cash flows. The lender fees for the changed debt reflects the lender fees of \$250,000 on June 30, 20X2, and on March 31, 20X3.

Note 3: \$7 million principal amount × 8% stated interest rate.

Note 4: \$9 million principal amount × 8% stated interest rate through March 31, 20X3, and \$24 million principal amount as of March 31, 20X3 × 8% stated interest rate through June 30, 20X9. Since interest is paid annually, the payment on June 30, 20X3, consists of the accrued and unpaid interest as of March 31, 20X3, plus the interest accrued from April 1 through June 30, 20X3.

Note 5: [Section 2.3.2.2](#) states that in evaluating changes on a cumulative basis, the discount rate used is the effective interest rate of the debt right before the first changes were made to the debt in the one-year period on June 30, 20X2.

The net change in present value of the remaining cash flows on a cumulative basis is \$269,362 or 3.9% when assuming the prepayment option is not exercised. As this is less than a 10% change in cash flows in one of the two calculations (i.e., with and without exercise of the prepayment option), Borrower accounts for the changes to the debt on March 31, 20X3, as a modification. Borrower defers the lender fees, calculates a new effective interest rate (see [Section 1.3](#)) after the changes to the debt on March 31, 20X3, and will recognize interest expense using the effective interest method over the remaining term of the debt using that rate. Third-party costs are expensed as incurred.





Example 3-14: Line-of-credit arrangement modification with decrease in borrowing capacity (Section 2.4)

Facts

On January 1, 20X1, Borrower obtains a line-of-credit (LOC) arrangement from Lender. The LOC's term is three years and the amount available under the LOC (i.e., the commitment amount) is \$30 million. For simplicity, fees for maintaining the LOC and the interest rate paid on amounts borrowed under the LOC are ignored. Borrower incurs \$180,000 of costs (e.g., lender's fee and legal costs) in connection with initiating the LOC and recognizes these costs as an asset on the balance sheet (see Section 2.4). These costs will be amortized over the term of the LOC (i.e., three years).

On January 1, 20X2, Borrower and Lender agree to modify the LOC. The term of the LOC is changed to three years from the date of the modification (i.e., the term was extended one year) and the amount available under the LOC is reduced to \$15 million from \$30 million. To execute this change, Borrower paid Lender a fee of \$100,000 and incurred third-party costs with its lawyers of \$40,000. Borrower is not experiencing financial difficulties.

On January 1, 20X2 (when Borrower and Lender agree to modify the LOC), there are \$120,000 of unamortized deferred costs related to the old LOC. Borrower must determine how it should account for those remaining deferred costs upon modification of the LOC. In addition, Borrower must determine how it should account for the costs incurred to execute the changes to the LOC (\$140,000 in lender's fees and third-party legal costs).

Analysis

Borrower first determines that the liability derecognition threshold has not been met because it has not been relieved of its obligation under the LOC nor has it been legally released as the primary obligor under the LOC.

Borrower next determines that the changes to the LOC do not meet the definition of a TDR because it is not experiencing financial difficulties (see Section 2.2.2.1).

Lastly, Borrower considers whether the borrowing capacity of the LOC increased or decreased.

The borrowing capacity (see Section 2.4) of the old LOC is \$60 million (\$30 million commitment amount \times 2-year remaining term). The borrowing capacity of the new LOC is \$45 million (\$15 million commitment amount \times 3-year term). The borrowing capacity under the LOC decreased by \$15 million (or 25%) as a result of the changes agreed to by Borrower and Lender on January 1, 20X2. The unamortized deferred costs related to the old LOC should be written off in proportion to the decrease in the LOC's borrowing capacity. As such, Borrower should write off \$30,000 (or 25%) of the \$120,000 of unamortized deferred costs related to the old LOC. Borrower defers and amortizes over three years (the term of the new LOC) the remaining amount of the unamortized deferred costs (\$90,000), as well as the costs incurred to execute the changes to the LOC (i.e., \$140,000 in lender's fees and third-party legal costs).

The following represents the journal entry that Borrower records on January 1, 20X2, to account for the unamortized deferred costs related to the old LOC and the costs incurred to execute the changes to the LOC:

| | Debit | Credit |
|--|-----------|-----------|
| Deferred costs – Line of credit (Note 1) | \$110,000 | |
| Interest expense (portion of unamortized deferred costs written off) | 30,000 | |
| Cash | | \$140,000 |

Note 1: \$140,000 of additional deferred costs related to changing the LOC – \$30,000 of preexisting unamortized deferred costs written off due to the decrease in borrowing capacity



After recording this entry, Borrower has unamortized deferred costs on its balance sheet related to the LOC in the amount of \$230,000 (\$90,000 of remaining unamortized deferred costs from the original LOC and \$140,000 of deferred costs related to changing the LOC).

Commentary

It is important to note in this example that Borrower appropriately applied the accounting guidance in determining that the borrowing capacity decreased by 25%. If Borrower had made its determination based on the decrease in the commitment amount (\$30 million decreased to \$15 million), it would have inappropriately concluded that \$60,000 of the preexisting unamortized deferred costs related to the old LOC should have been written off ($\$120,000$ unamortized deferred costs \times 50% decrease in the commitment amount) instead of the correct amount of \$30,000.



Example 3-15: Line-of-credit arrangement modification with increase in borrowing capacity (Section 2.4)

Facts

On January 1, 20X1, Borrower obtains a LOC arrangement from Lender. The LOC's term is three years and the amount available under the LOC (i.e., the commitment amount) is \$30 million. Borrower incurs \$180,000 of costs (e.g., lender's fee and legal costs) in connection with initiating the LOC and recognizes these costs as an asset on the balance sheet. These costs will be amortized over the term of the LOC (i.e., three years).

On January 1, 20X2, Borrower and Lender agree to modify the LOC. The term of the LOC is changed to three years from the date of the modification (i.e., the term was extended one year) and the amount available under the LOC is reduced to \$24 million from \$30 million. To execute this change, Borrower paid Lender a fee of \$100,000 and incurred third-party costs with its lawyers of \$40,000. Borrower is not experiencing financial difficulties (see Section 2.2.2.1).

On January 1, 20X2 (when Borrower and Lender agree to modify the LOC), there are \$120,000 of unamortized deferred costs related to the old LOC. Borrower must determine how it should account for those remaining deferred costs upon modification of the LOC. In addition, Borrower must determine how it should account for the costs incurred to execute the changes to the LOC (\$140,000 in lender's fees and third-party legal costs).

Analysis

Borrower first determines that the liability derecognition threshold has not been met because it has not been relieved of its obligation under the LOC nor has it been legally released as the primary obligor under the LOC.

Borrower next determines that the changes to the LOC do not meet the definition of a TDR because it is not experiencing financial difficulties.

Lastly, Borrower considers whether the borrowing capacity of the LOC increased or decreased.

The borrowing capacity of the old LOC is \$60 million ($\30 million commitment amount \times 2-year remaining term). The borrowing capacity of the new LOC is \$72 million ($\24 million commitment amount \times 3-year term). The borrowing capacity under the LOC increased by 20% as a result of the changes agreed to by Borrower and Lender on January 1, 20X2. As such, the unamortized deferred costs related to the old LOC are left on Borrower's balance sheet and amortized over the 3-year term of the new LOC (see Section 2.4). In addition, Borrower also defers and amortizes the costs incurred to execute the changes to the LOC (i.e., \$140,000 in lender's fees and third-party legal costs) over the three-year term of the new LOC.

The following represents the journal entry Borrower records on January 1, 20X2, to account for the costs incurred to execute the changes to the LOC:

| | Debit | Credit |
|---------------------------------|-----------|-----------|
| Deferred costs – Line of credit | \$140,000 | |
| Cash | | \$140,000 |

After recording this entry, Borrower has unamortized deferred costs on its balance sheet related to the LOC in the amount of \$260,000 (\$120,000 of remaining unamortized deferred costs from the original LOC + \$140,000 of deferred costs related to changing the LOC).

Commentary

It is important to note in this example that Borrower appropriately applied the accounting guidance in determining that the borrowing capacity increased by 20%. If Borrower had incorrectly made its determination based on the decrease in the commitment amount (\$30 million decreased to \$24 million), it would have inappropriately concluded that \$24,000 of the preexisting unamortized deferred costs related to the old LOC should have been written off ($\$120,000 \text{ unamortized deferred costs} \times 20\% \text{ decrease in the commitment amount}$) instead of none (the correct amount).



Appendix A: Acronyms, literature and technical accounting guide and whitepaper references

Many acronyms are used throughout this guide and numerous references are made to specific topics and subtopics in the ASC. Provided in this appendix are: (a) an acronym legend, which lists the acronyms used throughout this guide and their corresponding definitions; (b) a literature listing, which lists the topics and subtopics referred to throughout this guide and the corresponding titles; and (c) a listing of our other technical accounting guides and whitepapers referred to throughout this guide.

Acronym legend

| Acronym | Definition |
|---------|--|
| ASC | FASB Accounting Standards Codification |
| ASU | Accounting Standards Update |
| DDTL | Delayed-draw term loan |
| FASB | Financial Accounting Standards Board |
| GAAP | Generally Accepted Accounting Principles |
| IASB | International Accounting Standards Board |
| IFRS | International Financial Reporting Standard |
| LIBOR | London Interbank Offered Rate |
| LOC | Line of credit |
| SEC | Securities and Exchange Commission |
| SOFR | Secured Overnight Financing Rate |
| TDR | Troubled Debt Restructuring |

Literature Listing

| ASC topic or subtopic | Title |
|-----------------------|--|
| 220-40 | Income Statement – Reporting Comprehensive Income – Expense Disaggregation Disclosures |
| 360-10 | Property, Plant, and Equipment – Overall |
| 405-20 | Liabilities – Extinguishment of Liabilities |
| 460-10 | Guarantees – Overall |
| 470 | Debt |
| 470-10 | Debt – Overall |
| 470-20 | Debt – Debt with Conversion and Other Options |
| 470-50 | Debt – Modifications and Extinguishments |
| 470-60 | Debt – Troubled Debt Restructurings by Debtors |
| 505-10 | Equity – Overall |
| 815-15 | Derivatives and Hedging – Embedded Derivatives |
| 820 | Fair Value Measurement |
| 820-10 | Fair Value Measurement – Overall |
| 825-10 | Financial Instruments – Overall |
| 835-30 | Interest – Imputation of Interest |



| ASC topic or subtopic | Title |
|-----------------------|--------|
| 842 | Leases |

| Abbreviation used herein | Responsible party | Title |
|---------------------------|-------------------|---|
| ASU 2024-03 | FASB | Income Statement – Reporting Comprehensive Income – Expense Disaggregation Disclosures (Subtopic 220-40): Disaggregation of Income Statement Expenses |
| ASU 2024-04 | FASB | Debt – Debt with Conversion and Other Options (Subtopic 470-20): Induced Conversions of Convertible Debt Instruments |
| ASU 2025-12 | FASB | Codification Improvements |
| Regulation S-X, Rule 4.08 | SEC | General notes to financial statements |
| Regulation S-X, Rule 5.02 | SEC | Balance sheets |

RSM technical accounting guides and whitepapers

| Abbreviation used herein | Title |
|--|---|
| Our debt and equity guide | A guide to accounting for debt and equity instruments in financing transactions |
| Our financial assets guide | A guide to accounting for investments, loans and other receivables |
| Our lease accounting guide | A guide to lease accounting |
| Our debt classification whitepaper | Fundamentals of debt classification |
| Our bankruptcy whitepaper | Accounting for bankruptcies |
| Our U.S. GAAP to IFRS Comparisons compendium | U.S. GAAP to IFRS comparisons |

For a complete listing of our technical accounting guides and access to all of our financial reporting thought leadership, click [here](#).



Appendix B: Definitions

Several terms with specific meaning are used throughout this guide. Those terms and the corresponding definitions based on the Master Glossary of the Codification are provided in the table that follows.

| Term | Definition |
|-------------------------|--|
| Affiliate | A party that, directly or indirectly through one or more intermediaries, controls, is controlled by, or is under common control with an entity. See Control. |
| Amortized Cost Basis | The amortized cost basis is the amount at which a financing receivable or investment is originated or acquired, adjusted for applicable accrued interest, accretion, or amortization of premium, discount, and net deferred fees or costs, collection of cash, writeoffs, foreign exchange, and fair value hedge accounting adjustments. |
| Carrying Amount | For a payable, the face amount increased or decreased by applicable accrued interest and applicable unamortized premium, discount, finance charges, or issue costs. |
| Contract | An agreement between two or more parties that creates enforceable rights and obligations. |
| Control | The possession, direct or indirect, of the power to direct or cause the direction of the management and policies of an entity through ownership, by contract, or otherwise. |
| Discount | The difference between the net proceeds, after expense, received upon issuance of debt and the amount repayable at its maturity. |
| Fair Value | The price that would be received to sell an asset or paid to transfer a liability in an orderly transaction between market participants at the measurement date. |
| In-Substance Defeasance | Placement by the debtor of amounts equal to the principal, interest, and prepayment penalties related to a debt instrument in an irrevocable trust established for the benefit of the creditor. |
| Interest Method | The method used to arrive at a periodic interest cost (including amortization) that will represent a level effective rate on the sum of the face amount of the debt and (plus or minus) the unamortized premium or discount and expense at the beginning of each period. |
| Lease | A contract, or part of a contract, that conveys the right to control the use of identified property, plant, or equipment (an identified asset) for a period of time in exchange for consideration. |
| Lease Modification | A change to the terms and conditions of a contract that results in a change in the scope of or the consideration for a lease (for example, a change to the terms and conditions of the contract that adds or terminates the right to use one or more underlying assets or extends or shortens the contractual lease term). |



| Term | Definition |
|-----------------------------|---|
| Line-of-Credit Arrangement | A line-of-credit or revolving-debt arrangement is an agreement that provides the borrower with the option to make multiple borrowings up to a specified maximum amount, to repay portions of previous borrowings, and to then reborrow under the same contract. Line-of-credit and revolving-debt arrangements may include both amounts drawn by the debtor (a debt instrument) and a commitment by the creditor to make additional amounts available to the debtor under predefined terms (a loan commitment). |
| Loan Participation | A transaction in which a single lender makes a large loan to a borrower and subsequently transfers undivided interests in the loan to groups of banks or other entities. |
| Loan Syndication | A transaction in which several lenders share in lending to a single borrower. Each lender loans a specific amount to the borrower and has the right to repayment from the borrower. It is common for groups of lenders to jointly fund those loans when the amount borrowed is greater than any one lender is willing to lend. |
| Management | Persons who are responsible for achieving the objectives of the entity and who have the authority to establish policies and make decisions by which those objectives are to be pursued. Management normally includes members of the board of directors, the chief executive officer, chief operating officer, vice presidents in charge of principal business functions (such as sales, administration, or finance), and other persons who perform similar policy making functions. Persons without formal titles also may be members of management. |
| Market Participants | Buyers and sellers in the principal (or most advantageous) market for the asset or liability that have all of the following characteristics: <ul style="list-style-type: none"> a. They are independent of each other, that is, they are not related parties, although the price in a related party transaction may be used as an input to a fair value measurement if the reporting entity has evidence that the transaction was entered into at market terms b. They are knowledgeable, having a reasonable understanding about the asset or liability and the transaction using all available information, including information that might be obtained through due diligence efforts that are usual and customary c. They are able to enter into a transaction for the asset or liability d. They are willing to enter into a transaction for the asset or liability, that is, they are motivated but not forced or otherwise compelled to do so. |
| Net Carrying Amount of Debt | Net carrying amount of debt is the amount due at maturity, adjusted for unamortized premium, discount, and cost of issuance. |
| Orderly Transaction | A transaction that assumes exposure to the market for a period before the measurement date to allow for marketing activities that are usual and customary for transactions involving such assets or liabilities; it is not a forced transaction (for example, a forced liquidation or distress sale). |
| Premium | The excess of the net proceeds, after expense, received upon issuance of debt over the amount repayable at its maturity. |



| Term | Definition |
|-----------------------------|--|
| Public Debt Issuance | A public debt issuance occurs when a debtor issues a number of identical debt instruments to an underwriter that sells the debt instruments (in the form of securities) to various investors. |
| Reacquisition Price of Debt | The amount paid on extinguishment, including a call premium and miscellaneous costs of reacquisition. If extinguishment is achieved by a direct exchange of new securities, the reacquisition price is the total present value of the new securities. |
| Related Parties | <p>Related parties include:</p> <ol style="list-style-type: none"> a. Affiliates of the entity b. Entities for which investments in their equity securities would be required, absent the election of the fair value option under the Fair Value Option Subsection of Section 825-10-15, to be accounted for by the equity method by the investing entity c. Trusts for the benefit of employees, such as pension and profit-sharing trusts that are managed by or under the trusteeship of management d. Principal owners of the entity and members of their immediate families e. Management of the entity and members of their immediate families f. Other parties with which the entity may deal if one party controls or can significantly influence the management or operating policies of the other to an extent that one of the transacting parties might be prevented from fully pursuing its own separate interests g. Other parties that can significantly influence the management or operating policies of the transacting parties or that have an ownership interest in one of the transacting parties and can significantly influence the other to an extent that one or more of the transacting parties might be prevented from fully pursuing its own separate interests. |
| Time of Restructuring | Troubled debt restructurings may occur before, at, or after the stated maturity of debt, and time may elapse between the agreement, court order, and so forth, and the transfer of assets or equity interest, the effective date of new terms, or the occurrence of another event that constitutes consummation of the restructuring. The date of consummation is the time of the restructuring. |
| Troubled Debt Restructuring | A restructuring of a debt constitutes a troubled debt restructuring if the creditor for economic or legal reasons related to the debtor's financial difficulties grants a concession to the debtor that it would not otherwise consider. |



Appendix C: Summary of significant changes since last edition

The following list summarizes the significant changes to this guide since our last edition:

Chapter 2 – Relevant literature and general concepts

- [Section 2.2.4.5](#) and [Section 2.3.3.1](#) were updated to add reference to remarks at the 2010 AICPA National Conference on Current SEC and PCAOB Developments that clarify the accounting treatment for a gain when the lender also holds an equity investment in the borrower.
- [Section 2.3.2](#) and [Section 2.3.7](#) were updated for the current status of the FASB's technical agenda project, *Accounting for Debt Exchanges*.
- Section 2.3.2.4, which discussed reference rate reform, was removed due to the sunsetting of the guidance in ASC 848 as of December 31, 2024.

Appendices

- [Appendix A](#) was updated for the issuance of ASU 2024-03 and ASU 2025-12 and to remove reference to ASU 2020-04, ASU 2020-06 and 2022-06 which are fully effective.

A GUIDE TO ACCOUNTING FOR DEBT MODIFICATIONS AND RESTRUCTURINGS

This edition of A Guide to Accounting for Debt Modifications and Restructurings has been produced by the National Professional Standards Group of RSM US LLP.

June 2026

+1 800 274 3978
rsmus.com

This document contains general information, may be based on authorities that are subject to change, and is not a substitute for professional advice or services. This document does not constitute audit, tax, consulting, business, financial, investment, legal or other professional advice, and you should consult a qualified professional advisor before taking any action based on the information herein. RSM US LLP, its affiliates and related entities are not responsible for any loss resulting from or relating to reliance on this document by any person. Internal Revenue Service rules require us to inform you that this communication may be deemed a solicitation to provide tax services. This communication is being sent to individuals who have subscribed to receive it or who we believe would have an interest in the topics discussed.

RSM US LLP is a limited liability partnership and the U.S. member firm of RSM International, a global network of independent audit, tax and consulting firms. The member firms of RSM International collaborate to provide services to global clients, but are separate and distinct legal entities that cannot obligate each other. Each member firm is responsible only for its own acts and omissions, and not those of any other party. Visit rsmus.com/aboutus for more information regarding RSM US LLP and RSM International.

RSM, the RSM logo and *the power of being understood* are registered trademarks of RSM International Association.

© 2026 RSM US LLP. All Rights Reserved.

